PRELIMINARY MAJOR LAND DEVELOPMENT PLANS WATER GAP WELLNESS RECREATION CENTER

WATER GAP ACQUISITIONS PARTNERS, LLC SMITHFIELD TOWNSHIP MONROE COUNTY, PA

> AUGUST 26, 2024 LAST REVISED NOVEMBER 25, 2024

Plans Prepared by:



- **2**72.200.2050
- barryisett.com

525 Main Street, Suite 200 Stroudsburg, PA 18360

WAIVERS REQUESTED

THE FOLLOWING WAIVERS ARE BEING REQUESTED FROM THE SMITHFIELD TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE:

- I. SALDO SECTIONS 22-1301.6.B.(4) OUTLET STRUCTURES
- 3. SALDO SECTIONS 22-1301.7.L.(1) OUTLET PIPES SHALL BE RCP
- 4. SALDO SECTIONS 22-1301.7.Q.(2) STORM PIPES SHALL BE 18 INCHES
- 5. SALDO SECTIONS 22-603.1.D.(1) COMPLETE OUTLINE SURVEY OF PROPERTY
- 6. SALDO SECTIONS 22-603.1.D.(7) MONUMENTATION

2. SALDO SECTIONS 22-1301.6.B.(5) - OUTLET BOX

SITE DATA

OWNER/DEVELOPER: WATER GAP ACQUISITIONS PARTNERS, LLC

P.O. BOX 244 DELAWARE WATER GAP, PA 18327

WATER GAP WELLNESS SITE ADDRESS:

> 296 MOUNTAIN ROAD STROUDSBURG, PA 18360

PHONE: 203-524-3039

D.B.V. 2418, PG. 6739 DEED BOOK: TAX MAP: 16-9-1-26 16731000755147

NUMBER OF LOTS: ONE (1) TOTAL AREA: 68.35 AC. SEWER: ON-SITE

ON-SITE

BENCHMARK (BM)

WATER:

IRON PIN LOCATED APPROXIMATELY 53.4 FEET FROM THE SOUTHEAST CORNER OF THE EXISTING GARAGE AND APPROXIMATELY 20.6 FEET FROM THE LIGHT STANDARD LOCATED ALONG THE SOUTHERN PORTION OF THE PROPERTY WHERE THE PRIVATE DRIVEWAY ENDS AND THE GRAVEL LANE BEGINS. ELEVATION: 555.39 NAD83 DATUM.

ZONING DATA

ZONING DISTRICT: R-1: LOW DENSITY RESIDENTIAL ON-SITE SEWER AND WATER

PROPOSED BUILDING FOR PRIVATE RESORT, CONFERENCE CENTER AND INN MINIMUM LOT AREA: 50,000 SF

MINIMUM LOT WIDTH: 150 FEET MINIMUM LOT DEPTH: 200 FEET MINIMUM YARDS (BUILDING SETBACKS): FRONT: 35 FEET

REAR: 25 FEET SIDE: 30 FEET MAX. BUILDING LOT COVERAGE: 20% BUILDING HEIGHT: 35 FEET MAX. IMPERVIOUS COVERAGE:

EXISTING BUILDINGS COVERAGE 1.43% PROPOSED BUILDINGS COVERAGE 1.78% PROPOSED IMPERVIOUS COVERAGE 6.50% SMITHFIELD TWP PROPERTY AREA 51.29 AC.

ONING DATA PROVIDED IS BASED ON AN INTERPRETATION OF THE ZONING ORDINANCE BY THE PLAN PREPARER AND IS SUBJECT TO CONFIRMATION BY THE APPROPRIATE MUNICIPAL OFFICIAL.

GENERAL NOTES

1. CONTRACTOR SHALL NOTIFY THE PENNSYLVANIA ONE-CALL SYSTEM NO LESS THAN THREE DAYS AND NO GREATER THAN TEN DAYS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

2. CONTRACTOR SHALL VERIFY THE LOCATIONS AND ELEVATIONS OF ALL EXISTING UTILITIES AND

- 3. THE CONTRACTOR SHALL CONDUCT EXPLORATORY EXCAVATIONS AND LOCATE EXISTING UNDERGROUND UTILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS IF
- NECESSARY. CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF ANY DISCREPANCIES IN UTILITY LINE LOCATIONS ARE FOUND. . CONTRACTOR SHALL COORDINATE ALL WORK PERFORMED WITH THE APPROPRIATE UTILITY
- COMPANY OR AUTHORITY AND WITH ALL UTILITIES TO ENSURE ALL UTILITY SERVICES SERVE ALL UTILITY CUSTOMERS FOR CONTINUOUS FACILITY OPERATIONS OF ALL UTILITY CUSTOMERS. CONTRACTOR SHALL REWORK ALL UTILITY SERVICES INCLUDING PROVIDING TEMPORARY UTILITY SERVICES UNTIL PERMANENT UTILITY SERVICES ARE PROVIDED.
- 5. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO PUBLIC/PRIVATE PROPERTY AS A RESULT OF CONSTRUCTION ACTIVITIES.
- 6. CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS.
- 8. SITE SAFETY AND MAINTENANCE IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 9. CONTRACTOR IS RESPONSIBLE TO KEEP EXISTING ROADWAYS, PARKING AREAS AND LOCAL ROADS FREE OF CONSTRUCTION MATERIALS. ANY DIRT OR DEBRIS TRACKED ON TO SUCH AREAS WILL BE

7. CONTRACTOR SHALL ENSURE THE SAFETY OF THE GENERAL PUBLIC, EXISTING STRUCTURES, AND

- 10. THE CONTRACTOR IS RESPONSIBLE FOR BACKFILLING ALL TRENCHES, FENCING OFF CONSTRUCTION REAS AND REMOVING UNSUITABLE MATERIAL AND DEBRIS FROM THE CONSTRUCTION SITE.
- 11. CONSTRUCTION CREWS, VEHICLES AND ACTIVITIES SHALL NOT INTERFERE WITH NORMAL OPERATIONS OF THE FACILITY. DESIGNATED PARKING AREAS SHALL BE ESTABLISHED AND USED
- 12. CONSTRUCTION VEHICLES, MATERIALS OR ACTIVITIES SHALL NOT INTERFERE WITH PUBLIC ACCESS EXCEPT WHERE SHOWN ON THE PLANS. CONTROL VEHICULAR PARKING TO PREVENT INTERFERENCE WITH PUBLIC TRAFFIC AND PARKING, ACCESS BY EMERGENCY VEHICLES, AND OWNER'S
- 13. PREVENT PARKING ON OR ADJACENT TO ACCESS ROADS OR IN NON-DESIGNATED AREAS. 14. THE CONTRACTOR SHALL REMOVE ALL DEBRIS AND FLUSH OUT EXISTING AND PROPOSED STORM SEWER SYSTEMS WITHIN THE PROJECT AREA UPON COMPLETION OF CONSTRUCTION.
- 15. TRANSPORT, HANDLE, STORE AND PROTECT PRODUCTS IN ACCORDANCE WITH MANUFACTURER'S
- 16. PROTECT TREES, PLANT GROWTH, AND FEATURES DESIGNATED TO REMAIN, AS FINAL
- 17. PROTECT BENCH MARKS, (SURVEY CONTROL POINTS, AND EXISTING STRUCTURES) FROM DAMAGE OR DISPLACEMENT. CONTRACTOR TO REPLACE BENCHMARKS DISTURBED.


18. STAGING AND STOCKPILE AREAS WILL BE LIMITED TO ONLY THE AREAS NOTED ON THE PLANS.

STOCKPILING OF MATERIALS ON RIVERSIDE OF LEVEE OR SHEETPILING SHALL BE AT THE

- CONTRACTORS RISK. ANY LOSS OF MATERIAL SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. STOCKPILE IN SUFFICIENT QUANTITIES TO MEET PROJECT SCHEDULE AND REQUIREMENTS. 19. SEPARATE DIFFERING MATERIALS WITH DIVIDERS OR STOCKPILE APART TO PREVENT MIXING.
- 20. DIRECT SURFACE WATER AWAY FROM STOCKPILE SITE SO AS TO PREVENT EROSION OR DETERIORATION OF MATERIALS.
- 21. ALL ACTIVITIES SHALL REMAIN WITH THE AREA DESIGNATED THE "LIMIT OF DISTURBANCE" AS SHOWN ON THE EROSION AND SEDIMENT POLLUTION CONTROL PLANS. 22. THE CONTRACTORS WORKING ON THIS PROJECT SHALL BE RESPONSIBLE FOR ENSURING THAT ALL CONSTRUCTION ACTIVITIES RELATED TO THIS PROJECT ARE PERFORMED IN ACCORDANCE WITH ALL

O.S.H.A. (OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION) STANDARDS AND REQUIREMENTS.

- 23. IN ALL CASES, WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTOR SHALL NOT USE SCALED DIMENSIONS FOR CONSTRUCTION WITHOUT CONFIRMATION BY ENGINEER. CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS ON THE PROJECT SITE. ENGINEER MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN ON THESE DRAWINGS.
- 24. AS-BUILT PLANS SHALL BE PROVIDED TO THE TOWNSHIP AFTER CONSTRUCTION IS COMPLETE



Location Map USGS: STROUDSBURG QUADRANGLE SCALE: 1"=2000'

PLAN DESIGNATION	PLAN TITLE	PLAN NO.	LAST RE
* CS-1	COVER SHEET	1 of 27	11/25/20
SCM-1	SITE CONTEXT MAP	2 of 27	11/25/20
* SP-1	SITE DEVELOPMENT PLAN	3 of 27	11/25/20
* SP-2	SITE DEVELOPMENT PLAN	4 of 27	11/25/20
MER-1	MASTER EXISTING RESOURCES & SITE ANALYSIS PLAN	5 of 27	11/25/20
ER-1	EXISTING RESOURCES & SITE ANALYSIS PLAN	6 of 27	11/25/20
ER-2	EXISTING RESOURCES & SITE ANALYSIS PLAN	7 of 27	11/25/20
ER-3	EXISTING RESOURCES & SITE ANALYSIS PLAN	8 of 27	11/25/20
GP-1	GRADING PLAN	9 of 27	11/25/20
GP-2	GRADING PLAN	10 of 27	11/25/20
UP-1	UTILITY PLAN	11 of 27	11/25/20
UP-2	UTILITY PLAN	12 of 27	11/25/20
PP-1	STORM SEWER PLAN & PROFILES	13 of 27	11/25/20
PP-2	STORM SEWER PLAN & PROFILES	14 of 27	11/25/20
PP-3	STORM SEWER PLAN & PROFILES	15 of 27	11/25/20
PP-4	PLAN & PROFILES	16 of 27	11/25/20
LA-1	LANDSCAPING PLAN	17 of 27	11/25/20
LI-1	LIGHTING PLAN	18 of 27	11/25/20
ES-1	EROSION & SEDIMENT CONTROL PLAN	19 of 27	11/25/20
ES-2	EROSION & SEDIMENT CONTROL PLAN	20 of 27	11/25/20
ESD-1	EROSION & SEDIMENT CONTROL DETAILS	21 of 27	11/25/20
ESD-2	EROSION & SEDIMENT CONTROL DETAILS	22 of 27	11/25/20
DE-1	CONSTRUCTION DETAILS	23 of 27	11/25/20
* PC-1	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN	24 of 27	11/25/20
* PC-2	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN	25 of 27	11/25/20
* PCD-1	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS	26 of 27	11/25/20
* PCD-2	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS	27 of 27	11/25/20

USERS (OWNERS, CONTRACTORS) OF THIS PLAN ARE ADVISED THAT ALL PLANS SHOWN IN THE ABOVE REFERENCED PLAN INDEX SHALL BE UTILIZED WHEN PREPARING ESTIMATES, MANUFACTURING STRUCTURES, AND PERFORMING CONSTRUCTION. CERTAIN PLANS MAY HAVE FEATURES (EXISTING OR PROPOSED) WHICH MAY BE HIDDEN FROM VIEW TO PROVIDE CLARITY FOR THAT PARTICULAR PLAN. ALL DRAWINGS WITHIN THIS PLAN SET SHALL BE REVIEWED AND UTILIZED.

NOTIFICATION

HE DEVELOPER SHALL, AT LEAST FIFTEEN (15) CALENDAR DAYS PRIOR TO THE NITIATION OF CONSTRUCTION OF ANY REQUIRED IMPROVEMENTS. SUBMIT TO TOWNSHIP A SCHEDULE OF CONSTRUCTION FOR ALL REQUIRED IMPROVEMENTS, NCLUDING THE TIMING OF THE DEVELOPMENT OF ANY PROPOSED SECTIONS. 7 SCHEDULE MAY BE REVISED FROM TIME TO TIME UPON MUTUAL AGREEMENT OF HE APPLICANT ENGINEER AND THE TOWNSHIP ENGINEER T SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO NOTIFY THE APPROPRIATE INSPECTION CONSULTANT FOR THE TOWNSHIP OR DESIGNED

AMERICANS WITH DISABILITIES ACT (ADA)

THIS PERMIT AND/OR PLAN HAS NOT BEEN REVIEWED TO DETERMINE ITS COMPLIANCE WITH TITLE III OF THE AMERICANS WITH DISABILITIES ACT OF 1990 (ADA) WHICH PROHIBITS DISCRIMINATION ON THE BASIS OF DISABILITY IN PUBLIC ACCOMMODATIONS AND COMMERCIAL FACILITIES. COMPLIANCE WITH TITLE III OF THIS ACT WITH REGARD TO PUBLIC ACCOMMODATIONS AND COMMERCIAL FACILITIES IS THE RESPONSIBILITY OF THE APPLICANT/OWNER.


AUTHORITY AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO COMMENCING A

THE LAND DEVELOPMENT AS SUBMITTED AND AS BUILT ACCORDING TO THE NFORMATION INCLUDED IN THE CURRENT DESIGN WILL MEET THE ACCESSIBILITY REQUIREMENTS AS EXISTING UNDER THE CURRENT BUILDING CODES ESTABLISHED N SMITHFIELD TOWNSHIP.

TOWNSHIP LIMITED REVIEW STATEMENT

THIS PLAN HAS BEEN REVIEWED BY THE TOWNSHIP STAFF AND TOWNSHIP ENGINEER FOR CONSISTENCY WITH MUNICIPAL REGULATIONS AND ORDINANCES RELATING TO LAND USAGE AND DIMENSIONAL REQUIREMENTS OF ZONING. NVESTIGATIONS REGARDING PERIPHERAL LAND AND PLAN ISSUES WHICH ARE NOT REQUIRED AS PART OF A REVIEW PROCESS SUCH AS CLARITY OF TITLE SUBSURFACE CONDITIONS INCLUDING BUT NOT LIMITED TO, SOIL AND WATER QUALITY, AND HISTORIC AND ARCHEOLOGICAL ISSUES. OR SUCH OTHER ISSUES. (AS APPROPRIATE) THAT MAY AFFECT THE MERCHANTABILITY OF THE LAND. HAVE NOT BEEN INVESTIGATED OR REVIEWED BY THE TOWNSHIP ENGINEER MAKE NO REPRESENTATION OR WARRANTY CONCERNING THESE ISSUES, WHICH SHOULD BE ADDRESSED BY QUALIFIED PROFESSIONALS. COMMISSIONED BY THE DEVELOPER AND/OR LAND OWNER(S) AS APPROPRIATE, AND ENGAGED IN THE APPROPRIATE

\ENGINEER /



Know what's below.

Call before you dig.

PENNSYLVANIA LAW REQUIRES 3

CONSTRUCTION PHASE AND 10 WORKING

DAYS IN DESIGN STAGE - STOP CALL

PENNSYLVANIA ONE CALL SYSTEM, INC.

1-800-242-1776

WORKING DAYS NOTICE FOR

CONSTRUCTION ACTIVITY.

JAMES P. KELLEY. P.E BARRY ISETT & ASSOCIATES, INC. 1444 E. LACKAWANNA AVE., SUITE 214 OLYPHANT, PA 18447 (570) 285-8183 THE SITE SERIAL NUMBER IS 20240651009

SMITHFIELD TOWNSHIP PLANNING COMMISSION CERTIFICATE OF REVIEW AND RECOMMENDATIO AT A PUBLIC MEETING HELD ON THE PLANNING COMMISSION OF SMITHFIELD TOWNSHIP REVIEWED AND BY A MOTION, DULY CARRIED, DOES HEREBY RECOMMEND APPROVAL OF THIS

<u>SMITHFIELD TOWNSHIP BOARD OF SUPERVISORS</u> <u>CERTIFICATE OF REVIEW AND APPROVAL</u>

THE BOARD OF SUPERVISORS OF SMITHFIELD TOWNSHIP REVIEWED AND BY A MOTION, DULY CARRIED, DOES HEREBY APPROVE THIS LAND DEVELOPMENT

SUPERVISOR

SECRETAR

SANITARY AND OTHER APPLICABLE TOWNSHIP ORDINANCES AND REGULATIONS, AND ANY AREAS OF NONCONFORMANCE HAVE BEEN DETAILED, ALONG WITH

COUNTY OF MONROE

ACCORDING TO LAW.

MY COMMISSION EXPIRES: _

CERTIFICATION OF OWNERSHIP AND ACKNOWLEDGMENT OF PLAN COMMONWEALTH OF PENNSYLVANIA

WHO BEING DULY SWORN, ACCORDING TO LAW, DOTH DEPOSE AND SAY THAT THEY ARE THE OWNERS OF THE PROPERTY SHOWN AND DEPICTED ON THIS PLAN. THAT THIS LAND DEVELOPMENT PLAN WAS MADE AT THEIR DIRECTION, AND THAT HEY ACKNOWLEDGE THE SAME AND DESIRES THE SAME TO BE RECORDED

SIGNATURE OF SECRETARY SIGNATURE OF PRESIDENT

SIGNATURE OF NOTARY PUBLIC

MONROE COUNTY PLANNING COMMISSION REVIEW

THE SMITHFIELD TOWNSHIP ENGINEER


RECORDER OF DEEDS CERTIFICATION


RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS, IN MONROE COUNTY, PENNSYLVANIA, IN SUBDIVISION BOOK DLUME _____, PAGE ____. WITNESS MY HAND AND SEAL OF THE OFFICE THIS _____ DAY OF ______ A.D. 20___.

RECORDER OF DEEDS

SHEET: 1 of 27

#	PROPERTY OWNER AKIA S BLANDON	ADJOINERS ADDRESS 208 RAVENS NEST RD	PARCEL #	PIN #
2	TWIN LAKES ESTATES DEVELOPMENT JORGE GARRIDO	211 RAVENS NEST RD 209 RAVENS NEST RD	16.98061 16.9806	16731000751735 16731000659828
4	ETUX DANE BROSSEAU	7604 CHERRY VALLEY RD	16.8.3.45	16731002669440
5 6	JUDITH G & DENNIS C DOUDS	LR 45010 236 CHERRY VALLEY RD	16.8.3.48 4.93387	16731002762776 4731012766658
7 8	RAMNARINE- INDRANI & DMITRI SNYTKINE KUMAR RAVI MAMIDELA	9 SHEPARD CT 14 SHEPARD CT	4.93431 4.9343	4731012767950 4731012769921
9	ALEXANDRA & MANUEL FORS	10 SHEPARD CT	4.93429	4731012769771
10 11	RAFAEL CESAR MARTE L INGRAM BURNETT	8 SHEPARD CT 6 SHEPARD CT	4.93428 4.93427	4731012769506 4731012769433
12 13	AYANA PHILLIPS NEETA PURI	SHEPARD AVE 5 SHEPARD CT	4.93426 4.93424	4731012860521 4731012860259
14 15	D ROBERT KELLY WATER GAP ACQUISTIONS PARTNERS LLC	SHEPARD AVE TRL DOGWOOD	4.92606	4731012861365 4731012852921
16	WATER GAP ACQUISTIONS PARTNERS LLC	DOGWOOD DR	4.3.1.51-7 4.3.2.18	4731012856929
17 18	WATER GAP ACQUISTIONS PARTNERS LLC UNITED STATES OF AMERICA	MOUNTAIN RD WOLF HOLLOW DR	4.3.2.17 16.9.1.27	4731012855395 16731000501344
19 20	UNITED STATES OF AMERICA WATER GAP ACQUISTIONS PARTNERS LLC	T 405 145 WOLF HOLLOW DR	16.9.1.43 16.9.1.28	16731000930739 16731000646042
21	JUDITH G & DENNIS C DOUDS	236 CHERRY VALLEY RD	4.93387	4731012766658
22 23	STACEY BRUTUS KRISTINE K MCHUGH	1624 TOTTS GAP RD 1627 TOTTS GAP RD	16.9.1.23 16.9.1.29	16731000548256 16731004545417
24 25	WILLIAM RICHARD MCKENNA WILLIAM RICHARD MCKENNA	206 PAR THREE LN TOTTS GAP RD	16.110491 16.110492	16731004544373 16731004544149
26	RICHARD A BUBNIS	226 PAR THREE LN	16.9.1.30	16731004542020
27 28	UNITED STATES OF AMERICA	PAR THREE LN LR 45010	16.110493 16.9.1.21	16731004542454 16731000442404
29 30	WATER GAP ACQUISTIONS PARTNERS LLC DEW GAP LLC	T 383	16.9.1.22 16.98052	16731000555514 16731000641538
31	ALLEN EMMONIS	102 ROLLING HILL RD	16.98053	16731000642704
32 33	DENNIS BLANCO BRIAN CANNONIER	104 ROLLING HILL RD 106 ROLLING HILL RD	16.98054 16.98055	16731000642886 16731000653041
34 35	WATER GAP ACQUISTIONS PARTNERS LLC ROB EDWARD STIRTON	206 RAVENS NEST RD 108 ROLLING HILL RD	16.98063 16.98056	16731000646935 16731000654172
36	JEFFREY CHENG	110 ROLLING HILL RD	16.98057	16731000655247
37 38	KUANG MIN CHENG YIN YOKE & JEFFREY CHENG	204 RAVENS NEST RD 112 ROLLING HILL RD	16.98059 16.98058	16731000656564 16731000654500
39 40	VIR CONSTRUCTION CORPORATION ALVIN M DAVIS	111 ROLLING HILL RD 109 ROLLING HILL RD	16.98051	16731000651456
41	SEAN PATRICK KENNEDY	107 ROLLING HILL RD	16.9805 16.98049	16731000651362 16731000651109
42 43	VIR CONSTRUCTION CORPORATION KETTLY BIEN-AIME TURNBULL	105 ROLLING HILL RD 101 ROLLING HILL RD	16.98048 16.98046	16731000559097 16731000548855
44 45	MARY SUE & ANTHONY ARDITO ALLEN CLAUDE ETAL & MICHAEL METZGAR	1682 TOTS GAP RD	16.8.3.41-1 16.94614	16731002651757 16731002663236
46	MICHAEL MATTHEW METZGAR	7562 CHERRY VALLEY RD	16.8.3.40-2	16731002663236
47 48	PATRICIA B & DAVID A TRANSUE CHRISTOPHER ANDERSON	7591 CHERRY VALLEY RD 7599 CHERRY VALLEY RD	16.8.3.39 16.8.3.38	16731002674042 16731002676047
49 50	WILLIAM H HARRISON IV JOSEPH M MAIARA	7605 CHERRY VALLEY RD 7611 CHERRY VALLEY RD	16.8.3.37	16731002677092
51	DOUGLAS P POSTEN	7615 CHERRY VALLEY RD	16.8.3.36 16.8.3.35-1	16731002668996 16731002678291
52 53	ANGELO J CEGLIA II JAMES M TERWILLIGER	158 MAPLE AVE 7584 CHERRY VALLEY RD	16.8.3.34-3 16.8.3.40-1	16731002678593 16731002671242
54 55	SUSAN & JOSEPH L JR KELLERMAN FRANCES & LARRY R KRAMER	7590 CHERRY VALLEY RD 7594 CHERRY VALLEY RD	16.8.3.42	16731002663757
56	KRC INVESTMENTS LLC	7598 CHERRY VALLEY RD	16.8.3.43 16.8.3.44	16731002665718 16731002666758
57 58	SARA BODMAN ERIN K HIGGINS	7608 CHERRY VALLEY RD 7614 CHERRY VALLEY RD	16.8.3.46 16.8.3.47	16731002669709 16731002669799
59 60	FRANK NIPER SUSAN FINE	162MAPLE AVE LR 45010 CHERRY VALLEY RD	16.8.3.34	16731002771518
61	NAJI & DHABAH S ALMONTASER	7629 CHERRY VALLEY RD	16.8.3.35-2 16.8.3.35	16731002771180 16731002773244
62 63	DELAWARE WATER GAP MUNICIPAL AUTH GEORGE RIVERA	CHERRY VALLEY RD LR 45010 7636 CHERY VALLEY RD	16.117548 4.3.1.1-1	16731002774174 4731012775093
64 65	MANUEL GARCIA LISA S PIZZUTO	7642 CHERRY VALLEY RD 7648 CHERRY VALLEY RD	4.93533 4.93532	4731012777100
66	JESSE ROURKE	7654 CHERRY VALLEY RD	4.3.1.1	4731012777195 4731012778282
67 68	RICHARD MICHEL ELAINE M SHUEY	111 KIMBERLY RD 95 KIMBERLY RD	4.3.1.33 4.3.1.33–3	4731012870115 4731012870050
69 70	ROXANNE ANTONOWICH LEROY KAISER	91 KIMBERLY ROAD 67 KIMBERLY ROAD	4.3.1.33-4 4.3.1.33-1	4731012860970 4731012860793
71	SALVATORE A SERPE	2 SHEPARD CT	4.92607	4731012861519
72 73	JOHN JULIAN SUE ELLEN & KEVIN R WALSH	60 KIMBERLY RD 70 KIMBERLY RD	4.112753 4.112754	4731012862795 4731012862888
74 75	DARRIANE TABERER SARAH C & IAN S FOSTER	76 KIMBERLY RD KIMBERLY RD	4.112755 4.3.1.32	4731012862969
75 76	JAAN R HAGERUP	92 KIMBERLY RD	4.3.1.32	4731012873299 4731012873095
77 78	VALERIE L & JEFFREY J HIGBEE DARRIANE TABERER	210 SHEPARD AVE SHEPARD AVE	4.3.1.34-1 4.3.1.34-2	4731012864813 4731012864902
79 80	DEREK ANSPACH SUSAN & STEVEN F SIMISTER	186 SHEPARD AVE 177 SHEPARD AVE	4.3.1.49	4731012875080
81	GEORGE M GALLAGHER	24 CHEROKEE RD	4.3.2.4 4.3.2.3	4731012868919 4731012869953
82 83	ZACHARY M BOOTH BRIAN P HENNEBERRY	187 SHEPARD AVE 37 CHEROKEE RD	4.3.1.51-2 4.3.1.50	4731012867805 4731012867786
84 85	DAVID MARCUS SANTOS TARA M NYLANDER	197 SHEPARD AVE 207 SHEPARD AVE	4.3.1.51-3	4731012866746
86	SALEH TALAAT ELKERDASY	229 SHEPARD AVE	4.3.1.51-1 4.3.1.51-6	4731012865669 4731012863588
37 38	BOROUGH OF DELAWARE WATER GAP KAREN & EDWARD B CRONK	SHEPARD AVE 329 DOGWOOD DR	4.3.1.51-5 4.3.1.56	4731012862447 4731012863369
89	CARLOS QUINTEROS	230 DOGWOOD DR	4.3.1.51	4731012866504
90 91	BOROUGH OF DELAWARE WATER GAP WAYNE MACWILLIAMS	DOGWOOD DR 242 DOGWOOD DR	4.117087 4.3.1.52	4731012866423 4731012865325
92 93	JOHN & ELAINE STARINSKI KAREN OHREM	246 DOGWOOD DR 323 DOGWOOD DR	4.3.1.53 4.3.1.55	4731012864234 4731012862289
94 95	CHRISTINE TREMBLY CHRISTINE TREMBLY	311 DOGWOOD DR 303 DOGWOOD DR	4.3.1.55-1	4731012862231
96	AMANDA & ANTHONY N JAKUBOWSKI	247 DOGWOOD DR	4.3.1.54 4.111734	4731012863007 4731012865150
97 98	LAWRENCE KUCZMA ANNA MOSER	245 DOGWOOD DR 243 DOGWOOD DR	4.111735 4.111736	4731012866118 4731012866276
99	BOROUGH OF DELAWARE WATER GAP	DOGWOOD DR 209 DOGWOOD DR	4.3.2.1	4731012866389
101	HAROLD D CREARY GAIL ELLIOT	199 DOGWOOD DR	4.3.2.18-2 4.3.2.2-2	4731012868416 4731012869527
02 03	JOHN KENNETH ELWOOD EDWARD J ARNER	25 CHEROKEE DR 15 CHEROKEE RD	4.3.2.2-1 4.3.2.2-3	4731012869710 4731012960632
04	JOHN W ETAL SHOEMAKER	178 MOUNTAIN RD	4.3.2.13	4731012962409
105 106	JOHN W SHOEMAKER DAWN Y KOHL	198 MOUNTAIN RD 230 MOUNTAIN RD	4.3.2.14 4.119552	4731012961301 4731012869197
107 108	TERENCE NOEL SMOTH LEANNE CRAMER	230 MOUNTAIN RD MOUNTAIN RD	4.3.2.16 4.119551	4731012960144 4731012960153
109	CAROL T PENNA	230 MOUNTAIN RD	4.11955	4731012960192
110 111	VALERIE GANCI LAICO WESLEY L CAMPBELL	242 MOUNTAIN RD 258 MOUNTAIN RD	4.3.2.18-1 4.3.2.17-1	4731012859937 4731012858789
112 113	BOROUGH OF DELAWARE WATER GAP BOROUGH OF DELAWARE WATER GAP	MOUNTAIN RD OFF MOUTAIN RD	4.110811 4.111258	4731012858602 4731012868153
114	DEREK ANSPACH	EAST OF SHEPARD AVE ST	4.3.1.34	4731012875241
115	MARSHALL E ANDERS	7 SHEPARD CT	4.93425	4731012767406
116	UNITED STATES OF AMERICA	MOUNTAIN RD	4.3.4.1	4732000072449







OWNER/DEVELOPER: WATER GAP ACQUISITIONS PARTNERS, LLC

P.O. BOX 244 DELAWARE WATER GAP, PA 18327

PHONE: 203-524-3039

SITE ADDRESS: WATER GAP WELLNESS 296 MOUNTAIN ROAD

STROUDSBURG, PA 18360 D.B.V. 2418, PG. 6739 DEED BOOK:

16-9-1-26 16731000755147

SEWER: ON-SITE WATER: ON-SITE

ZONING DATA

ZONING DISTRICT: K-1: LOW DEINGTON ... SEWER AND WATER R-1: LOW DENSITY RESIDENTIAL ON-SITE

PROPOSED USE: PROPOSED BUILDING FOR PRIVATE RESORT, CONFERENCE CENTER AND INN MINIMUM LOT AREA: 50,000 SF

MINIMUM LOT WIDTH: 150 FEET MINIMUM LOT DEPTH: 200 FEET MINIMUM YARDS (BUILDING SETBACKS):

FRONT: 35 FEET REAR: 25 FEET

SIDE: 30 FEET LOT COVERAGE (BUILDING): 20%

BUILDING HEIGHT: 35 FEET MAX. IMPERVIOUS COVERAGE: 25% EXISTING BUILDINGS COVERAGE 1.43% PROPOSED BUILDINGS COVERAGE 1.78% PROPOSED IMPERVIOUS COVERAGE 6.50%

SMITHFIELD TWP PROPERTY AREA 51.29 AC. ZONING NOTE: ZONING DATA PROVIDED IS BASED ON AN INTERPRETATION OF THE ZONING ORDINANCE BY THE PLAN PREPARER AND IS SUBJECT TO CONFIRMATION BY THE APPROPRIATE MUNICIPAL

ZONING CLASSIFICATIONS

SMITHFIELD TOWNSHIP

LOW-DENSITY RESIDENTIAL RESIDENTIAL CONSERVATION

LOW-DENSITY RESIDENTIAL CONSERVATION & PARK VILLAGE COMMERCIAL/RESIDENTIAL

NOTE
ALL BOUNDARY, ZONING, AND MUNICIPAL LINE INFORMATION
IS SHOWN AS PER THE MONROE COUNTY, PA PUBLIC GIS DATA.

LEGEND PROPERTY BOUNDARY LOT LINE MUNICIPAL BOUNDARY ZONING BOUNDARY APPALACHIAN TRAIL

COPYRIGHT 2024

8/26/2024

1022419.004

SHEET: 2 OF 27

1"=400'

SCALE:

DRAWN:


TAL/DFG


CRS


JPK

P MGR:

TRAIL CORRIDOR LIMT TRAIL CORRIDOR












SITE D SAP WEI GAP AC

8/26/2024 TAL/DFG P MGR: 1022419.004

SP-










TAL/DFG 8/26/2024 P MGR: 1022419.004 COPYRIGHT 2024

SP-2







WETLAN	ID B METES &	& BOUNDS	WETLAN	ID B METES &	& BOUNDS
SEGMENT	LENGTH (FT.)	DIRECTION	SEGMENT	LENGTH (FT.)	DIRECTION
L1	35.00	S88° 02' 25"W	L13	41.46	S44° 24′ 40″E
L2	28.32	S61° 43′ 08″W	L14	28.26	S41° 24' 09"E
L3	8.75	N79° 37' 21"W	L15	15.50	S74° 02' 37"E
L4	11.66	N19° 51' 04"W	L16	18.26	N5° 52′ 20"W
L5	18.67	N74° 24' 20"W	L17	22.27	N55° 32′ 42″V
L6	14.13	N18° 57' 02"W	L18	56.11	N35° 44' 16"V
L7	21.20	N6° 05' 59"W	L19	15.99	N13° 22' 08"W
L8	50.71	N32° 42' 59"W	L20	42.11	S51° 44' 11"E
L9	24.00	N36° 35' 44"W	L21	13.27	S11° 42′ 13″E

L23

L24

20.28

36.44

31.53

S54° 48' 51"E

S54° 41′ 09″E

S15° 45′ 43″W

N69° 09' 54"E

S40° 51' 27"E

S64° 13' 50"E

13.14


35.79

26.58

40"E				
09"E	CTE	DEAM DUEEED DA	\ T A	
37"E	STREAM BUFFER DATA			
20"W	STREAM BUFFER AREA	STREAM BUFFER DISTURBANCE	DISTURBANCE %	
42"W	43,208.75 S.F.	1,400.84 S.F.	3.24%	
16"W				

PROPERTY SLOPE DATA								
MINIMUM SLOPE	MAXIMUM SLOPE	COLOR	AREA (AC.)	AREA (S.F.)	AREA (%)	DISTURBED AREA (S.F.)	DISTURBED AREA (%)	MAXIMUM AREA OF DISTURBANCE
15%	25%		17.72 AC.	771,789.36 S.F.	16.76%	13,417.45 S.F.	1.74%	60%
25%	100%		8.79 AC.	382,966.72 S.F.	8.32%	6,410.70 S.F.	1.67%	10%

		<u>LE</u>	<u>EGEND</u>		
	<u>EXISTING</u>	<u>DEMOLITION</u>		<u>EXISTING</u>	<u>DEMOLITION</u>
PROPERTY BOUNDARY			CHAIN-LINK FENCE	$\longleftarrow X \xrightarrow{CHAIN-LINK FENCE} X \longrightarrow$	
LOT LINE			WOOD FENCE	← □ WOOD FENCE □ ─ ─ ·	
BUILDING SETBACK			SIGN	o	
LEGAL RIGHT-OF-WAY				ا پرسسر 6" MAPLE	
EASEMENT			DECIDUOUS TREE	+ +	
CURBING	DEPRESSED CURB		EVERGREEN TREE	6" PINE	
BUILDING	EXIST. BUILDING		TREE ROW		
	(11111111111111111111111111111111111111		CONTOUR		
PAVEMENT		<u>[j</u>	SPOT ELEVATION	_X 590.53	
GRAVEL			STREAM		
SOIL BOUNDARY			WETLANDS		
UTILITY POLE	Ø ^{U.P.}		EDGE OF PAVEMENT	E.O.P.	
OVERHEAD ELECTRIC	<i>₩</i> /		EDGE OF GRAVEL	E.O.G.	
WATER MAIN & VALVE	$\begin{array}{ccccc} & & & & & & & & & & \\ & & & & & & & & $		BITUMINOUS	BIT.	
GAS MAIN & VALVE			TYPICAL	(TYP.)	
SANITARY LINE, MANHOLE, & CLEANOUT	$SAN. MH \longrightarrow SAN \longrightarrow CO \longrightarrow ($		TO BE REMOVED		(T.B.R.)
STORM LINE, MANHOLE,	STORM MH INLET		FINISHED FLOOR	F.F.	
& INLET			DOOR SILL	D.S.	
		NOTE:	TEVT INDICATES DRODOSED FEATURE	0 30'	60'
			TEXT INDICATES PROPOSED FEATU TEXT INDICATES EXISTING FEATURE		o'




ER

XISTING RESOURCES & SITE ANALYSIS PLARWATER GAP WELLNESS RECREATION CENTER WATER GAP ACQUISITIONS PARTNERS, LLCSMITHFIELD TOWNSHIP MONROE COUNTY, PA


TAL/DFG 8/26/2024 SCALE: CRS 1"=30' DRAWN: P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 7 OF 27

ER-2









SOIL CLASSIFICATIONS

BATH CHANNERY SILT LOAM - HSG C
3 TO 8 PERCENT SLOPES

BATH CHANNERY SILT LOAM - HSG C
8 TO 15 PERCENT SLOPES

BATH CHANNERY SILT LOAM - HSG C
0 TO 8 PERCENT SLOPES, EXTREMELY STONY

BATH CHANNERY SILT LOAM - HSG C
8 TO 25 PERCENT SLOPES, EXTREMELY STONY

BENSON-ROCK OUTCROP COMPLEX - HSG D
8 TO 25 PERCENT SLOPES


CHIPPEWA AND NORWICH SOIL - HSG D
0 TO 8 PERCENT SLOPES, EXTREMELY STONY


LACKAWANNA AND BATH SOILS - HSG D
STEEP, RUBBLY

MARDIN VERY STONY SILT LOAM - HSG D
0 TO 8 PERCENT SLOPES

PROPERTY SLOPE DATA								
MINIMUM SLOPE	MAXIMUM SLOPE	COLOR	AREA (AC.)	AREA (S.F.)	AREA (%)	DISTURBED AREA (S.F.)	DISTURBED AREA (%)	MAXIMUM AREA OF DISTURBANCE
15%	25%		17.72 AC.	771,789.36 S.F.	16.76%	13,417.45 S.F.	1.74%	60%
25%	100%		8.79 AC.	382,966.72 S.F.	8.32%	6,410.70 S.F.	1.67%	10%

	<u>EXISTING</u>	<u>DEMOLITION</u>		<u>EXISTING</u>	<u>DEMOLITION</u>
PROPERTY BOUNDARY LOT LINE			CHAIN-LINK FENCE WOOD FENCE	¿—— χ CHAIN-LINK FENCE Z —— X WOOD FENCE □	
BUILDING SETBACK			SIGN	٩	
LEGAL RIGHT-OF-WAY EASEMENT			DECIDUOUS TREE	6" MAPLE	
CURBING	DEPRESSED CURB		EVERGREEN TREE	6" PINE	
BUILDING	EXIST. BUILDING		TREE ROW		
D 41/51/51/5	(//////////////////////////////////////	·	CONTOUR		
PAVEMENT			SPOT ELEVATION	_X 590.53	
GRAVEL			STREAM		
SOIL BOUNDARY UTILITY POLE			WETLANDS	ψ ψ ψ ψ ψ	
OVERHEAD ELECTRIC	φ 		EDGE OF PAVEMENT	E.O.P.	
WATER MAIN & VALVE	<i>WV W W W W W W W W W W</i>		EDGE OF GRAVEL	E. O. G.	
GAS MAIN & VALVE	$\longleftrightarrow \frac{GV}{G} \longrightarrow G \longrightarrow$		BITUMINOUS	BIT.	
SANITARY LINE, MANHOLE,	SAN. MH CO		TYPICAL	(TYP.)	
& CLEANOUT	₹ SAN SAN		TO BE REMOVED		(T.B.R.)
STORM LINE, MANHOLE, & INLET	STORM MH INLET		FINISHED FLOOR	F.F.	
& INLET			DOOR SILL	D.S.	








SOURCES & SITE ANALYSIS PLAN
WELLNESS RECREATION CENTER
P ACQUISITIONS PARTNERS, LLC
MONROE COUNTY, PA


TAL/DFG 8/26/2024 SCALE: CRS DRAWN: 1022419.004 COPYRIGHT 2024 SHEET: 8 OF 27










8/26/2024 TAL/DFG DRAWN: P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 9 OF 27













TAL/DFG 8/26/2024 CRS 1"=30' P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 10 OF 27










OT NE

8/26/2024 TAL/DFG 1"=30

JPK P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 11 OF 27











TAL/DFG 8/26/2024 CRS P MGR: 1022419.004 COPYRIGHT 2024

UP-2









STA::0+00 TO 1+12.45 SCALE: 1"=30'(H), 1"=3'(V)

STORM SEWER PLAN & PROFILES

VATER GAP WELLNESS RECREATION CENTER

WATER GAP ACQUISITIONS PARTNERS, LLC

SMITHFIELD TOWNSHIP

MONROE COUNTY, PA TAL/DFG 8/26/2024 SCALE: CRS 1"=30' DRAWN: JPK

COPYRIGHT 2024 SHEET: 13 OF 27 PP-1


P MGR:


JPK

JOB:

1022419.004









0 30' 60' 90


STORM SEWER PLAN & PROFILES


WATER GAP WELLNESS RECREATION CENTER
WATER GAP ACQUISITIONS PARTNERS, LLC
SMITHFIELD TOWNSHIP
MONROE COUNTY, PA

9 (1)

PP-2

SHEET: 14 OF 27








STORM SEWER PLAN & PROFILES

WATER GAP WELLNESS RECREATION CENTER
WATER GAP ACQUISITIONS PARTNERS, LLC
SMITHFIELD TOWNSHIP
MONROE COUNTY, PA

8/26/2024 TAL/DFG SCALE: CHK: 1"=30' CRS DRAWN: JPK JOB: P MGR: 1022419.004 JPK

SHEET: 15 OF 27 PP-3




PLAN VIEW
SCALE: 1"=30'

Know what's below.
Call before you dig.

SITE SERIAL #20240651009


8/26/2024 TAL/DFG SCALE: 1"=30' CRS DRAWN: P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 16 OF 27

PP-4



502.7.A TREE FENCES
- EVERGREEN TREES PROVIDED ALONG THE PROPERTY LINE TO BUFFER STORMWATER BASIN.

SITE SERIAL #20240651009






LANDSCAPING PLAN
AP WELLNESS RECREATION
SAP ACQUISITIONS PARTNE
SMITHFIELD TOWNSHIP
MONROE COUNTY, PA

8/26/2024 TAL/DFG CRS 1"=30' JPK P MGR: 1022419.004

SHEET: 17 OF 27

NOTE:
VERTICAL TEXT INDICATES PROPOSED FEATURES


SLANTED TEXT INDICATES EXISTING FEATURES






8/26/2024 TAL/DFG DRAWN: P MGR: 1022419.004 COPYRIGHT 2024


SHEET: 18 OF 27





NOTES & DETAILS

SITE SERIAL #20240651009





8/26/2024 TAL/DFG CRS 1"=30' JPK P MGR: 1022419.004 COPYRIGHT 2024

ES-2


NOTE: VERTICAL TEXT INDICATES PROPOSED FEATURES

SLANTED TEXT INDICATES EXISTING FEATURES

* MOUNTABLE BERM USED TO PROVIDE PROPER COVER FOR PIPE REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE. MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED. MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK, A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE B 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR

STANDARD CONSTRUCTION DETAIL #3-1 **ROCK CONSTRUCTION ENTRANCE**

OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.



- COMPOST FILTER SOCK

NOTES:

1. PLACE STOCKPILES AT LOCATIONS SHOWN ON PLAN. 2. STOCKPILE TO BE IMMEDIATELY SEEDED WITH A TEMPORARY SEED 3. SIDE SLOPES SHALL NOT EXCEED 1' VERTICAL TO 2' HORIZONTAL. 4. MAXIMUM TOPSOIL STOCKPILE HEIGHT NOT TO EXCEED 35'.

SEEDING SCHEDULE SPECIFICATION: THE FOLLOWING SPECIFICATION SHALL BE USED FOR THIS PROJECT UNLESS OTHERWISE NOTED. Penn State College of Agriculture Sciences, EROSION CONTROL AND CONSERVATION PLANTINGS ON NONCROPLAND by Peter Landschoot, 1997 or as revised.

PRIOR TO STARTING EARTH DISTURBANCE, CONTRACTOR SHALL SAMPLE THE SITE TOPSOIL AND OBTAIN A SOIL TEST FROM A REPUTABLE LABORATORY, AT A MINIMUM, THE TEST SHALL INCLUDE SOIL PH, COMPOSITION, AND % ORGANICS

SCARIFY SUBGRADE WITH DEEP TINE PLOW. SCREEN TOPSOIL AND UNIFORMLY BLEND IN 0-25% BY VOLUME LEAF MOULD OR PROCESSED MUSHROOM SUBSTRATE. SPREAD AMENDED/SCREENED TOPSOIL OVER SUBGRADE TO OBTAIN FINISHED GRADE. COMPACT

TEMPORARY COVER FOR EROSION CONTROL INITIAL PROTECTION: APPLY TEMPORARY SEEDING WHEN PERMANENT SEEDING IS DELAYED OR OUT OF PLANTING SEASON.

SITE PREPARATION: INCORPORATE LIME AND FERTILIZER (RATE BASED ON SOIL TEST) INTO THE TOP 4-6" OF TOPSOIL. IF SOIL TESTS ARE NOT AVAILABLE, APPLY ONE TON PER ACRE F AGRICULTURAL LIMESTONE AND 10-10-10 FERTILIZER

METHOD: APPLY SEED USING SURFACE BROADCASTING OR HYDROSEEDING

SEASO	<u>N</u>	SPECIES	RATE (LB./ACRE
SPRING (MARCH 15 T	O JUNE 15)	ANNUAL RYEGRASS or SPRING OATS		40 96
SUMMER (JUNE 16 TO	AUGUST 15)	ANNUAL RYEGRASS		40
FALL (AUGUST 16	TO NOVEMBER 1)	ANNUAL RYEGRASS or WINTER RYE		40 168
MULCHING:	CELLULOSE FIBER TACKI	R 3/4-1" DEEP. USE THAN STRAW ON STEEP SLOPES. APPLY FIER OVER STRAW MULCH AT A RATE ACRE. HYDROMULCHING IS ACCEPTABLI		

ALL DISTURBED AREAS TO BE PREPARED AND SEEDE TH THE FOLLOWING SPECIES AT THE NOTED SEEDING

RATE FOLLOWING FINAL GRADING AUGUST 15 - OCTOBER 15

PERMANENT COVER FOR STABILIZATION

SITE PREPARATION: INCORPORATE LIME AND FERTILIZER (RATE BASED ON SOIL TEST) INTO THE TOP 6" OF TOPSOIL. IF SOIL TESTS ARE NOT AVAILABLE. APPLY SIX TONS PER ACRE AGRICULTURAL LIMESTONE AND 10-20-20 FERTILIZER AT 1.000 LB PER ACRE.


MULCHING: APPLY THREE TONS PER ACRE OF STRAW TO ACHIEVE A LOOSE LAYER 3/4-1" DEEP. USE JUTE MATTING RATHER THAN STRAW ON STEEP SLOPES. APPLY LLULOSE FIBER TACKIFIER OVER STRAW MULCH AT A RATE 800-1000 LBS. PER ACRE. HYDROMULCHING IS ACCEPTABLE WHEN BLOWING OF STRAW IS A CONCERN.

METHOD: APPLY SEED USING DRILL FITTED WITH A DEPTH BAND AND PACKER WHEEL. PLANT GRASS SEEDS AT 0.25 TO 0.5 INCHES DEEP. WHEAT, RYE AND OATS MAYBE PLANTED 1 TO 15 INCHES DEEP BROADCAST SEEDING PERMITTED WITH IMMEDIATE MULCH COVER HYDROSEEDING OF PERMANENT SEEDING IS NOT PERMITTED.


LAWNS	KENTUCKY BLUEGRASS (POA PRATENSIS) and	4
	TURF—TYPE PERENNIAL RYEGRASS (LOLIÚM PERENNE) and	1.5
	FINE (RED or CHEWING) FESCUE (FESTUCA RUBA RUBA/COMMUTATA)	2.5
SLOPES	AND BANKS	
	CHEWINGS FESCUE (FESTUCA RUBRA COMMUTATA) and	2
	BLUE FESCUE (FESTUCA OVINA GLAUCA) and	2
	HARD FESCUE (FESTUCA OVINA DURIUSĆULA) and	1
	CREEPING RED FESCUE (FESTUCA RUBRA RUBRA) and	1
	SLENDER FESCUE (FESTÙCA RUBRA TRICHOPHYLLA) and	1
	DAWSON RED FESCUE (FESTUCA RUBRA DAWSON) and	1
	ANNUAL RYEGRASS (FÈSTUCA MULTIFLORUM)	0.5

REDTOP (AGROSTIS ALBA) and L FESCUE (FESTUCA ARUNDINACEA) and SWITCHGRASS (PANICUM VIRGATUM) * ALL SEED TO BE MIN. 98% PURE LIVE SEED

SUGGESTED VARIETIES RELIANT II. SR3100, DISCOVERY, OSPREY Houndog V, Montauk, Marksman, and Apache II WINTER RYE ARCOOSTOOK OR BALBO TYPE KENTUCKY BLUEGRASS - SR 2109, NORTH STAR, BLACKSBURG, BRILLIANT



STAPLE PATTERN A DETAIL STAPLE PATTERN B DETAIL



INSTALL BEGINNING OF ROLL IN 6 IN. x 6 IN. ANCHOR TRENCH, STAPLE, AND OVERLAPPED (4 IN. MIN.) BACKFILL AND COMPACT SOIL SLOPE, ROLL BLANKETS II PREPARE SEED BED FERTILIZER AND SEED) PRIOR TO THE BLANKET SHOULD $^{\perp}$ OVERLAP BLANKET ENDS 6 IN. MIN. $^{\perp}$ REFER TO MANUF. RECOMMENDED NOT BE STRETCHED; WITH THE UPSLOPE BLANKED STAPLING PATTERN FOR STEEPNESS T MUST MAINTAIN OVERLYING THE DOWNSLOPE AND LENGTH OF SLOPE BEING

BLANKET EDGES STAPLED

ALL EROSION CONTROL BLANKETS SHALL BE NORTH AMERICAN GREEN PHOTODEGRADABLE BLANKET S75 UNLESS OTHERWISE NOTED FOR SPILLWAYS OR BERM STABILIZATION. SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET. PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.

BLANKET (SHINGLE STYLE). STAPLE

SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS. BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET. THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

MODIFIED CONSTRUCTION DETAIL #11-1 EROSION <u>CONTROL BLANKET INSTALLATION</u>

Job #: 1022419.004

PLAN PREPARER CONTACT INFORMATION

JAMES P. KELLEY, P.E. BARRY ISETT & ASSOCIATES, INC. 1444 E. LACKAWANNA AVE., SUITE 214 OLYPHANT, PA 18447 PHONE: (570) 285-8183

PLANNING AND DESIGN

EMAIL: JKELLEY@BARRYISETT.COM


THE EARTH CONSTRUCTION ACTIVITIES, PROPOSED BY THIS PLAN, HAVE BEEN PLANNED AND IMPLEMENTED TO THE MAXIMUM EXTENT PRACTICABLE, IN ACCORDANCE WITH THE FOLLOWING:

- 1. MINIMIZE THE EXTENT AND DURATION OF THE EARTH DISTURBANCE.
- 2. MAXIMIZE PROTECTION OF EXISTING DRAINAGE FEATURES AND VEGETATION.
- MINIMIZE SOIL COMPACTION.
- 4. UTILIZE OTHER MEASURES OR CONTROLS THAT PREVENT OR MINIMIZE THE GENERATION OF INCREASED STORMWATER RUNOFF.

FLOODPLAIN MAPPING

THE PROJECT AREA WAS REVIEWED USING THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) NATIONAL FLOOD HAZARD LAYER (NFHL). THE NFHL IS A COMPILATION OF GIS DATA THAT COMPRISES A NATIONWIDE DIGITAL FLOOD INSURANCE RATE MAP. THE GIS DATA AND SERVICES ARE DESIGNED TO PROVIDE THE USER WITH THE ABILITY TO DETERMINE THE FLOOD ZONE, BASE FLOOD ELEVATION, AND FLOODWAY STATUS FOR A PARTICULAR LOCATION.

THE PROJECT AREA IS NOT LOCATED WITHIN A MAPPED FLOODPLAIN. THE PANEL FOR THE PROJECT AREA IS 42089C0432E, HAVING AN EFFECTIVE DATE OF 05/2/2013.



WASH RACK SHALL BE 20 FEET (MIN.) WIDE OR TOTAL WIDTH OF ACCESS. WASH RACK SHALL BE DESIGNED AND CONSTRUCTED TO ACCOMMODATE ANTICIPATED

A WATER SUPPLY SHALL BE MADE AVAILABLE TO WASH THE WHEELS OF ALL VEHICLES EXITING

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. DRAIN SPACE UNDER WASH RACK SHALL BE KEPT OPEN AT ALL TIMES. DAMAGE TO THE WASH RACK SHALL BE REPAIRED PRIOR TO FURTHER USE OF THE RACK. ALL SEDIMENT DEPOSITED ON ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS

STANDARD CONSTRUCTION DETAIL #3-2 ROCK CONSTRUCTION ACCESS WITH WASH RACK NOT TO SCALE

SOILS RESOURCES

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
ВаВ	Bath channery silt loam, 3 to 8 percent slopes	9.4	11.6%
BaC	Bath channery silt loam, 8 to 15 percent slopes	20.9	25.6%
BaD	Bath channery silt loam, 15 to 25 percent slopes	3.2	3.9%
BbB	Bath channery silt loam, 0 to 8 percent slopes, extremely stony	2.5	3.0%
BbC	Bath channery silt loam, 8 to 25 percent slopes, extremely stony	2.7	3.3%
BeC	Benson-Rock outcrop complex, 8 to 25 percent slopes	14.6	17.8%
BeF	Benson-Rock outcrop complex, 25 to 70 percent slopes	1.6	2.0%
CnB	Chippewa and Norwich soils, 0 to 8 percent slopes, extremely stony	12.4	15.1%
LBE	Lackawanna and Bath soils, steep, rubbly	4.8	5.9%
MbB	Mardin very stony silt loam, 0 to 8 percent slopes	6.4	7.9%
ReA	Rexford gravelly silt loam, 0 to 3 percent slopes	3.2	3.9%
Totals for Area of Interest		81.7	100.0%

SOILS LIMITATIONS & RESOLUTIONS SHEET

LOCAT	TION: Smithfield Township			COUNTY: Monroe
CHARAC	CTERISTICS	LIMITATIONS	RESOLUTIONS	COMMENTS
HYDRIC	WETLANDS	NO DISTURBANCE (UNLESS ALLOWED BY DEP PERMIT)	DELINEATE WETLANDS PROTECT WETLANDS OBTAIN PERMIT(S)	SEE SOIL EROSION PLAN SHEET COPIES OF PERMITS
DEPTH TO BEDROCK		RESERVOIR AREAS DIVERSIONS - WATERWAYS TERRACES UTILITIES BUILDING SITES	REVISE DESIGN - RELOCATE	NOT ALWAYS POSSIBLE
TOPSOIL	POOR	VEGETATIVE STABILIZATION EMBANKMENTS HIGH ACIDITY LOW FERTILITY EXCESSIVE DRYNESS EXCESSIVE WETNESS	SOIL TESTS ADJUST SOILS IMPLEMENTS AS NEEDED	SEE SEEDING WORKSHEETS AND DETAIL SHEET NOTES
WET	HIGH WATER TABLE FLOODING HYDRIC PIPING SEEPAGE	RESERVOIR AREAS UTILITIES EMBANKMENTS DIKES LEVEES BUILDING SITES LANDSCAPING	SELECT FILL MATERIAL FROM OTHER AREA OF SITE SELECT APPROPRIATE PLANT MIXTURE PROVIDE PUMPED WATER SEDIMENT REMOVAL FACILITY DRAINAGE CHANNELS - UNDERDRAINS IMPORT BORROW MATERIAL FROM OFFSITE	SEE SEEDING WORKSHEETS AND DETAIL SHEET NOTES SEE DETAIL SHEET
WINTER GRADING FROST ACTION	POOR COMPACTION	RESERVOIR AREAS EMBANKMENTS	LIMIT DATES OF EARTH MOVING SELECT FILL MATERIAL FROM OTHER AREA OF SITE IMPORT BORROW MATERIAL FROM OFFSITE	SEE CONSTRUCTION SCHEDULE

CONSTRUCTION SCHEDULE

ANTICIPATED START OF CONSTRUCTION: START DATE: MARCH 2025

ANTICIPATED END OF CONSTRUCTION: END DATE: AUGUST 2025

AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES. INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE MONROE COUNTY CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING. AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO

AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED BY THE MONROE COUNTY CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO

IMPLEMENTATION. EACH STEP OF THE SEQUENCE SHALL BE COMPLETED BEFORE PROCEEDING TO THE NEXT STEP, EXCEPT WHERE NOTED. IMMEDIATELY STABILIZE ALL DISTURBED AREAS UPON TEMPORARY CESSATION OF WORK (4 DAYS OR LONGER) OR AS SOON AS ANY GRADED AREA REACHES FINAL GRADE. NO AREA EXCEEDING 15,000 SQUARE FEET, WHICH IS TO BE STABILIZED BY VEGETATION, SHOULD

REACH FINAL GRADE WITHOUT BEING SEEDED AND MULCHED. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED VEGETATED AREAS. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS.

- REFER TO THE SPECIFIC BMP SEQUENCES OF CONSTRUCTION ON THE PCSM PLANS FOR THE INSTALLATION OF PCSM BMP'S ON STEPS 5 AND 7 OF THE CONSTURCTION SEQUENCE BELOW: 1. DELINEATE THE LIMIT OF DISTURBANCE, INSTALL RCE, CFS-1 TO CFS-15, ORANGE CONSTRUCTION FENCING, AND THE CONCRETE WASHOUT.
- . REMOVE SITE FEATURES DESIGNATED AS TBR. STRIP TOPSOIL AND STOCKPILE AT THE LOCATION SPECIFIED ON THE PLANS BEFORE BEGINNING EXCAVATION OR GRADING.
- 3. BEGIN ROUGH GRADING. INSTALL SLOPE PROTECTION MATTING ON AREAS OF STEEP SLOPES. 4. INSTALL PROPOSED ROCK/RETAINING WALL TREE PROTECTION BEFORE GRADING UPSLOPE
- CRITICAL STAGE: BEGIN CONSTRUCTION OF PROPOSED INFILTRATION BASIN. REFER TO PCSM PLAN SET FOR CONSTRUCTION SEQUENCE AND FURTHER DETAILS AND INFORMATION. AT NO POINT SHALL EQUIPMENT TRAVERSE WITHIN THE ORANGE CONSTRUCTION FENCING OR OVERTOP THE PROPOSED BASIN BOTTOM. SEE STEP 6 FOR STORM SEWER INSTALLATION DURING BASIN BERM CONSTRUCTION
- BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM EW-25 TO IN-21, FROM MH-24 TO IN-20, AND THE BASIN OUTLET PIPE, INSTALL PROPOSED STORM SEWER RUNS FROM DOWNSTREAM TO UPSTREAM. IMMEDIATELY INSTALL INLET PROTECTION ON INSTALLED INLETS. INSTALL RIPRAP PROTECTION AT OUTLET OF STORM PIPING. INSTALL ANTI-SEEP COLLARS ON BASIN OUTLET PIPE.
- CRITICAL STAGE: INSTALL AMENDED SOILS IN INFILTRATION BASIN TO BRING BOTTOM UP TO GRADE. INFILTRATION TESTING SHALL BE PERFORMED DURING AND AFTER CONSTRUCTION TO VERIFY INFILTRATION RATES OF AMENDED SOILS.
- 8. BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM FES-19 TO MH-10. INSTALL PROPOSED STORM SEWER RUNS FROM DOWNSTREAM TO UPSTREAM. INSTALL RIPRAP PROTECTION AT OUTLET OF STORM PIPING
- 9. BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM MH-10 TO AD-12 AND FROM MH-10 TO DEPRESSION. IMMEDIATELY INSTALL INLET PROTECTION ON INSTALLED INLETS.
- 10. BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM MH-10 TO AD-2 AND FROM DEPRESSION TO RD-7. IMMEDIATELY INSTALL INLET PROTECTION ON INSTALLED INLETS.
- 11. BEGIN CONSTRUCTION OF THE PROPOSED IMPROVEMENTS.
- 15. INSTALL SITE LIGHTING.
- 16. FINAL GRADE, SPREAD TOPSOIL, RAKE, AND SEED ALL DISTURBED AREAS. TOPSOIL SHALL BE REPLACED ACROSS LAWN AREAS AT A MINIMUM THICKNESS OF 6 INCHES. 18. AFTER ALL DISTURBED AREAS ACHIEVE FINAL STABILIZATION, REMOVE ALL E&S CONTROLS.
- REPAIR, SEED, AND STABILIZE ANY AREAS DISTURBED DURING THE REMOVAL OF THE EROSION
- 19. CRITICAL STAGE: FIELD VERIFY TRIBUTARY AREAS TO PCSM BMPS.
- 20. AFTER THE PROJECT IS COMPLETED, THE NPDES NOTICE OF TERMINATION PAPERWORK AND AS-BUILT PLANS SHALL BE COMPLETED AND SUBMITTED TO MONROE COUNTY CONSERVATION DISTRICT.
- 1. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70 PERCENT PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE RE-DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE RE-DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.
- TEMPORARY EROSION CONTROL MEASURES MAY ONLY BE REMOVED AFTER APPROVAL BY THE MONROE COUNTY CONSERVATION DISTRICT, AFTER THE CONSTRUCTION AREA AND RETAINED SILT ARE STABILIZED AND AFTER LAWN AREAS ARE ESTABLISHED.

OPERATION AND MAINTENANCE PROGRAM

THE CONTRACTOR SHALL FURNISH, INSTALL, OPERATE, AND MAINTAIN ALL EROSION AND SEDIMENT POLLUTION CONTROL (E&S) BEST MANAGEMENT PRACTICES (BMPS) IDENTIFIED HEREIN. E&S BMPS SHALL BE MAINTAINED IN ACCORDANCE WITH THIS E&S PLAN AND THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP) EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL (E&S MANUAL), MARCH 2012.

E&S BMPS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF, UNLESS OTHERWISE INDICATED. THE CONTRACTOR SHALL KEEP RECORD OF ALL INSPECTIONS USING THE VISUAL SITE INSPECTION REPORT FORM (FORM 3150-FM-BWEW0083). E&S BMPS WHICH NEED REPAIR OR REPLACEMENT, SHALL BE REMEDIED IMMEDIATELY. DISPOSAL OF MATERIALS REMOVED FROM THE BMPS SHALL BE PERFORMED IN ACCORDANCE WITH THE RECYCLING OR DISPOSAL OF MATERIALS

RECYCLING OR DISPOSAL OF MATERIALS

CONSTRUCTION WASTES FROM LAND DISTURBANCE AND DEVELOPMENT SHALL BE DISPOSED OF BY THE CONTRACTOR IN AREAS SUITABLE FOR SUCH WASTES IN ACCORDANCE WITH PA DEP REGULATIONS. EXCESS SOIL/ROCK SHALL BE UTILIZED ON SITE TO IMPROVE FINAL GRADING OF LOW AREA LOTS. THESE WASTES INCLUDE, BUT ARE NOT LIMITED TO, EXCESS SOIL MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER, SANITARY WASTES, ETC. THAT COULD ADVERSELY IMPACT WATER QUALITY. MEASURES SHOULD BE PLANNED AND IMPLEMENTED FOR HOUSEKEEPING, MATERIALS MANAGEMENT, AND LITTER CONTROL. WHEREVER POSSIBLE, RECYCLING OF EXCESS MATERIALS IS PREFERRED, RATHER THAN DISPOSAL.

THE OPERATOR SHALL ASSURE THAT AN E&S CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE GOVERNING CONSERVATION DISTRICT, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL/ROCK SPOIL AND BORROW AREAS, REGARDLESS OF THEIR LOCATIONS.

RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THIS PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH PA DEP RULES AND REGULATIONS.

SEDIMENT REMOVED FROM ESPCP CONTROLS AND FACILITIES SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED OR PLACED IN TOPSOIL STOCKPILES.

- ANTICIPATED CONSTRUCTION WASTES INCLUDE, BUT MAY NOT BE LIMITED TO, THE FOLLOWING: SEDIMENT TRASH / DEBRIS
- VEGETATION CLIPPINGS AS MAY RESULT FROM MAINTENANCE PACKAGING MATERIAL
- FORMWORK ASSOCIATED WITH CONCRETE FOUNDATIONS

CLEAN FILL NOTES

THE OPERATOR MUST USE ENVIRONMENTAL DUE DILIGENCE TO ENSURE THAT ALL FILL MATERIAL ASSOCIATED WITH THE PROJECT QUALIFIES AS CLEAN FILL.


CLEAN FILL IS DEFINED AS UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPERATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.)


ENVIRONMENTAL DUE DILLIGENCE TO ENSURE ALL FILL IS "CLEAN", AS DEFINED ABOVE, SHALL INCLUDE. BUT NOT BE LIMITED TO. INVESTIGATIVE TECHNIQUES SUCH AS VISUAL PROPERTY INSPECTIONS. ELECTRONIC DATA BASE SEARCHES. REVIEW OF PROPERTY OWNERSHIP. REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND LISE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE REEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE. IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. ALL TESTING SHALL BE PREFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY OF "MANAGEMENT OF FILL."

STANDARD E&S PLAN NOTES

DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING.

- ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED. SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.
- AT LEAST 7 DAYS PRIOR TO EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING. THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LAND OWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION
- 3. AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THE SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO
- AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL.
- 6. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THE E&S PLAN.
- 7. AT NO TIMES SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- 8. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN MAP(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR FLATTER.
- IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT.
- 10. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET. SEQ., 271.1 AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.
- 11. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING
- 12. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER OF ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BY QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING.
- 13. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER DISTURBED VEGETATED AREAS.
- 14. VEHICLES AND EQUIPMENT MAY NEITHER ENTER DIRECTLY NOR EXIT DIRECTLY FROM THE SITE ONTO THE ADJACENT ROADWAY UNLESS USING THE CONSTRUCTION ENTRANCE.
- 15. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE
- 16. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION.
- SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- 18. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS.
- 19. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES - 6 TO 12 INCHES ON COMPACTED SOILS - PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL.
- 20. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.
- 21. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN
- 22. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS.
- 23. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHLL NOT BE INCORPORATED INTO FILLS.
- 24. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.
- 25. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED
- 26. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.
- 27. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN AN AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS.
- 28. PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
- 29. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PFRMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.
- 30. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S
- 31. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATION SEASON.
- 32. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION.
- 33. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION.







& SEDIMENT CONT
P WELLNESS RECRE
AP ACQUISITIONS PA
SMITHFIELD TOWNS
MONROE COUNTY, ۵ | ۱۰ SION ER GAF TER G/


> 8/26/2024 TAL/DFG SCALE: AS NOTED CRS DRAWN: JPK P MGR: 1022419.004 JPK

COPYRIGHT 2024 SHEET: 21 OF 27

- NOTES:

 1. OVER EXCAVATE SINKHOLE THROAT TO REMOVE ALL SOIL AND LOOSE ROCK. 2. PLACE ROCK(S) TO PLUG SINKHOLE THROAT. ROCKS SHALL BE SIZED SO THEY CANNOT GO THROUGH THE THROAT. FILL SMALL VOIDS WITH SMALLER ROCK TO LEVEL THE PLUG. 3. PLACE A THIN LIFT OF BENTONITE CLAY TO LEVEL THE ROCK PLUG. PLACE GEOTEXTILE DRAINAGE FABRIC OVER THE DISTURBED AREA, EMBEDDING 6" ON ALL EDGES. FABRIC TO HAVE TENSILE STRENGTH OF 90 LBS. AND AN
- EQUIVALENT OPENING SIZE OF SIEVE #200 MINIMUM. LARGER OPENINGS MAY REQUIRE A CONCRETE PLUG. 18"-24" THICK. PLAC E BENTONITE CLAY/SOIL (1 TO 2 LBS./S.F., 8" LIFT, 95% MOD. PROCTOR). PLACE COMPACTED FINE-GRAINED NATIVE CLAY FILL (8" LIFTS, 95% MOD. PROCTOR) EVERY OTHER LIFT TO 12" BELOW FINAL GRADE. INSTALL BENTONITE CLAY/SOIL CAP 10' BEYOND THE EXCAVATION AS SHOWN. GRADE NATIVE CLAY TO DRAIN AWAY FROM THE AREA.
- 8. PLACE 4" OF TOPSOIL, RESEED OR SOD TO STABILIZE. ALL STABILIZATION WORK SHOULD BE DONE UNDER SUPERVISION OF A GEOLOGIST OR ENGINEER FAMILIAR WITH SITE AND FOUNDATION CONDITIONS.

SINKHOLE MITIGATION DETAIL



		RIP	RAP	APR□N			
OUTLE T NO.	PIPE DIA Pd (IN)	SIZE R	THICK. Rt (IN)	LENGT H Al (FT)	INITIA L WIDTH Aiw (FT)	TERMINA L WIDTH Atw (FT)	
□P-1	15	3	9	6	3.8	6.15	
□P-2	24	7	45	27	6.0	33	


ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS. ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND

STANDARD CONSTRUCTION DETAIL #9-1 RIPRAP APRON AT PIPE OUTLET

AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN

THE APRON SHALL BE REPLACED IMMEDIATELY.


WITH FLARED END SECTION OR ENDWALL NOT TO SCALE




NOTES:

ALL COLLARS SHALL BE INSTALLED SO AS TO BE WATERTIGHT. COLLAR SIZE AND SPACING SHALL BE AS INDICATED WITHIN TABLE.

> STANDARD CONSTRUCTION DETAIL #7-16 CONCRETE ANTI-SEEP COLLAR FOR PERMANENT BASINS OR TRAPS NOT TO SCALE






PA DEP EROSION CONTROL MANUAL TABLE 13.1 MAXIMUM SPACING AND MATERIALS FOR TRENCH PLUGS

TRENCH SLOPE (%)	SPACING L (FT)	PLUG MATERIAL
< 5	1000	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
5 - 15	500	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
15 - 25	300	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
25 - 35	200	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
35 - 100	100	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
> 100	50	CEMENT BAGS (WETTED) OR MORTARED STONE
* TOPSOIL MAY NOT BE U	JSED TO FIL	L SACKS

NOTES:
IMPERVIOUS TRENCH PLUGS ARE REQUIRED FOR ALL STREAM, RIVER, WETLAND, OR OTHER WATER BODY CROSSINGS.

STANDARD CONSTRUCTION DETAIL #13-4 TRENCH PLUG INSTALLATION

NOT TO SCALE




ELEVATION VIEW

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON—WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5% FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS. NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

> STANDARD CONSTRUCTION DETAIL #3-16 PUMPED WATER FILTER BAG




1. FENCING SHALL BE INSTALLED AT THE DRIP LINE (MIN. 5 FEET FROM TREE TRUNK) BOARDS SHALL NOT BE NAILED TO TREES DURING CONSTRUCTION. FEEDER ROOTS SHALL NOT BE CUT IN AREA INSIDE THE DRIP LINE 4. THE CONTRACTOR SHALL NOT BE CUI IN AREA INSIDE THE DRIP LINE.

4. THE CONTRACTOR SHALL NOT ENCROACH ONTO AREAS DELINEATED AS TREE PROTECTION. THE STORAGE OF EQUIPMENT OR MATERIALS IN THIS AREA IS STRICTLY FORBIDDEN. THE SILT FENCE ERECTED AT THE TREE PROTECTION LINE SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION PROCESS AND SHALL NOT BE CROSSED.

5. REFER TO PLAN SHEETS FOR LOCATION OF WOODS AND TREES TO REMAIN. ALL TREES TO REMAIN WHICH ARE ADJACENT TO CONSTRUCTION AREAS SHALL BE PROTECTED IN ACCORDANCE WITH THIS DETAIL.

NO CLEARING, EARTHMOVING, OR CONSTRUCTION SHALL COMMENCE PRIOR TO INSTALLATION OF TREE PROTECTION FENCES AROUND ALL EXISTING TREES. 7. A 48 INCH HIGH WOODEN OR PLASTIC FENCE WITH POSTS ON 8 FOOT CENTER TO CENTER (MAXIMUM) SHALL BE INSTALLED AROUND EACH EXISTING TREE PRIOR TO START OF CONSTRUCTION (TYPICAL FOR ALL TREES).

TREE PROTECTION/CONSTRUCTION FENCE DETAIL



NOTES: INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS NOT LOCATED AT A LOW POINT.

PLAN VIEW


ROLLED EARTHEN BERM IN ROADWAY SHALL BE PROVIDED AND MAINTAINED IMMEDIATELY DOWN GRADIENT OF THE PROTECTED INLET UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR TO REMAIN PERMANENTLY.

STONE INLET PROTECTION AND BERM FOR A TYPE M INLET CAN BE USED IN ONE ACRE MAXIMUM DRAINAGE AREA WITH 15 IN. OVERFLOW PIPE AND 4 IN. HEAD. A PERFORATED PLATE WELDED TO A METAL RISER MAY NOT BE SUBSTITUTED FOR THE WIRE MESH. A SLOTTED PLATE WELDED TO THE RISER MAY BE USED IN CONJUNCTION WITH THE WIRE MESH IF CALCULATIONS ARE PROVIDED TO SHOW SUFFICIENT CAPACITY OF THE INLET TO ACCEPT THE PEAK RUNOFF FOR A 2-YEAR STORM EVENT FROM THE TRIBUTARY DRAINAGE AREA. TOP OF PIPE SHALL BE AT LEAST 6 INCHES BELOW ADJACENT ROADWAY IF PONDED WATER WOULD POSE A SAFETY HAZARD TO TRAFFIC. EARTHEN BERM SHALL BE

SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE HEIGHT OF THE STONE. DAMAGED OR CLOGGED INSTALLATIONS SHALL BE REPAIRED OR REPLACED IMMEDIATELY. FOR SYSTEMS DISCHARGING TO HQ OR EV SURFACE WATER, A 6 IN. THICK COMPOST LAYER SHALL BE SECURELY ANCHORED ON OUTSIDE AND OVER TOP OF STONE. COMPOST SHALL MEET THE STANDARDS

IN TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL. DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS. STANDARD CONSTRUCTION DETAIL #4-20

STONE INLET PROTECTION AND BERM - TYPE M INLET NOT TO SCALE



MAXIMUM DRAINAGE AREA = 1/2 ACRE.

INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS.


ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR

AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40

INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS. ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.


DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS. STANDARD CONSTRUCTION DETAIL #4-16


FILTER BAG INLET PROTECTION - TYPE M INLET NOT TO SCALE



SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE HEIGHT OF THE FILTERS. IMMEDIATELY UPON STABILIZATION OF EACH CHANNEL, REMOVE ACCUMULATED SEDIMENT, REMOVE ROCK FILTER, AND STABILIZE DISTURBED AREAS.

STANDARD CONSTRUCTION DETAIL #4-14 ROCK FILTER NOT TO SCALE





BARRIER NO.	LOCATION	SLOPE %	SLOPE LENGTH ABOVE BARRIER (FT)	SIZE (IN)
CFS-1	SW OF RECREATION CENTER	6	165	12
CFS-2	NW OF RECREATION CENTER	12	205	18
CFS-3	N OF RECREATION CENTER	11	189	18
CFS-4	NE OF RECREATION CENTER	10	150	18
CFS-5	NW OF PROJECT SITE	7	189	12
CFS-6	NW OF SOIL STOCKPILE	9	103	12
CFS-7	N OF PROJECT SITE	7	89	12
CFS-8	NE OF MAIN PROJECT SITE	4	77	12
CFS-9	DOWNSLOPE OF SOIL STOCKPILE	30	20	12
CFS-10	N OF CHANNEL 4	20	31	12
CFS-11	NE OF BASIN	20	36	12
CFS-12	N OF BASIN	5	166	12
CFS-13	N OF BASIN SPILLWAY	5	147	12
CFS-14	N OF CHANNEL 3	6	116	12
CFS-15	W OF CHANNEL 3	8	80	12

MATERIAL TYPE	3 MIL HDPE	5 MIL HDPE	5 MIL HDPE	MULT-FILAMENT POLYPROPYLENE (MFPP)	HEAVY DUTY MULT-FILAMENT POLYPROPYLENI (HDMFPP)	
MATERIAL CHARACTERISTICS	PHOTO- DEGRADABLE	PHOTO- DEGRADABLE	BIO- DEGRADABLE	PHOTO- DEGRADABLE	PHOTO- DEGRADABLE	
SOCK DIAMETERS	12" 18"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	
MESH OPENING	3/8"	3/8"	3/8"	3/8"	1/8"	
TENSILE STRENGTH		26 PSI	26 PSI	44 PSI	202 PSI	
ULTRAVIOLET STABILITY % ORIGINAL STRENGTH (ASTM G-155)	23% AT 1000 HR.	23% AT 1000 HR.		100% AT 1000 HR.	100% AT 1000 HR.	
MINIMUM FUNCTIONAL LONGEVITY	6 MONTHS	9 MONTHS	6 MONTHS	1 YEAR	2 YEARS	
	1	TWO-PL	SYSTEMS			
INNER CO	NTAINMENT N	ETTING	HDPE BIAXIAL NET CONTINUOUSLY WOUND FUSION-WELDED JUNCTURES 3/4" X 3/4" MAX. APERTURE SIZE			
	FILTRATION M		COMPOSITÉ POLYPROPYLENE FABRIC (WOVEN LAYER AND NO-WOVEN FLEECE MECHANICALLY FUSED VIA NEEDLE PUNCH) 3/16"APERTURE SIZE			
SOCK FABRICS CO	MPOSED OF BU	JRLAP MAY BE	USED ON PROJ	ECTS LASTING 6 N	MONTHS OR LESS.	

SOLUBLE SALT CONCENTRATION 5.0 dS/m (mmhos/cm) MAXIMUM SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1, AS INDICATED. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2. COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.


25% - 100% (DRY WEIGHT BASIS)

30% - 50% PASS THROUGH 3/8" SIEVE

TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.

COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION. COMPOST FILTER SOCKS SHALL BE REPLACED AFTER THE MINIMUM FUNCTIONAL LONGEVITY, AS INDICATED IN TABLE 4.1, HAS PASSED. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STATES SHALL BE REMOVED. THE MESH SHALL BE CUT OPEN AND REMOVED. THE MULCH CAN BE SPREAD AS A SOIL SUPPLEMENT IN VEGETATED AREAS.

MODIFIED CONSTRUCTION DETAIL #4-1 COMPOST FILTER SOCK NOT TO SCALE



CHANNEL CROSS-SECTION

* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL

AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY. NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL

BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

CHANNEL NO.	LOCATION	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *	STAPLE PATTER N
1	SOUTH OF REC. CENTER	1	1.15	7.9	З	Э	NAG-S75/ VEGETATED	D
2	SOUTH OF MAINT, BLDG,	1	1.08	7.48	3	3	NAG-S75/ VEGETATED	D
3	WEST OF BASIN	3	2	19	4	4	NAG-S75/ VEGETATED	D
4	EAST OF BASIN	3	1.25	11	4	4	NAG-S75/ VEGETATED	D

NOTE: PUMP ANY PONDING WATER ON SITE TO A PUMPED WATER FILTER BAG.

MODIFIED STANDARD CONSTRUCTION DETAIL #6-1 VEGETATED CHANNEL


NOT TO SCALE


NTROL REATION PARTNE NSHIP R SEDIMENT (P WELLNF? EROSION WATER GA


8/26/2024 SCALE: AS NOTED

TAL/DFG CRS DRAWN: JPK P MGR: 1022419.004

COPYRIGHT 2024 SHEET: 22 OF 27









ETAILS EATION PARTNEF ISHIP ', PA CONSTRUCTION DET
GAP WELLNESS RECREA
R GAP ACQUISITIONS PA
SMITHFIELD TOWNSI
MONROE COUNTY, F

TAL/DFG 8/26/2024 CHK: CRS JPK P MGR:









N STORMWATER MANAGEMENT PLASTLNESS RECREATION CENTER CQUISITIONS PARTNERS, LLC
THFIELD TOWNSHIP
NROE COUNTY, PA

TAL/DFG CRS JPK P MGR: COPYRIGHT 2024




CONCRETE PIPE

HDPE, PVC, & METAL PIPE



STANDARD INLET BOX

REFER TO PENNDOT RC-46M, LATEST EDITION FOR ADDITIONAL NOTES & REQUIREMENTS



STRUCTURAL STEEL GRATE BICYCLE SAFE

REFER TO PENNDOT RC-45M & RC-46M, LATEST EDITION

GRATE (STRUCTURAL STEEL SHOWN)
(SEE RC-45M)

-GRADE ADJUSTMENT RING. (SEE RC-45M)

·GRATE (STRUCTURAL STEEL SHOWN) (SEE RC-45M)

TYPE M FRAME

53 3/4" MIN.

SYMMETRICAL

TYPE M FRAME

FERROUS CAST MATERIAL STRUCTURAL STEEL FABRICATION FABRICATION

5/8" MIN-

1 1/4" MIN_¬

--| |---1 1/4" MIN

└5/8″ MIN.

└1 1/4" MIN.

(CAST IRON SHOWN) (SEE RC-45M)

4" MIN. — | -

3" MAX. - - -

1 1/4" MIN. = | |-

POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM) STANDARD NOTES

PERMIT TERMINATION

UPON PERMANENT STABILIZATION OF THE EARTH DISTURBANCE ACTIVITY UNDER \$ 102.22(A)(2) (RELATING TO PERMANENT STABILIZATION), AND INSTALLATION OF BMPS IN ACCORDANCE WITH AN APPROVED PLAN PREPARED AND IMPLEMENTED IN ACCORDANCE WITH §§ 102.4 AND 102.8 (RELATING TO EROSION AND SEDIMENT CONTROL REQUIREMENTS; AND PCSM REQUIREMENTS), THE PERMITTEE OR CO-PERMITTEE SHALL SUBMIT A NOTICE OF TERMINATION TO THE DEPARTMENT OR CONSERVATION

- THE NOTICE OF TERMINATION MUST INCLUDE:
- (1) THE FACILITY NAME, ADDRESS AND LOCATION. (2) THE OPERATOR NAME AND ADDRESS.
- 3) THE PERMIT NUMBER.
- (4) THE REASON FOR PERMIT TERMINATION (5) IDENTIFICATION OF THE PERSONS WHO HAVE AGREED TO AND WILL BE RESPONSIBLE FOR

LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS IN ACCORDANCE WITH § 102.8(M) AND PROOF OF COMPLIANCE WITH § 102.8(M)(2)

PCSM REQUIREMENTS PCSM REPORTING AND RECORDKEEPING. THE PCSM PLAN, INSPECTION REPORTS AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.

LICENSED PROFESSIONAL OVERSIGHT OF CRITICAL STAGES.

LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS.

A LICENSED PROFESSIONAL OR A DESIGNEE SHALL BE PRESENT ONSITE AND BE RESPONSIBLE DURING CRITICAL STAGES OF IMPLEMENTATION OF THE APPROVED PCSM PLAN. THE CRITICAL STAGES MAY INCLUDE THE INSTALLATION OF UNDERGROUND TREATMENT OR STORAGE BMPS, STRUCTURALLY ENGINEERED BMPS, OR OTHER BMPS AS DEEMED APPROPRIATE BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.

NOTES:

1. CONSTRUCTION REQUIREMENTS:

YIELD STRENGTH OF 400 MPa (60,000 PSI).

D. CLEAR COVER FOR STEEL:

• WALLS: PRE CAST 1'-1/2"

• FOOTINGS: PRE CAST 2' TOP BARS

8. PROVIDE WEEP HOLE ON INLET BOXES WHEN REQUIRED.

RUBBER FLEXIBLE CONNECTORS.

__1 1/4" MIN

└ 1 1/4″ MIN.

TYPE M INLET FRAME

REFER TO PENNDOT RC-45M, LATEST EDITION


∟3″ мах.

THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL. WHICH READS AS FOLLOWS: I (NAME) DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA.C.S.A. § 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THE ACCOMPANYING RECORD DRAWINGS ACCURATELY REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN

CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION AND THAT THE PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSM PLAN, ALL APPROVED PLAN CHANGES AND ACCEPTED CONSTRUCTION PRACTICES."

(1) THE PERMITTEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED (2) THE PERMITTEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED

PCSM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPONSIBLE FOR THE



A. CONSTRUCT IN ACCORDANCE WITH PUBLICATION 408, SECTIONS 605, 606 AND 714; AND AS MODIFIED HEREIN.

C. PROVIDE STEEL REINFORCEMENT IN ACCORDANCE WITH PUBLICATION 408, SECTION 709, PROVIDE MINIMUM

1'-1/2" BOTTOM BARS

TYPE 'C' INLET IS DESIGNATED FOR INSTALLATION WITH NON-MOUNTABLE CURBS.

3. THE SELECTION OF COMPONENTS TO ACHIEVE A SPECIFIED INLET ASSEMBLY IS THE CONTRACTORS RESPONSIBILITY

4. USE PRE CAST CONCRETE OR STEEL GRADE ADJUSTMENT RINGS WHEN REQUIRED. (REHABILITATION PROJECTS)

5. FOR WALL REINFORCEMENT, BOTH DIRECTIONS, USE 10"MINIMUM EACH WAY, EACH FACE 6" MAXIMUM SPACING.

7. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED. U.S. CUSTOMARY UNITS IN PARENTHESIS.

6. FOR FOOTING REINFORCEMENT, TOP AND BOTTOM, USE #4 BARS AT 12" CENTER EACH WAY OR 17"/M2 WWF 6"

9. PIPES MAY BE CONNECTED TO DRAINAGE STRUCTURES (PRE CAST INLETS. ETC.) WITH MORTAR OR WATERTIGHT

< → 1/2" MIN.

SECTION D-D

(STRUCTURAL STEEL)

INSIDE DIRECTION

TYPE 'M' INLET IS DESIGNATED FOR INSTALLATION IN MEDIAN AREAS AND MOUNTABLE CURBS.

1'-1/2" SIDE COVER

2. EACH TYPE OF INLET SHOWN IS SUITED FOR A PARTICULAR SITUATION AS FOLLOWS:

SECTION C-C

(FERROUS CAST MATERIAL)

INSIDE DIRECTION

*CORNER CONFIGURATION DETAILS ARE THE FABRICATOR'S RESPONSIBILITY AND ARE APPROVED BY THE INSPECTOR.

INFILTRATION BASIN

TYPICAL INFILTRATION BASIN CONSTRUCTION SEQUENCE:


- NOTE: ENGINEER SHALL BE NOTIFIED AND ON-SITE FOR STEPS 4, 5, AND 6. PROTECT INFILTRATION BASIN AREA FROM COMPACTION PRIOR TO INSTALLATION.
- CONSTRUCTION VEHICLES SHALL NOT DRIVE OVER INFILTRATION BASIN AREA BEFORE, DURING, OR AFTER CONSTRUCTION, EXCEPT AS NEEDED FOR POLLUTANT REMEDIATION.
- . INSTALL AND MAINTAIN PROPER EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION TO PREVENT SEDIMENT FROM ENTERING THE INFILTRATION BASIN DURING CONSTRUCTION. PIPES AND INLETS SHALL BE VACUUMED, RATHER THAN FLUSHED INTO
- 3. INSTALL BASIN OUTFLOW PIPES AND STRUCTURES.
- 4. EXCAVATE INFILTRATION BASIN BOTTOM TO AN UNCOMPACTED SUBGRADE FREE FROM DEBRIS AND STONES LARGER THAN 2 INCHES IN ANY DIRECTION. DO NOT COMPACT SUBGRADE. CONSTRUCTION VEHICLES SHALL NOT DRIVE WITHIN THE LIMITS OF THE BASIN BOTTOM (WITHIN 2 VERTICAL FEET OF SUBGRADE ELEVATION), AND EXCAVATION SHALL BE COMPLETÈD FROM THE SIDES OF THE BASIN. CONSTRUCT BERM IN COMPACTED LIFTS.
- 5. HALT EXCAVATION AND NOTIFY ENGINEER IMMEDIATELY IF EVIDENCE OF SINKHOLE ACTIVITY OR PINNACLES OF CARBONATE BEDROCK ARE ENCOUNTERED IN THE BIO-RETENTION AREA.
- 6. SCARIFY SUBGRADE TO LOOSEN TOP 4-6 INCHES. SPREAD MINIMUM 6 INCHES OF IMPORTED TOPSOIL. SEED AND STABILIZE. ADD BASIN PLANTINGS PER PLANS. STABILIZE BASIN SLOPES WITH EROSION CONTROL MATTING.
- PROTECT BIO-RETENTION AREAS FROM SEDIMENT AT ALL TIMES DURING CONSTRUCTION. DO NOT REMOVE INLET PROTECTION OR OTHER EROSION AND SEDIMENT CONTROL MEASURES UNTIL SITE IS FULLY STABILIZED.
- WATER SEEDING/GRASS ONCE EVERY TWO DAYS IN THE EARLY MORNING OR EVENING, PROVIDING ONE INCH OF WATER PER WEEK UNTIL 70% UNIFORM GRASS COVER IS ESTABLISHED.
- TYPICAL INFILTRATION BASIN MAINTENANCE:
- CATCH BASINS AND INLETS (UPGRADIENT OF INFILTRATION BASIN) SHOULD BE INSPECTED AND CLEANED AT LEAST TWÒ TIMES PER YEAR AND AFTER RUNÓFF EVENTS.
- THE VEGETATION ALONG THE SURFACE OF THE INFILTRATION BASIN SHOULD BE MAINTAINED IN GOOD CONDITION, AND ANY BARE SPOTS RE-VEGETATED AS SOON AS
- . VEHICLES SHOULD NOT BE PARKED OR DRIVEN ON AN INFILTRATION BASIN, AND CARE SHALL BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS.
- INSPECT THE BASIN AFTER RUNOFF EVENTS AND MAKE SURE THAT RUNOFF DRAINS DOWN WITHIN 72 HOURS. MOSQUITOES SHOULD NOT BE A PROBLEM IF THE WATER DRAINS IN 72 HOURS.MOSQUITOES REQUIRE A CONSIDERABLY LONG BREEDING PERIOD WITH RELATIVELY
- . ALSO INSPECT FOR ACCUMULATION OF SEDIMENT, DAMAGE TO OUTLET CONTROL STRUCTURES, EROSION CONTROL MEASURES, SIGNS OF WATER CONTAMINATION/SPILLS, AND SLOPE STABILITY IN THE BERMS.
- 6. MOW ONLY AS APPROPRIATE FOR VEGETATIVE COVER SPECIES.
- REMOVE ACCUMULATED SEDIMENT FROM BASIN AS REQUIRED. RESTORE ORIGINAL CROSS-SECTION AND INFILTRATION RATE. PROPERLY DISPOSE OF SEDIMENT.

SOIL RESTORATION NOTES

STATIC WATER LEVELS.

1. BEFORE THE TIME THE COMPOST IS PLACED AND PREFERABLY WHEN EXCAVATION IS COMPLETE, THE SUBSOIL SHALL BE IN A LOOSE, FRIABLE CONDITION TO A DEPTH OF 20 INCHES BELOW FINAL TOPSOIL GRADE AND THERE SHALL BE NO EROSION RILLS OR WASHOUTS IN THE SUBSOIL SURFACE EXCEEDING 3 INCHES IN DEPTH.

- 2. TO ACHIEVE THIS CONDITION, SUB-SOILING, RIPPING, OR SCARIFICATION OF THE SUBSOIL WILL BE REQUIRED WHEREVER THE SUBSOIL HAS BEEN COMPACTED BY EQUIPMENT OPERATION OR HAS BECOME DRIED OUT AND CRUSTED AND WHERE NECESSARY TO OBLITERATE FROSION RILLS. SUB-SOLING SHALL BE REQUIRED TO REDUCE SOIL COMPACTION IN ALL AREAS WHERE PLANT ESTABLISHMENT IS PLANNED. SUB—SOILING SHALL BE PERFORMED BY
- THE PRIME OR EXCAVATING CONTRACTOR AND SHALL OCCUR BEFORE COMPOST PLACEMENT 3. SPREAD 2—3 INCHES OF APPROVED COMPOST ON EXISTING SOIL. TILL ADDED SOIL INTO EXISTING SOIL WITH ROTARY ILLER THAT IS SET TO A DEPTH OF 6 INCHES. ADD AN ADDITIONAL 4 INCHES OF APPROVED COMPOST TO BRING
- THE AREA UP TO GRADE 4. AFTER PERMANENT PLANTING/SEEDING, 2-3 INCHES OF COMPOST BLANKET WILL BE APPLIED TO ALL AREAS NOT PROTECTED BY GRASS OR OTHER PLANTS.




COMPACTED TOPSOIL/IN-SITU SOIL WITHIN THE BOTTOM OF THE BMP BOTTOM WILL REQUIRE SOILS RESTORATION. AS FOLLOWS:

SOILS RESTORATION SHALL TAKE PLACE ONLY WHEN THE SOIL IS DRY THE SOIL SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES. SOIL SHALL BE SCARIFIED IN A 2-DIRECTIONAL GRID PATTERN. THE SCARIFIED GRID SHALL BE SPACED A MAXIMUM OF 3 FEET APART.

IMMEDIATELY AFTER SCARIFYING IS COMPLETE, ADD AMENDED SOILS AND THEN THE DISTURBED AREAS SHALL BE SEEDED AND MULCHED.

<u>AMENDED SOILS DETAIL</u>

POST-CONSTRUCTION STORMWATER MANAGEMENT WATER QUALITY CONTROL SEED MIXTURE



MAINTENANCE PERFORMANCE

TASK	FREQUENCY
1. Inspect for sediment accumulation	Annually
2. Remove accumulated sediment	Every 5-10 years
3. Inspect for debris (dead vegetation and trash)	Early spring, fall and after major storms
4. Inspect for bank erosion	Early spring, fall and after major storms
5. Clear debris/repair erosion areas	As needed
6. Rake out dead vegetation	Annually, early spring
7. Inspect and remove invasive plants	Annually — July
8. Mow to a height of 6"	Annually — late fall
9. Inspect during wet weather and compare to as—built plans (by prof. engineer)	Annually
10. Adjust/correct as determined by wet weather inspection	As needed
11. Maintain records on all activities	Annually
12. Conduct emergency inspections by prof. engineer	As needed

MAINTENANCE: THE OWNER WILL MOW THE SWALES AND BASIN AREAS TO WITHIN 6 INCHES HIGH, ONCE A YEAR. IN THE FALL WHEN CONDITIONS PERMIT. THE OWNER SHALL MAINTAIN AND PERIODICALLY CHECK THE BASIN AND SWALES TO OBSERVE ANY EROSION PROBLEMS HAT MAY BE DEVELOPING. ANY DAMAGED AREAS SHALL BE REPAIRED IMMEDIATELY. ANY TRASH/DEBRIS SHALL BE REMOVED FROM PLANTINGS. ANNUALLY CHECK FOR INVASIVE PLANT SPECIES AND REMOVE TO ENCOURAGE A NATIVE PLANT SPECIES HABITAT.

STORMWATER BMP CONSTRUCTION NOTES

- SEDIMENT REMOVED FROM BMPs SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS, OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES.
- 2. TRASH THAT IS REMOVED FROM ANY OF THE CONTROL DEVICES SHALL BE DISPOSED OF AT AN APPROVED MUNICIPAL DISPOSAL AREA.
- 3. ALL CATCH BASINS AND INLETS SHOULD BE INSPECTED AND CLEANED AT LEAST 2 TIMES

CRITICAL STAGES OF PCSM IMPLEMENTATION

CRITICAL STAGES OF POST-CONSTRUCTION STORMWATER MANAGEMENT PLAN (PCSM) IMPLEMENTATION SHOULD BE OBSERVED AND/OR INSPECTED BY A LICENSED PROFESSIONAL OR DESIGNEE. THESE CRITICAL STAGES INCLUDE THE CONSTRUCTION OF CRITICAL BMPS AND ANY OTHER ACTIVITIES AS MAY BE REQUIRED BY THE DEP OR CONSERVATION DISTRICT. THESE CRITICAL BMPS INCLUDE:

- CONSTRUCTION OF INFILTRATION BASIN INSTALLATION OF AMENDED SOILS
- VERIFY TRIBUTARY AREAS
- A LICENSED PROFESSIONAL QUALIFIED TO OBSERVE AND INSPECT THE ABOVE SHOULD BE CONTACTED AT LEAST THREE (3) DAYS PRIOR TO EXECUTION OF ANY CRITICAL STAGES.

CONSTRUCTION, OWNERSHIP, OPERATIONS, & MAINTENANCE

POST CONSTRUCTION BEST MANAGEMENT PRACTICES (BMP) AS PROPOSED HEREON, SHALL BE OWNED, OPERATED, AND MAINTAINED AS FOLLOWS:

LANCE PULSE, FACILITY DIRECTOR P.O. BOX 244 DELAWARE WATERGAP, PA. 18327 LPULSE@WATERGAPWELLNESS.COM 570-269-8977

OPERATIONS AND MAINTENANCE RESPONSIBILITIES SHALL BE TRANSFERRED TO ANY SUBSEQUENT OWNER(S). UPON TRANSFERENCE, PARTY CURRENTLY RESPONSIBLE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS PART OF THIS APPROVED PCSM PLAN TO THE NEW OWNER.

BMPS, AS PROPOSED, SHALL BE OPERATED & MAINTAINED IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS AND IN ACCORDANCE WITH THE FOLLOWING SPECIFICATIONS:

PCSM LONG TERM OPERATIONS AND MAINTENANCE REQUIREMENTS

UNTIL THE PERMITTEE OR CO-PERMITTEE HAS RECEIVED WRITTEN APPROVAL OF A NOTICE OF TERMINATION, THE PERMITTEE OR CO-PERMITTEE WILL REMAIN RESPONSIBLE FOR COMPLIANCE WITH THE PERMIT TERMS AND CONDITIONS INCLUDING LONG-TERM OPERATION AND MAINTENANCE OF ALL PCSM BMPS ON THE PROJECT SITE AND IS RESPONSIBLE FOR VIOLATIONS OCCURRING ON THE PROJECT SITE. THE DEPARTMENT OR CONSERVATION DISTRICT WILL CONDUCT A FINAL INSPECTION AND APPROVE OR DENY THE NOTICE OF TERMINATION

THE PERMITTEE OR CO-PERMITTEE SHALL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS UNLESS A DIFFERENT PERSON IS IDENTIFIED IN THE NOTICE OF TERMINATION AND HAS AGREED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM

FOR ANY PROPERTY CONTAINING A PCSM BMP, THE PERMITTEE OR CO-PERMITTEE SHALL RECORD AN INSTRUMENT WITH THE RECORDER OF DEEDS WHICH WILL ASSURE DISCLOSURE OF THE PCSM BMP AND THE RELATED OBLIGATIONS IN THE ORDINARY COURSE OF A TITLE SEARCH OF THE SUBJECT PROPERTY. THE RECORDED INSTRUMENT MUST IDENTIFY THE PCSM BMP, PROVIDE FOR NECESSARY ACCESS RELATED TO LONG-TERM OPERATION AND MAINTENANCE FOR PCSM BMPS AND PROVIDE NOTICE THAT THE RESPONSIBILITY FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP IS A COVENANT THAT RUNS WITH THE LAND THAT IS BINDING UPON AND ENFORCEABLE BY SUBSEQUENT GRANTEES, AND PROVIDE PROOF OF FILING WITH THE NOTICE OF TERMINATION UNDER § 102.7(B)(5) (RELATING TO PERMIT TERMINATION

THE PERSON RESPONSIBLE FOR PERFORMING LONG-TERM OPERATION AND MAINTENANCE MAY ENTER INTO AN AGREEMENT WITH ANOTHER PERSON INCLUDING A CONSERVATION DISTRICT NONPROFIT ORGANIZATION, MUNICIPALITY, AUTHORITY, PRIVATE CORPORATION OR OTHER PERSON. TO TRANSFER THE RESPONSIBILITY FOR PCSM BMPS OR TO PERFORM LONG-TERM OPERATION AND MAINTENANCE AND PROVIDE NOTICE THEREOF TO THE DEPARTMENT.

A PERMITTEE OR CO-PERMITTEE THAT FAILS TO TRANSFER LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP OR OTHERWISE FAILS TO COMPLY WITH THIS REQUIREMENT SHALL REMAIN JOINTLY AND SEVERALLY RESPONSIBLE WITH THE LANDOWNER FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS LOCATED ON THE PROPERTY.

CLEAN FILL NOTES

1. IF THE SITE WILL NEED TO IMPORT OR EXPORT MATERIAL FROM THE SITE, THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND DETERMINATION OF CLEAN FILL WILL REST WITH (CONTRACTOR).


- 2. CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE).
- 3. CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE STILL QUALIFIES AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- 4. ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS.
- 5. ENVIRONMENTAL DUE DILIGENCE: THE APPLICANT MUST PERFORM ENVIRONMENTAL DUE DILIGENCE TO DETERMINE IF THE FILL MATERIALS ASSOCIATED WITH THE PROJECT QUALIFY AS CLEAN FILL. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- 6. FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE. THESE REGULATIONS ARE AVAILABLE ON-LINE AT WWW.PACODE.COM.


RECYCLING OR DISPOSAL OF MATERIALS

RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THIS PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH PA DEP RULES AND REGULATIONS. SEDIMENT REMOVED FROM BMPS AND STORMWATER FACILITIES SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE

SWALES AND IMMEDIATELY STABILIZED OR PLACED IN TOPSOIL STOCKPILES. ON-GOING PROJECT WASTES INCLUDE, BUT MAY NOT BE LIMITED TO, THE FOLLOWING:

- SEDIMENT • TRASH/DEBRIS
- VEGETATION CLIPPINGS AS MAY RESULT FROM MAINTENANCE







MANAGEMENT I REATION CENTE PARTNERS, LLO

EATION PARTNE ISHIP LLNESS RECRE CQUISITIONS PA HFIELD TOWNS NROE COUNTY, CONSTRUCTION ST VATER GAP WELL WATER GAP ACC SMITH MONF

> 8/26/2024 TAL/DFG SCALE: AS NOTED CRS DRAWN: JPK P MGR: 1022419.004

SHEET: 26 OF 27

