# PRELIMINARY MAJOR LAND DEVELOPMENT PLANS WATER GAP WELLNESS RECREATION CENTER

WATER GAP ACQUISITIONS PARTNERS, LLC SMITHFIELD TOWNSHIP MONROE COUNTY, PA

> AUGUST 26, 2024 LAST REVISED MARCH 28, 2025

## **Plans Prepared by:**



- **Q** 272.200.2050
- barryisett.com

525 Main Street, Suite 200 Stroudsburg, PA 18360

# IMPROVEMENTS DELAWARE WATER GAD NATIONAL RECREATION AREA

Location Map USGS: STROUDSBURG QUADRANGL SCALE: 1"=2000'

PLAN DESIGNATION	PLAN TITLE	PLAN NO.	LAST R
* CS-1	COVER SHEET	1 of 27	3/28/20
SCM-1	SITE CONTEXT MAP	2 of 27	3/28/20
* SP-1	SITE DEVELOPMENT PLAN	3 of 27	3/28/20
* SP-2	SITE DEVELOPMENT PLAN	4 of 27	3/28/20
MER-1	MASTER EXISTING RESOURCES & SITE ANALYSIS PLAN	5 of 27	3/28/20
ER-1	EXISTING RESOURCES & SITE ANALYSIS PLAN	6 of 27	3/28/20
ER-2	EXISTING RESOURCES & SITE ANALYSIS PLAN	7 of 27	3/28/20
ER-3	EXISTING RESOURCES & SITE ANALYSIS PLAN	8 of 27	3/28/20
GP-1	GRADING PLAN	9 of 27	3/28/20
GP-2	GRADING PLAN	10 of 27	3/28/20
UP-1	UTILITY PLAN	11 of 27	3/28/20
UP-2	UTILITY PLAN	12 of 27	3/28/20
PP-1	STORM SEWER PLAN & PROFILES	13 of 27	3/28/20
PP-2	STORM SEWER PLAN & PROFILES	14 of 27	3/28/20
PP-3	STORM SEWER PLAN & PROFILES	15 of 27	3/28/20
PP-4	PLAN & PROFILES	16 of 27	3/28/20
LA-1	LANDSCAPING PLAN	17 of 27	3/28/20
LI-1	LIGHTING PLAN	18 of 27	3/28/20
ES-1	EROSION & SEDIMENT CONTROL PLAN	19 of 27	3/28/20
ES-2	EROSION & SEDIMENT CONTROL PLAN	20 of 27	3/28/20
ESD-1	EROSION & SEDIMENT CONTROL DETAILS	21 of 27	3/28/20
ESD-2	EROSION & SEDIMENT CONTROL DETAILS	22 of 27	3/28/20
DE-1	CONSTRUCTION DETAILS	23 of 27	3/28/20
* PC-1	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN	24 of 27	3/28/20
* PC-2	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN	25 of 27	3/28/20
* PCD-1	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS	26 of 27	3/28/20
* PCD-2	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS	27 of 27	3/28/20

ALL DRAWINGS WITHIN THIS PLAN SET SHALL BE REVIEWED AND UTILIZED.

### **NOTIFICATION**

THE DEVELOPER SHALL, AT LEAST FIFTEEN (15) CALENDAR DAYS PRIOR TO THE INITIATION OF CONSTRUCTION OF ANY REQUIRED IMPROVEMENTS, SUBMIT TO THE TOWNSHIP A SCHEDULE OF CONSTRUCTION FOR ALL REQUIRED IMPROVEMENTS, INCLUDING THE TIMING OF THE DEVELOPMENT OF ANY PROPOSED SECTIONS. THI SCHEDULE MAY BE REVISED FROM TIME TO TIME UPON MUTUAL AGREEMENT OF THE APPLICANT ENGINEER AND THE TOWNSHIP ENGINEER. SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO NOTIFY THE

### AMERICANS WITH DISABILITIES ACT (ADA)

APPROPRIATE INSPECTION CONSULTANT FOR THE TOWNSHIP OR DESIGNED AUTHORITY AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO COMMENCING A

ONSTRUCTION ACTIVITY.

THIS PERMIT AND/OR PLAN HAS NOT BEEN REVIEWED TO DETERMINE ITS COMPLIANCE WITH TITLE III OF THE AMERICANS WITH DISABILITIES ACT OF 1990 (ADA) WHICH PROHIBITS DISCRIMINATION ON THE BASIS OF DISABILITY IN PUBLIC ACCOMMODATIONS AND COMMERCIAL FACILITIES. COMPLIANCE WITH TITLE III OF THIS ACT WITH REGARD TO PUBLIC ACCOMMODATIONS AND COMMERCIAL FACILITIES IS THE RESPONSIBILITY OF THE APPLICANT/OWNER.

THE LAND DEVELOPMENT AS SUBMITTED AND AS BUILT ACCORDING TO THE INFORMATION INCLUDED IN THE CURRENT DESIGN WILL MEET THE ACCESSIBILITY REQUIREMENTS AS EXISTING UNDER THE CURRENT BUILDING CODES ESTABLISHED N SMITHFIELD TOWNSHIP

### TOWNSHIP LIMITED REVIEW STATEMENT

THIS PLAN HAS BEEN REVIEWED BY THE TOWNSHIP STAFF AND TOWNSHIP ENGINEER FOR CONSISTENCY WITH MUNICIPAL REGULATIONS AND ORDINANCES RELATING TO LAND USAGE AND DIMENSIONAL REQUIREMENTS OF ZONING. INVESTIGATIONS REGARDING PERIPHERAL LAND AND PLAN ISSUES WHICH ARE NOT REQUIRED AS PART OF A REVIEW PROCESS SUCH AS CLARITY OF TITLE SUBSURFACE CONDITIONS INCLUDING BUT NOT LIMITED TO, SOIL AND WATER QUALITY, AND HISTORIC AND ARCHEOLOGICAL ISSUES, OR SUCH OTHER ISSUES (AS APPROPRIATE) THAT MAY AFFECT THE MERCHANTABILITY OF THE LAND, HAVE NOT BEEN INVESTIGATED OR REVIEWED BY THE TOWNSHIP ENGINEER MAKE NO REPRESENTATION OR WARRANTY CONCERNING THESE ISSUES. WHICH SHOULD BE ADDRESSED BY QUALIFIED PROFESSIONALS, COMMISSIONED BY THE DEVELOPER AND/OR LAND OWNER(S) AS APPROPRIATE, AND ENGAGED IN THE APPROPRIATE FIELD OF PRACTICE.

SURVEYOR'S CERTIFICATION HEREBY CERTIFY THAT THIS PLAN REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECT SUPERVISION AND THAT THE DIMENSIONAL DETAILS ARE CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ENGINEER'S CERTIFICATION HEREBY CERTIFY THAT THE INFORMATION CONTAINED IN THE ACCOMPANYING PLANS, SPECIFICATIONS AND REPORTS HAS BEEN PREPARED N ACCORDANCE WITH ACCEPTED ENGINEERING PRACTICES, IS TRUE AND CORRECT IN ALL DETAILS TO THE BEST OF MY KNOWLEDGE AND BELIEF.

(ENGINEER SIGNATURE)

<u>SMITHFIELD TOWNSHIP PLANNING COMMISSION</u> CERTIFICATE OF REVIEW AND RECOMMENDATION AT A PUBLIC MEETING HELD ON THE PLANNING COMMISSION OF SMITHFIELD TOWNSHIP REVIEWED AND BY A MOTION, DULY CARRIED, DOES HEREBY RECOMMEND APPROVAL OF THIS LAND DEVELOPMENT PLAN FOR THE PROPERTY AS SHOWN HEREON.

SMITHFIELD TOWNSHIP BOARD OF SUPERVISORS CERTIFICATE OF REVIEW AND APPROVAL

AT A PUBLIC MEETING HELD ON \_\_\_\_\_\_, 2025, THE BOARD OF SUPERVISORS OF SMITHFIELD TOWNSHIP REVIEWED AND BY A MOTION, DULY CARRIED, DOES HEREBY APPROVE THIS LAND DEVELOPMENT

SUPERVISOR

CERTIFICATION OF ACCURACY AND COMPLETENESS

AS ALL RELATED DRAWINGS AND DOCUMENTS SUBMITTED HEREWITH ARE TO TH BEST OF MY KNOWLEDGE, IN CONFORMITY WITH ENGINEERING, ZONING, BUILDING, SANITARY AND OTHER APPLICABLE TOWNSHIP ORDINANCES AND REGULATIONS, AND ANY AREAS OF NONCONFORMANCE HAVE BEEN DETAILED, ALONG WITH REASONS FOR REQUESTING MODIFICATIONS TO TOWNSHIP STANDARDS

SIGNATURE OF APPLICANT/DEVELOPER

CERTIFICATION OF OWNERSHIP AND ACKNOWLEDGMENT OF PLAN

COMMONWEALTH OF PENNSYLVANIA

S THE \_\_\_\_\_ DAY OF \_\_\_\_,
\_\_\_\_, BEFORE ME, THE UNDERSIGNED OFFICERS, PERSONALLY APPEARED

WHO BEING DULY SWORN, ACCORDING TO LAW, DOTH DEPOSE AND SAY THAT THEY ARE THE OWNERS OF THE PROPERTY SHOWN AND DEPICTED ON THIS PLAN THAT THIS LAND DEVELOPMENT PLAN WAS MADE AT THEIR DIRECTION, AND THAT

ACCORDING TO LAW.

SIGNATURE OF PRESIDENT SIGNATURE OF SECRETARY

SIGNATURE OF NOTARY PUBLIC

MY COMMISSION EXPIRES: \_

MONROE COUNTY PLANNING COMMISSION REVIEW

THE SMITHFIELD TOWNSHIP ENGINEER

RECORDER OF DEEDS CERTIFICATION

RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS, IN MONROE COUNTY, PENNSYLVANIA, IN SUBDIVISION BOOK \_ DLUME \_\_\_\_\_, PAGE \_\_\_\_. WITNESS MY HAND AND SEAL OF THE OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ A.D. 20\_\_\_.

RECORDER OF DEEDS

WAIVERS REQUESTED

SITE DATA

DEED BOOK:

TOTAL AREA:

SEWER:

WATER:

NUMBER OF LOTS: ONE (1)

BENCHMARK ( BM)

ZONING DATA

PROPOSED USE:

ELEVATION: 555.39 NAD83 DATUM.

MINIMUM LOT AREA: 50,000 SF

MINIMUM LOT WIDTH: 150 FEET

MINIMUM LOT DEPTH: 200 FEET

BUILDING HEIGHT: 35 FEET

MAX. IMPERVIOUS COVERAGE:

MINIMUM YARDS (BUILDING SETBACKS):

MAX. BUILDING LOT COVERAGE: 20%

EXISTING BUILDINGS COVERAGE 1.43%

PROPOSED BUILDINGS COVERAGE 1.78%

PROPOSED IMPERVIOUS COVERAGE 6.50%

APPROPRIATE MUNICIPAL OFFICIAL.

PARKING DATA

PARKING REQUIRED

PARKING REQUIREMENTS

SMITHFIELD TWP PROPERTY AREA 51.29 AC.

FRONT: 35 FEET

REAR: 25 FEET

SIDE: 30 FEET

TAX MAP:

SUBDIVISION AND LAND DEVELOPMENT ORDINANCE:

1. SALDO SECTIONS 22-1301.6.B.(5) - OUTLET BOX

5. SALDO SECTIONS 22-603.1.D.(7) - MONUMENTATION

THE FOLLOWING WAIVERS ARE BEING REQUESTED FROM THE SMITHFIELD TOWNSHIP

2. SALDO SECTIONS 22-1301.7.L.(1) - OUTLET PIPES SHALL BE RCP

OWNER/DEVELOPER: WATER GAP ACQUISITIONS PARTNERS, LLC

PHONE: 203-524-3039

WATER GAP WELLNESS

296 MOUNTAIN ROAD

D.B.V. 2418, PG. 6739

16-9-1-26

68.35 AC.

ON-SITE

ON-SITE

DRIVEWAY ENDS AND THE GRAVEL LANE BEGINS.

16731000755147

STROUDSBURG, PA 18360

P.O. BOX 244

3. SALDO SECTIONS 22-1301.7.Q.(2) - STORM PIPES SHALL BE 18 INCHES

4. SALDO SECTIONS 22-603.1.D.(1) - COMPLETE OUTLINE SURVEY OF PROPERTY

DELAWARE WATER GAP, PA 18327

IRON PIN LOCATED APPROXIMATELY 53.4 FEET FROM THE SOUTHEAST CORNER OF

THE EXISTING GARAGE AND APPROXIMATELY 20.6 FEET FROM THE LIGHT STANDARD

LOCATED ALONG THE SOUTHERN PORTION OF THE PROPERTY WHERE THE PRIVATE

ZONING DISTRICT: R-1: LOW DENSITY RESIDENTIAL ON-SITE SEWER AND WATER

ACCESSORY BUILDING FOR INN AND CONFERENCE CENTER

INN AND CONFERENCE CENTER

ZONING DATA PROVIDED IS BASED ON AN INTERPRETATION OF THE ZONING

TOTAL EXISTING = 52 SPACES

TOTAL PROVIDED = 52 SPACES

THE RECREATION CENTER IS AN ACCESSORY USE TO THE INN AND WILL NOT ADD

ANY ADDITIONAL GUESTS OR GUEST ROOMS, THEREFORE NO ADDITIONAL PARKING

WILL BE REQUIRED, IN ACCORDANCE WITH ZO SECTION 402.2 AND SCHEDULE II

ORDINANCE BY THE PLAN PREPARER AND IS SUBJECT TO CONFIRMATION BY THE

4 PARKING SPACES FOR EVERY 3 SLEEPING ROOMS

48 TOTAL ROOMS / 3 ROOMS X 4 SPACES = 64 SPACES

- **GENERAL NOTES** 1. CONTRACTOR SHALL NOTIFY THE PENNSYLVANIA ONE-CALL SYSTEM NO LESS THAN THREE DAYS AND NO GREATER THAN TEN DAYS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- 2. CONTRACTOR SHALL VERIFY THE LOCATIONS AND ELEVATIONS OF ALL EXISTING UTILITIES AND
- 3. THE CONTRACTOR SHALL CONDUCT EXPLORATORY EXCAVATIONS AND LOCATE EXISTING UNDERGROUND UTILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS IF NECESSARY. CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF ANY DISCREPANCIES IN UTILITY LINE LOCATIONS ARE FOUND.
- 4. CONTRACTOR SHALL COORDINATE ALL WORK PERFORMED WITH THE APPROPRIATE UTILITY COMPANY OR AUTHORITY AND WITH ALL UTILITIES TO ENSURE ALL UTILITY SERVICES SERVE ALL UTILITY CUSTOMERS FOR CONTINUOUS FACILITY OPERATIONS OF ALL UTILITY CUSTOMERS. CONTRACTOR SHALL REWORK ALL UTILITY SERVICES INCLUDING PROVIDING TEMPORARY UTILITY SERVICES UNTIL PERMANENT UTILITY SERVICES ARE PROVIDED.
- 5. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO PUBLIC/PRIVATE PROPERTY AS A RESULT OF CONSTRUCTION ACTIVITIES.
- 6. CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS.
- 7. CONTRACTOR SHALL ENSURE THE SAFETY OF THE GENERAL PUBLIC, EXISTING STRUCTURES, AND OTHER PUBLIC AND PRIVATE PROPERTY
- 8. SITE SAFETY AND MAINTENANCE IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 9. CONTRACTOR IS RESPONSIBLE TO KEEP EXISTING ROADWAYS. PARKING AREAS AND LOCAL ROADS FREE OF CONSTRUCTION MATERIALS. ANY DIRT OR DEBRIS TRACKED ON TO SUCH AREAS WILL BE
- 10. THE CONTRACTOR IS RESPONSIBLE FOR BACKFILLING ALL TRENCHES, FENCING OFF CONSTRUCTION AREAS AND REMOVING UNSUITABLE MATERIAL AND DEBRIS FROM THE CONSTRUCTION SITE.
- 11. CONSTRUCTION CREWS, VEHICLES AND ACTIVITIES SHALL NOT INTERFERE WITH NORMAL OPERATIONS OF THE FACILITY. DESIGNATED PARKING AREAS SHALL BE ESTABLISHED AND USED
- 12. CONSTRUCTION VEHICLES, MATERIALS OR ACTIVITIES SHALL NOT INTERFERE WITH PUBLIC ACCESS EXCEPT WHERE SHOWN ON THE PLANS. CONTROL VEHICULAR PARKING TO PREVENT INTERFERENCE WITH PUBLIC TRAFFIC AND PARKING, ACCESS BY EMERGENCY VEHICLES, AND OWNER'S
- 13. PREVENT PARKING ON OR ADJACENT TO ACCESS ROADS OR IN NON-DESIGNATED AREAS. 14. THE CONTRACTOR SHALL REMOVE ALL DEBRIS AND FLUSH OUT EXISTING AND PROPOSED STORM SEWER SYSTEMS WITHIN THE PROJECT AREA UPON COMPLETION OF CONSTRUCTION.

15. TRANSPORT, HANDLE, STORE AND PROTECT PRODUCTS IN ACCORDANCE WITH MANUFACTURER'S

- 16. PROTECT TREES, PLANT GROWTH, AND FEATURES DESIGNATED TO REMAIN, AS FINAL
- 17. PROTECT BENCH MARKS, (SURVEY CONTROL POINTS, AND EXISTING STRUCTURES) FROM DAMAGE OR DISPLACEMENT. CONTRACTOR TO REPLACE BENCHMARKS DISTURBED. 18. STAGING AND STOCKPILE AREAS WILL BE LIMITED TO ONLY THE AREAS NOTED ON THE PLANS.

STOCKPILING OF MATERIALS ON RIVERSIDE OF LEVEE OR SHEETPILING SHALL BE AT THE

- CONTRACTORS RISK. ANY LOSS OF MATERIAL SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. STOCKPILE IN SUFFICIENT QUANTITIES TO MEET PROJECT SCHEDULE AND REQUIREMENTS. 19. SEPARATE DIFFERING MATERIALS WITH DIVIDERS OR STOCKPILE APART TO PREVENT MIXING.
- 20. DIRECT SURFACE WATER AWAY FROM STOCKPILE SITE SO AS TO PREVENT EROSION OR DETERIORATION OF MATERIALS.
- 21. ALL ACTIVITIES SHALL REMAIN WITH THE AREA DESIGNATED THE "LIMIT OF DISTURBANCE" AS SHOWN ON THE EROSION AND SEDIMENT POLLUTION CONTROL PLANS.
- 22. THE CONTRACTORS WORKING ON THIS PROJECT SHALL BE RESPONSIBLE FOR ENSURING THAT ALL CONSTRUCTION ACTIVITIES RELATED TO THIS PROJECT ARE PERFORMED IN ACCORDANCE WITH ALL O.S.H.A. (OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION) STANDARDS AND REQUIREMENTS.
- 23. IN ALL CASES. WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTOR SHALL NOT USE SCALED DIMENSIONS FOR CONSTRUCTION WITHOUT CONFIRMATION BY ENGINEER. CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS ON THE PROJECT SITE. ENGINEER MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN ON THESE DRAWINGS.
- 24. AS-BUILT PLANS SHALL BE PROVIDED TO THE TOWNSHIP AFTER CONSTRUCTION IS COMPLETE.

USERS (OWNERS, CONTRACTORS) OF THIS PLAN ARE ADVISED THAT ALL PLANS SHOWN IN THE ABOVE REFERENCED PLAN INDEX SHALL BE UTILIZED WHEN PREPARING ESTIMATES, MANUFACTURING STRUCTURES, AND PERFORMING CONSTRUCTION. CERTAIN PLANS MAY HAVE FEATURES (EXISTING OR PROPOSED) WHICH MAY BE HIDDEN FROM VIEW TO PROVIDE CLARITY FOR THAT PARTICULAR PLAN.

PROFESSIONAL James Peter Kelley \ENGINEER . Know what's below. Call before you dig. PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR BARRY ISETT & ASSOCIATES, INC. CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL OLYPHANT, PA 18447 PENNSYLVANIA ONE CALL SYSTEM, INC.

1-800-242-1776

THE SITE SERIAL NUMBER IS 20240651009

1444 E. LACKAWANNA AVE., SUITE 214 (570) 285-8183

**	_	ADJOINERS		
# 1	PROPERTY OWNER AKIA S BLANDON	ADDRESS 208 RAVENS NEST RD	PARCEL ID 16.98062	MAP # 16731000750465
2	TWIN LAKES ESTATES DEVELOPMENT  JORGE GARRIDO	211 RAVENS NEST RD 209 RAVENS NEST RD	16.98061	16731000751735
4	ETUX DANE BROSSEAU	7604 CHERRY VALLEY RD	16.9806 16.8.3.45	16731000659828 16731002669440
5 6	DIANE A & RALPH C ROMSPERT JUDITH G & DENNIS C DOUDS	LR 45010 236 CHERRY VALLEY RD	16.8.3.48 4.93387	16731002762776 4731012766658
7	RAMNARINE- INDRANI & DMITRI SNYTKINE	9 SHEPARD CT	4.93431	4731012767950
8 9	KUMAR RAVI MAMIDELA ALEXANDRA & MANUEL FORS	14 SHEPARD CT 10 SHEPARD CT	4.9343 4.93429	4731012769921 4731012769771
10	RAFAEL CESAR MARTE	8 SHEPARD CT	4.93428	4731012769506
11 12	L INGRAM BURNETT  AYANA PHILLIPS	6 SHEPARD CT SHEPARD AVE	4.93427 4.93426	4731012769433 4731012860521
13 14	NEETA PURI D ROBERT KELLY	5 SHEPARD CT SHEPARD AVE	4.93424	4731012860259 4731012861365
15	WATER GAP ACQUISTIONS PARTNERS LLC	TRL DOGWOOD	4.92606 4.3.1.51-7	4731012851383
16 17	WATER GAP ACQUISTIONS PARTNERS LLC WATER GAP ACQUISTIONS PARTNERS LLC	DOGWOOD DR MOUNTAIN RD	4.3.2.18 4.3.2.17	4731012856929 4731012855395
18	UNITED STATES OF AMERICA	WOLF HOLLOW DR	16.9.1.27	16731000501344
19 20	UNITED STATES OF AMERICA  WATER GAP ACQUISTIONS PARTNERS LLC	T 405 145 WOLF HOLLOW DR	16.9.1.43 16.9.1.28	16731000930739 16731000646042
21	JUDITH G & DENNIS C DOUDS	236 CHERRY VALLEY RD	4.93387	4731012766658
22	STACEY BRUTUS  KRISTINE K MCHUGH	1624 TOTTS GAP RD 1627 TOTTS GAP RD	16.9.1.23 16.9.1.29	16731000548256 16731004545417
24 25	WILLIAM RICHARD MCKENNA WILLIAM RICHARD MCKENNA	206 PAR THREE LN TOTTS GAP RD	16.110491	16731004544373
26	RICHARD A BUBNIS	226 PAR THREE LN	16.110492 16.9.1.30	16731004544149 16731004542020
27 28	CINDY E & RICHARD A BUBNIS UNITED STATES OF AMERICA	PAR THREE LN LR 45010	16.110493 16.9.1.21	16731004542454 16731000442404
29	WATER GAP ACQUISTIONS PARTNERS LLC	T 383	16.9.1.22	16731000442404
30 31	DEW GAP LLC ALLEN EMMONIS	119 WOLF HOLLOW DR 102 ROLLING HILL RD	16.98052 16.98053	16731000641538 16731000642704
32	DENNIS BLANCO	104 ROLLING HILL RD	16.98053	16731000642704
33 34	BRIAN CANNONIER  WATER GAP ACQUISTIONS PARTNERS LLC	106 ROLLING HILL RD 206 RAVENS NEST RD	16.98055 16.98063	16731000653041 16731000646935
35	ROB EDWARD STIRTON	108 ROLLING HILL RD	16.98056	16731000654172
36 37	JEFFREY CHENG KUANG MIN CHENG	110 ROLLING HILL RD 204 RAVENS NEST RD	16.98057 16.98059	16731000655247 16731000656564
38	YIN YOKE & JEFFREY CHENG	112 ROLLING HILL RD	16.98058	16731000654500
39 40	VIR CONSTRUCTION CORPORATION ALVIN M DAVIS	111 ROLLING HILL RD 109 ROLLING HILL RD	16.98051 16.9805	16731000651456 16731000651362
41	SEAN PATRICK KENNEDY	107 ROLLING HILL RD	16.98049	16731000651362
42 43	VIR CONSTRUCTION CORPORATION KETTLY BIEN-AIME TURNBULL	105 ROLLING HILL RD 101 ROLLING HILL RD	16.98048 16.98046	16731000559097 16731000548855
44	MARY SUE & ANTHONY ARDITO	1682 TOTS GAP RD	16.8.3.41-1	16731002651757
45 46	ALLEN CLAUDE ETAL & MICHAEL METZGAR MICHAEL MATTHEW METZGAR	T 383 7562 CHERRY VALLEY RD	16.94614 16.8.3.40-2	16731002663236 16731002661452
47	PATRICIA B & DAVID A TRANSUE	7591 CHERRY VALLEY RD	16.8.3.39	16731002674042
48 49	CHRISTOPHER ANDERSON WILLIAM H HARRISON IV	7599 CHERRY VALLEY RD 7605 CHERRY VALLEY RD	16.8.3.38 16.8.3.37	16731002676047 16731002677092
50	JOSEPH M MAIARA	7611 CHERRY VALLEY RD	16.8.3.36	16731002668996
51 52	DOUGLAS P POSTEN  ANGELO J CEGLIA II	7615 CHERRY VALLEY RD 158 MAPLE AVE	16.8.3.35-1 16.8.3.34-3	16731002678291 16731002678593
53	JAMES M TERWILLIGER	7584 CHERRY VALLEY RD	16.8.3.40-1	16731002671242
54 55	SUSAN & JOSEPH L JR KELLERMAN FRANCES & LARRY R KRAMER	7590 CHERRY VALLEY RD 7594 CHERRY VALLEY RD	16.8.3.42 16.8.3.43	16731002663757 16731002665718
56	KRC INVESTMENTS LLC	7598 CHERRY VALLEY RD	16.8.3.44	16731002666758
57 58	SARA BODMAN ERIN K HIGGINS	7608 CHERRY VALLEY RD 7614 CHERRY VALLEY RD	16.8.3.46 16.8.3.47	16731002669709 16731002669799
59	FRANK NIPER	162MAPLE AVE	16.8.3.34	16731002771518
60 61	SUSAN FINE NAJI & DHABAH S ALMONTASER	LR 45010 CHERRY VALLEY RD 7629 CHERRY VALLEY RD	16.8.3.35-2 16.8.3.35	16731002771180 16731002773244
62	DELAWARE WATER GAP MUNICIPAL AUTH	CHERRY VALLEY RD LR 45010	16.117548	16731002774174
63 64	GEORGE RIVERA MANUEL GARCIA	7636 CHERY VALLEY RD 7642 CHERRY VALLEY RD	4.3.1.1-1 4.93533	4731012775093 4731012777100
65	LISA S PIZZUTO	7648 CHERRY VALLEY RD	4.93532	4731012777195
66 67	JESSE ROURKE RICHARD MICHEL	7654 CHERRY VALLEY RD 111 KIMBERLY RD	4.3.1.1 4.3.1.33	4731012778282 4731012870115
68	ELAINE M SHUEY	95 KIMBERLY RD	4.3.1.33-3	4731012870050
69 70	ROXANNE ANTONOWICH  LEROY KAISER	91 KIMBERLY ROAD 67 KIMBERLY ROAD	4.3.1.33-4 4.3.1.33-1	4731012860970 4731012860793
71 72	SALVATORE A SERPE  JOHN JULIAN	2 SHEPARD CT 60 KIMBERLY RD	4.92607	4731012861519
73	SUE ELLEN & KEVIN R WALSH	70 KIMBERLY RD	4.112753 4.112754	4731012862795 4731012862888
74	DARRIANE TABERER	76 KIMBERLY RD	4.112755	4731012862969
75 76	SARAH C & IAN S FOSTER  JAAN R HAGERUP	KIMBERLY RD  92 KIMBERLY RD	4.3.1.32 4.112525	4731012873299 4731012873095
77 78	VALERIE L & JEFFREY J HIGBEE	210 SHEPARD AVE	4.3.1.34-1	4731012864813
78 79	DARRIANE TABERER DEREK ANSPACH	SHEPARD AVE 186 SHEPARD AVE	4.3.1.34-2 4.3.1.49	4731012864902 4731012875080
80 81	SUSAN & STEVEN F SIMISTER	177 SHEPARD AVE	4.3.2.4	4731012868919
81	ZACHARY M BOOTH	24 CHEROKEE RD 187 SHEPARD AVE	4.3.2.3 4.3.1.51-2	4731012869953 4731012867805
83 84	BRIAN P HENNEBERRY DAVID MARCUS SANTOS	37 CHEROKEE RD 197 SHEPARD AVE	4.3.1.50 4 3 1 51 – 3	4731012867786 4731012866746
85	TARA M NYLANDER	207 SHEPARD AVE	4.3.1.51-3 4.3.1.51-1	4731012866746
86 87	SALEH TALAAT ELKERDASY BOROUGH OF DELAWARE WATER GAP	229 SHEPARD AVE SHEPARD AVE	4.3.1.51-6 4.3.1.51-5	4731012863588 4731012862447
88	KAREN & EDWARD B CRONK	329 DOGWOOD DR	4.3.1.56	4731012863369
89 90	CARLOS QUINTEROS  BOROUGH OF DELAWARE WATER GAP	230 DOGWOOD DR DOGWOOD DR	4.3.1.51 4.117087	4731012866504 4731012866423
91	WAYNE MACWILLIAMS	242 DOGWOOD DR	4.3.1.52	4731012865325
92 93	JOHN & ELAINE STARINSKI KAREN OHREM	246 DOGWOOD DR 323 DOGWOOD DR	4.3.1.53 4.3.1.55	4731012864234 4731012862289
94	CHRISTINE TREMBLY	311 DOGWOOD DR	4.3.1.55-1	4731012862231
95 96	CHRISTINE I TREMBLY  AMANDA & ANTHONY N JAKUBOWSKI	303 DOGWOOD DR 247 DOGWOOD DR	4.3.1.54 4.111734	4731012863007 4731012865150
97	LAWRENCE KUCZMA	245 DOGWOOD DR	4.111735	4731012866118
98 99	ANNA MOSER BOROUGH OF DELAWARE WATER GAP	243 DOGWOOD DR DOGWOOD DR	4.111736 4.3.2.1	4731012866276 4731012866389
100	HAROLD D CREARY	209 DOGWOOD DR	4.3.2.18-2	4731012868416
101 102	GAIL ELLIOT  JOHN KENNETH ELWOOD	199 DOGWOOD DR 25 CHEROKEE DR	4.3.2.2-2 4.3.2.2-1	4731012869527 4731012869710
103	EDWARD J ARNER	15 CHEROKEE RD	4.3.2.2-3	4731012960632
104 105	JOHN W ETAL SHOEMAKER  JOHN W SHOEMAKER	178 MOUNTAIN RD 198 MOUNTAIN RD	4.3.2.13 4.3.2.14	4731012962409 4731012961301
106	DAWN Y KOHL	230 MOUNTAIN RD	4.119552	4731012961301
107 108	TERENCE NOEL SMOTH LEANNE CRAMER	230 MOUNTAIN RD MOUNTAIN RD	4.3.2.16 4.119551	4731012960144 4731012960153
109	CAROL T PENNA	230 MOUNTAIN RD	4.119551 4.11955	4731012960153 4731012960192
110 111	VALERIE GANCI LAICO WESLEY L CAMPBELL	242 MOUNTAIN RD 258 MOUNTAIN RD	4.3.2.18-1	4731012859937 4731012858789
112	BOROUGH OF DELAWARE WATER GAP	MOUNTAIN RD	4.3.2.17-1 4.110811	4731012858789 4731012858602
113	BOROUGH OF DELAWARE WATER GAP DEREK ANSPACH	OFF MOUTAIN RD EAST OF SHEPARD AVE ST	4.111258 4 3 1 34	4731012868153 4731012875241
11/	PENER ANDLAUT		4.3.1.34	4731012875241 4731012767406
114 115	MARSHALL E ANDERS	7 SHEPARD CT	4.93425	<del>473101</del> 2707 <del>4</del> 00
	MARSHALL E ANDERS UNITED STATES OF AMERICA BOROUGH OF DELAWARE WATER GAP	MOUNTAIN RD OLD US 611	4.93423 4.3.4.1 4.4.1.1	4732000072449 4732000051302





SITE DATA

OWNER/DEVELOPER: WATER GAP ACQUISITIONS PARTNERS, LLC P.O. BOX 244 DELAWARE WATER GAP, PA 18327 PHONE: 203-524-3039

SITE ADDRESS: WATER GAP WELLNESS 296 MOUNTAIN ROAD STROUDSBURG, PA 18360

D.B.V. 2418, PG. 6739 DEED BOOK: TAX MAP: 16-9-1-26 16731000755147 NUMBER OF LOTS: ONE (1) TOTAL AREA:

SEWER: ON-SITE WATER: ON-SITE

### ZONING DATA

ZONING DISTRICT: R-1: LOW DENSITY RESIDENTIAL ON-SITE SEWER AND WATER

EXISTING USE: INN AND CONFERENCE CENTER ACCESSORY BUILDING FOR INN AND PROPOSED USE: CONFERENCE CENTER MINIMUM LOT AREA: 50,000 SF MINIMUM LOT WIDTH: 150 FEET

MINIMUM LOT DEPTH: 200 FEET MINIMUM YARDS (BUILDING SETBACKS): FRONT: 35 FEET REAR: 25 FEET

SIDE: 30 FEET LOT COVERAGE (BUILDING): BUILDING HEIGHT: 35 FEET MAX. IMPERVIOUS COVERAGE: EXISTING BUILDINGS COVERAGE 1.43% PROPOSED BUILDINGS COVERAGE 1.78% PROPOSED IMPERVIOUS COVERAGE 6.50% SMITHFIELD TWP PROPERTY AREA 51.29 AC.

ZONING NOTE:
ZONING DATA PROVIDED IS BASED ON AN INTERPRETATION OF
THE ZONING ORDINANCE BY THE PLAN PREPARER AND IS
SUBJECT TO CONFIRMATION BY THE APPROPRIATE MUNICIPAL

### ZONING CLASSIFICATIONS

SMITHFIELD TOWNSHIP

LOW-DENSITY RESIDENTIAL RESIDENTIAL CONSERVATION BOROUGH OF DELAWARE WATER GAP


LOW-DENSITY RESIDENTIAL CONSERVATION & PARK VILLAGE COMMERCIAL/RESIDENTIAL


NOTE
ALL BOUNDARY, ZONING, AND MUNICIPAL LINE INFORMATION
IS SHOWN AS PER THE MONROE COUNTY, PA PUBLIC GIS DATA.

PROPERTY BOUNDARY LOT LINE MUNICIPAL BOUNDARY ZONING BOUNDARY APPALACHIAN TRAIL TRAIL CORRIDOR LIMT TRAIL CORRIDOR


TAL/CRS 8/26/2024 SCALE: 1"=400' CRS DRAWN: TAL/DFG 1022419.004 COPYRIGHT 2024


SHEET: 2 OF 27






TAL/CRS 8/26/2024 1"=30' TAL/DFG 1022419.004 COPYRIGHT 2024








TAL/CRS 8/26/2024 1"=30' CRS TAL/DFG 1022419.004 COPYRIGHT 2024

SP-2



DATE BY 11/25/24 TAL 3/4/25 TAL 3/28/25 TAL

EVISIONS

1. TOWNSHIP COMMENTS

2. MCCD COMMENTS

3. TOWNSHIP COMMENTS

4, Suite 200

A 18360

A 18360

© 272.200.2050

© barryisett.com

525 Main Street, Suite 200

Stroudsburg, PA 18360

BARRY
SECIPLINE ENGINEERS AND CONSULTANTS

R EXISTING RESOURCES & SITE ANALYSIS FATER GAP WELLNESS RECREATION CENTER ATER GAP ACQUISITIONS PARTNERS, LLC SMITHFIELD TOWNSHIP

DATE: 8/26/2024 DSGN: TAL/CRS

SCALE: CHK: CRS


DRAWN: APPRD: JPK


JOB: P MGR: JPK


COPYRIGHT 2024

SHEET: 5 OF 27

COPYRIGHT 2024
ET: 5 OF 27








XISTING WATER G

TAL/CRS 8/26/2024 DRAWN: TAL/DFG 1022419.004 COPYRIGHT 2024 SHEET: 6 OF 27



PROPERTY SLOPE DATA

17.72 AC. 771,789.36 S.F. 16.76% 13,417.45 S.F. 1.74%

(S.F.)

25% 100% 8.79 AC. 382,966.72 S.F. 8.32% 6,410.70 S.F. 1.67%

AREA DISTURBED DISTURBED MAXIMUM AREA

(%) AREA (S.F.) AREA (%) OF DISTURBANCE

GAS MAIN & VALVE

SANITARY LINE, MANHOLE, & CLEANOUT

STORM LINE, MANHOLE, & INLET

L8

L9

L10

L11

L12

Know what's below.

Call before you dig.

SITE SERIAL #20240651009

50.71

24.00

13.14

35.79

26.58

N32° 42′ 59″W

N36° 35′ 44″W

N69° 09' 54"E

S40° 51' 27"E

S64° 13′ 50″E

L20

L22

L24

42.11

13.27

20.28

36.44

31.53

S51° 44' 11"E

S11°42′13″E

S54° 48′ 51"E

S54° 41' 09"E

S15° 45' 43"W

MINIMUM MAXIMUM SLOPE SLOPE

15% 25%

(T.B.R.)

BITUMINOUS

TO BE REMOVED

FINISHED FLOOR DOOR SILL

NOTE: VERTICAL TEXT INDICATES PROPOSED FEATURES SLANTED TEXT INDICATES EXISTING FEATURES

TYPICAL

BIT.


TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 7 OF 27

1"=30'


TAL/CRS

CRS

ER-2







SOIL CLASSIFICATIONS

BATH CHANNERY SILT LOAM - HSG C
3 TO 8 PERCENT SLOPES

BATH CHANNERY SILT LOAM - HSG C
8 TO 15 PERCENT SLOPES

BATH CHANNERY SILT LOAM - HSG C
0 TO 8 PERCENT SLOPES, EXTREMELY STONY

BATH CHANNERY SILT LOAM - HSG C
8 TO 25 PERCENT SLOPES, EXTREMELY STONY

BENSON-ROCK OUTCROP, COMPLEX - HSG D

BENSON-ROCK OUTCROP COMPLEX - HSG D
8 TO 25 PERCENT SLOPES

CHIPPEWA AND NORWICH SOIL - HSG D
0 TO 8 PERCENT SLOPES, EXTREMELY STONY


LBE LACKAWANNA AND BATH SOILS — HSG D STEEP, RUBBLY MARDIN VERY STONY SILT LOAM - HSG D
O TO 8 PERCENT SLOPES


PROPERTY SLOPE DATA								
MINIMUM SLOPE	MAXIMUM SLOPE	COLOR	AREA (AC.)	AREA (S.F.)	AREA (%)	DISTURBED AREA (S.F.)	DISTURBED AREA (%)	MAXIMUM AREA OF DISTURBANCE
15%	25%		17.72 AC.	771,789.36 S.F.	16.76%	13,417.45 S.F.	1.74%	60%
25%	100%		8.79 AC.	382,966.72 S.F.	8.32%	6,410.70 S.F.	1.67%	10%

	<u>EXISTING</u>	<u>DEMOLITION</u>		<u>EXISTING</u>	<b>DEMOLITION</b>
PROPERTY BOUNDARY OT LINE			CHAIN-LINK FENCE WOOD FENCE	$\longleftarrow \stackrel{CHAIN-LINK\ FENCE}{X} \longrightarrow \\ \longleftarrow \square \stackrel{WOOD\ FENCE}{\longrightarrow} \square \longrightarrow$	
BUILDING SETBACK			SIGN	d	
EGAL RIGHT-OF-WAY EASEMENT			DECIDUOUS TREE	6" MAPLE	
CURBING	DEPRESSED CURB		EVERGREEN TREE	6" PINE	
BUILDING	EXIST. BUILDING		TREE ROW		
	<i>\\////////\</i>		CONTOUR		
PAVEMENT			SPOT ELEVATION	<sub>X</sub> 590.53	
RAVEL			STREAM		
SOIL BOUNDARY JTILITY POLE		ک بنا میش خانوان میش با آن بیان میش خانوان میش د	WETLANDS	<u> </u>	
VERHEAD ELECTRIC	<i>y</i> □		EDGE OF PAVEMENT	E.O.P.	
ATER MAIN & VALVE	<i>w∨ w w w w w w w w w w</i>		EDGE OF GRAVEL	E.O.G.	
GAS MAIN & VALVE	$\longleftarrow \otimes \overset{GV}{\longrightarrow} G \longrightarrow$		BITUMINOUS	BIT.	
SANITARY LINE, MANHOLE,	SAN. MH CO		TYPICAL	(TYP.)	
& CLEANOUT	≥ SAN SAN		TO BE REMOVED		(T.B.R.)
STORM LINE, MANHOLE,	STORM MH INLET		FINISHED FLOOR	F.F.	
& INLET			DOOR SILL	D.S.	



TAL/CRS SCALE: CRS 1"=30' DRAWN: TAL/DFG 1022419.004 COPYRIGHT 2024 SHEET: 8 OF 27












TAL/CRS











8/26/2024 TAL/CRS CRS 1"=30' TAL/DFG 1022419.004 JPK COPYRIGHT 2024 SHEET: 10 OF 27

GP-2












TAL/CRS 8/26/2024 1"=30' TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 11 OF 27












TAL/CRS


P MGR:

CRS













272.200.2050

8/26/2024 TAL/CRS SCALE: CRS 1"=30' DRAWN: TAL/DFG 1022419.004 COPYRIGHT 2024


PP-1

SHEET: 13 OF 27










STORM SEWER PLAN & PROFILES
WATER GAP WELLNESS RECREATION CENTER
WATER GAP ACQUISITIONS PARTNERS, LLC
SMITHFIELD TOWNSHIP
MONROE COUNTY, PA

272.200.2050

DSGN: 8/26/2024 TAL/CRS SCALE: CRS 1"=30' DRAWN: TAL/DFG JPK P MGR: 1022419.004 COPYRIGHT 2024

PP-2

SHEET: 14 OF 27






STORM SEWER PLAN & PROFILES

WATER GAP WELLNESS RECREATION CENTER
WATER GAP ACQUISITIONS PARTNERS, LLC
SMITHFIELD TOWNSHIP
MONROE COUNTY, PA

DATE: DSGN: TAL/CRS 8/26/2024 SCALE: CRS 1"=30' DRAWN: TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024

SHEET: 15 OF 27

PP-3



PLAN VIEW
SCALE: 1"=30'

Know what's below.

Call before you dig.

SITE SERIAL #20240651009

PROPOSED WATERLINE PROFILE

STA.:0+00 TO 1+46.01 SCALE: 1"=30'(H), 1"=3'(V)


PROPOSED SANITARY SEWER PROFILE


STA.:0+00 TO 1+46.53 SCALE: 1"=30'(H), 1"=3'(V)

272,200,2050


TAL/CRS 8/26/2024 SCALE: 1"=30' CRS DRAWN: TAL/DFG 1022419.004 COPYRIGHT 2024

SHEET: 16 OF 27





### SHRUB PLANTING



NOTES:

1. TREE PITS SHOULD BE HAND DUG. IF MECHANICALLY DIGGING PIT, SCARIFY EDGES OF PIT TO LOOSEN SOIL TO ALLOW ROOTS TO

2. BACKFILLED SOIL SHOULD NOT BE OVERLY REFINED. SOIL SHOULD CONSIST OF CLUMPS OF VARYING SIZES. GRAVEL SHALL NOT BE USED AS FILL MATERIAL.

INSTALL TREE SO THAT ROOT FLARE IS JUST ABOVE FINISH GRADE. DO NOT PLACE MULCH ABUTTING TRUNK. TREE STAKING — (ONLY IF IT IS EXPECTED BY THE CONTRACTOR OR FOUND BY THE LANDSCAPE ARCHITECT THAT THE TREE WILL NOT

SUPPORT ITSELF) TIGHTEN WIRE OR CABLE ONLY ENOUGH TO KEEP FROM SLIPPING. ALLOW FOR SOME TRUNK MOVEMENT. PLASTIC HOSE SHALL BE LONG ENOUGH TO ACCOMMODATE 1.5" OF GROWTH AND BUFFER ALL BRANCHES FROM THE WIRE. TUCK ANY LOOSE ENDS OF THE WIRE CABLE INTO THE WIRE WRAP SO THAT NO SHARP WIRE ENDS ARE EXPOSED. ASSURE THAT THE BEARING SURFACE OF THE PROTECTIVE COVERING OF THE WIRE OR CABLE AGAINST THE TREE TRUNK REMOVE ALL STAKING AS SOON AS THE TREE HAS GROWN SUFFICIENT ROOTS (USUALLY AFTER ONE GROWING SEASON) PROVIDE AND MAINTAIN WARNING FLAGS ON ALL WIRES.

5. ENSURE THAT THERE ARE NO GIRDLING ROOTS AROUND TRUNK OF TREE. IF THERE ARE GIRDLED ROOTS AROUND TRUNK, TREE SHOULD NOT BE INSTALLED.

5. ENSURE THAT THERE ARE NO GIRDLING ROUTS AROUND TROUN OF TREE. IT THERE ARE GIRDLED ROOTS AND ALL THE ROOTS AND CUT CIRCLING ROOTS WITH A SHARP KNIFE LOOSEN THE POTTING MEDIUM AND SHAKE AWAY FROM THE ROOT MAT. IMMEDIATELY AFTER REMOVING THE CONTAINER, INSTALL THE PLANT SUCH THAT THE ROOTS DO NOT DRY OUT. PACK PLANTING MIX AROUND THE EXPOSED ROOTS WHILE PLANTING. WATER THOROUGHLY.
7. TREE AND SHRUB MASSINGS SHALL BE ENCOMPASSED BY ONE LARGE MULCHED BED.

		INFILTRATION BASIN PLANTING SCHEDUL	_E	
KEY	QTY.	NAME	SIZE	SPACING
Sc	1052	SCHIZACHYRIUM SCOPARIUM, FORT INDIANTOWN GAP - PA ECOTYPE	QUART	18" O.C.
Ер	304	ECHINACEA PURPUREA (PURPLE CONEFLOWER)	QUART	18" O.C.
Rh	387	RUDBECKIA HIRTA (BLACKEYED SUSAN)	QUART	18" O.C.
An	238	ASTER NOVAE - ANGLIAE (NEW ENGLAND ASTER)	QUART	18" O.C.
Cv	690	CAREX VULPINOIDEA, PA ECOTYPE (FOX SEDGE)	QUART	18" O.C.
Ва	397	BAPTISIA AUSTRALIS, SOUTHERN WV ECOTYPE (BLUE FALSE INDIGO)	QUART	18" O.C.
Je	541	JUNCUS EFFUSUS (SOFT RUSH)	QUART	18" O.C.
			1	1

Know what's below.

Call before you dig.

SITE SERIAL #20240651009

LANDSCAPE CALCULATIONS:

1101.1.F.(2).(e)(1) STORMWATER BASIN PERIMETER PLANTINGS: - 505 LF/30 = 16.8 = 17 REQUIRED TREES PROPOSED: 17 TREES


- EVERGREEN TREES PROVIDED ALONG THE PROPERTY LINE TO BUFFER STORMWATER BASIN.

	PLANTING SCHEDULE							
SYMBOL	KEY	QTY.	BOTANICAL NAME	COMMON NAME	ROOT	SIZE	COMMENTS	
$\odot$	Am	12	ARONIA MELANOCARPA	BLACK CHOKEBERRY	QUART PLUG	12"-18" TALL	HEIGHT/SPREAD: 5 TO 6 FT	
$\odot$	Ca	15	CLETHRA ALNIFOLIA 'COMPACTA'	COMPACT SWEET-PEPPERBUSH	QUART PLUG	12"-18" TALL	HEIGHT/SPREAD: 3 TO 4 FT	
$\odot$	It	13	ITEA VIRGINICA	VIRGINIA SWEETSPIRE	QUART PLUG	12"-18" TALL	HEIGHT/SPREAD: 3 TO 5 FT	
$\odot$	lv	15	ILEX VERTICILLATA	WINTERBERRY	QUART PLUG	12"-18" TALL	HEIGHT/SPREAD: 6 TO 8 FT	
*	То	16	THUJA OCCIENTALIS	AMERICAN ARBORVITAE	B&B	6' HT.	SINGLE STEM FULL BRANCHING	
**	Jv	15	JUNIPERUS VIRGINIANA	EASTERN RED CEDAR	B&B	6' HT.	SINGLE STEM FULL BRANCHING	
(x)	Ar	9	ACER RUBRUM 'OCTOBER GLORY'	'OCTOBER GLORY' RED MAPLE	B&B	2.5" CAL.	SINGLE, CENTRAL LEADER, FULL CROWN AND BRANCHING	
(x)	Bn	8	BETULA NIGRA	RIVER BIRCH	B&B	2.5" CAL.	SINGLE, CENTRAL LEADER, FULL CROWN AND BRANCHING	
×	Ро	2	PLATANUS OCCIDENTALIS	AMERICAN SYCAMORE	B&B	2.5" CAL.	SINGLE, CENTRAL LEADER, FULL CROWN AND BRANCHING	

SEED MIX: ERNMX-126 - RETENTION BASIN FLOOR MIX - LOW MAINTENANCE SEEDING RATE: 20-40LB PER ACRE OR 0.5-1 LB/1,000 SQ FT WITH A COVER CROP. FOR A COVER CROP USE ONE OF THE FOLLOWING: GRAIN RYE (1 SEP TO 30 APR; 30 LBS/ACRE), JAPANESE MILLET (1 MAY TO 31 AUG; 10 LBS/ACRE), OR BARNYARD GRASS (1 MAY TO 31 AUG; 10 LBS/ACRE).

1. IN THE EVENT OF A CONFLICT BETWEEN THE LANDSCAPE PLAN AND SCHEDULE. PLAN TO BE FOLLOWED. 2. LIST OF PLANTS PURCHASED BY CONTRACTOR TO BE PROVIDED TO LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

3. ANY PLANT SUBSTITUTIONS TO BE SUBMITTED AND APPROVED BY LANDSCAPE ARCHITECT.





NOTE: VERTICAL TEXT INDICATES PROPOSED FEATURES


SLANTED TEXT INDICATES EXISTING FEATURES

TAL/CRS 8/26/2024 SCALE: CRS 1"=30' DRAWN: TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024

SHEET: 17 OF 27







TAL/CRS 8/26/2024 CRS 1"=30' TAL/DFG 1022419.004 COPYRIGHT 2024 SHEET: 20 OF 27


REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.

\* MOUNTABLE BERM USED TO PROVIDE PROPER COVER FOR PIPE

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE B 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

STANDARD CONSTRUCTION DETAIL #3-1 ROCK CONSTRUCTION ENTRANCE NOT TO SCALE



NOTES:
1. PLACE STOCKPILES AT LOCATIONS SHOWN ON PLAN. 2. STOCKPILE TO BE IMMEDIATELY SEEDED WITH A TEMPORARY SEED 3. SIDE SLOPES SHALL NOT EXCEED 1' VERTICAL TO 2' HORIZONTAL. . MAXIMUM TOPSOIL STOCKPILE HEIGHT NOT TO EXCEED 35'.

# SEEDING SCHEDULE

SPECIFICATION: THE FOLLOWING SPECIFICATION SHALL BE USED FOR THIS PROJECT UNLESS OTHERWISE NOTED. Penn State College of Agriculture Sciences, EROSION CONTROL AND CONSERVATION PLANTINGS ON NONCROPLAND by Peter Landschoot, 1997 or as revised.

# PRIOR TO STARTING EARTH DISTURBANCE, CONTRACTOR SHALL SAMPLE THE SITE TOPSOIL AND OBTAIN A SOIL TEST FROM A REPUTABLE LABORATORY. AT A MINIMUM, THE TEST SHALL INCLUDE SOIL pH, COMPOSITION, AND % ORGANICS ALONG WITH RECOMMENDATIONS FOR pH BALANCE, FERTILIZATION, AND LIMING.

BEFORE PLACING TOPSOIL, PREPARE SUBGRADE TO A DEPTH 6" BELOW FINAL GRADE. SCARIFY SUBGRADE WITH DEEP TINE PLOW. SCREEN TOPSOIL AND UNIFORMLY BLEND IN 20-25% BY VOLUME LEAF MOULD OR PROCESSED MUSHROOM SUBSTRATE. SPREAD AMENDED/SCREENED TOPSOIL OVER SUBGRADE TO OBTAIN FINISHED GRADE. COMPACT SURFACE TO 80-85% COMPACTION. DO NOT OVER COMPACT.

### TEMPORARY COVER FOR EROSION CONTROL INITIAL PROTECTION: APPLY TEMPORARY SEEDING WHEN PERMANENT SEEDING IS DELAYED OR OUT OF PLANTING SEASON.

SITE PREPARATION: INCORPORATE LIME AND FERTILIZER (RATE BASED ON SOIL TEST) INTO THE TOP 4-6" OF TOPSOIL. IF SOIL TESTS ARE NOT AVAILABLE, APPLY ONE TON PER ACRE OF AGRICULTURAL LIMESTONE AND 10-10-10 FERTILIZER AT 500 LB PER ACRE.

### METHOD: APPLY SEED USING SURFACE BROADCASTING OR HYDROSEEDING

<u>SEA</u>	<u>ason</u>	<u>SPECIES</u>	RATE (LB./ACRE)
SPRING (MARCH 15	5 TO JUNE 15)	ANNUAL RYEGRASS or SPRING OATS	40 96
SUMMER (JUNE 16	TO AUGUST 15)	ANNUAL RYEGRASS	40
FALL (AUGUST 1	6 TO NOVEMBER 1)	ANNUAL RYEGRASS or WINTER RYE	40 168
MULCHING:	ACHIEVE A LOOSE LAY JUTE MATTING RATHER CELLULOSE FIBER TAC	ER ACRE OF STRAW TO (ER 3/4-1" DEEP. USE THAN STRAW ON STEEP SLOPES. KIFIER OVER STRAW MULCH AT A F R ACRE. HYDROMULCHING IS ACCE A CONCERN.	RATE

### PERMANENT COVER FOR STABILIZATION

ALL DISTURBED AREAS TO BE PREPARED AND SEEDED WITH THE FOLLOWING SPECIES AT THE NOTED SEEDING

### SEEDING DATES: MARCH 15 - MAY 15 AUGUST 15 - OCTOBER 15

SITE PREPARATION: INCORPORATE LIME AND FERTILIZER (RATE BASED ON SOIL TEST) INTO THE TOP 6" OF TOPSOIL. IF SOIL TESTS ARE NOT AVAILABLE, APPLY SIX TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 10-20-20 FERTILIZER

AT 1,000 LB PER ACRE. MULCHING: APPLY THREE TONS PER ACRE OF STRAW TO ACHIEVE A LOOSE LAYER 3/4-1" DEEP. USE JUTE MATTING RATHER THAN STRAW ON STEEP SLOPES. APPLY

HYDROSEEDING OF PERMANENT SEEDING IS NOT PERMITTED.


LULOSE FIBER TACKIFIER OVER STRAW MULCH AT A RATE 800-1000 LBS. PER ACRE. HYDROMULCHING IS ACCEPTABLE WHEN BLOWING OF STRAW IS A CONCERN. METHOD: APPLY SEED USING DRILL FITTED WITH A DEPTH BAND AND PACKER WHEEL. PLANT GRASS SEEDS AT 0.25 TO 0.5 INCHES DEEP. WHEAT, RYE AND OATS MAYBE PLANTED 1 TO 1.5 INCHES DEEP. BROADCAST SEEDING PERMITTED WITH IMMEDIATE MULCH COVER.

SEED SPECIES BY SITE	RATE (LB./1000 S
KENTUCKY BLUEGRASS (POA PRATENSIS) and TURF-TYPE PERENNIAL RYEGRASS (LOLIUM PERENNE) and FINE (RED or CHEWING) FESCUE (FESTUCA RUBA RUBA/COMMUTA	4 1.5 (TA) 2.5
SLOPES AND BANKS CHEWINGS FESCUE (FESTUCA RUBRA COMMUTATA) and	2

BLUE FESCUE (FESTUCA OVINA GLAUCA) and HARD FESCUE (FESTUCA OVINA DURIUSCULA) and CREEPING RED FESCUE (FESTUCA RUBRA RUBRA) and SLENDER FESCUE (FESTUCA RUBRA TRICHOPHYLLA) and DAWSON RED FESCUE (FESTUCA RUBRA DAWSON) and ANNUAL RYEGRASS (FESTUCA MULTIFLORUM)


DRAINAGE DITCHES, DETENTION BASIN (MOWED) REDTOP (AGROSTIS ALBA) and FESCUE (FESTUCA ARUNDINACEA) and SWITCHGRASS (PANICUM VIRGATUM) \* ALL SEED TO BE MIN. 98% PURE LIVE SEED

SUGGESTED VARIETIES RELIANT II, SR3100, DISCOVERY, OSPREY FINE FESCUE Houndog V, Montauk, Marksman, and Apache II ARCOOSTOOK OR BALBO TYPE KENTUCKY BLUEGRASS - SR 2109, NORTH STAR, BLACKSBURG, BRILLIANT



STAPLE PATTERN A DETAIL STAPLE PATTERN B DETAIL 1:1 & STEEPER SLOPES HIGH FLOW CHANNEL MEDIUM/HIGH FLOW CHANNEL AND SHORELINE ----) • • • <u>•</u>

 $\bullet$   $\bullet$   $\bullet$ <del>\* • • •</del> 1.7 STAPLES PER SQ.YD. 3.4 STAPLES PER SQ.YD. 3.75 STAPLES PER SQ.YI STAPLE PATTERN STAPLE PATTERN STAPLE PATTERN **D DETAIL** E DETAIL C DETAIL



ALL EROSION CONTROL BLANKETS SHALL BE NORTH AMERICAN GREEN PHOTODEGRADABLE BLANKET S75 UNLESS OTHERWISE NOTED FOR SPILLWAYS OR BERM STABILIZATION. SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET. PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.

SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS. BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

### MODIFIED CONSTRUCTION DETAIL #11-1 EROSION CONTROL BLANKET INSTALLATION

### PLAN PREPARER CONTACT INFORMATION

JAMES P. KELLEY, P.E. BARRY ISETT & ASSOCIATES, INC. 1444 E. LACKAWANNA AVE., SUITE 214 OLYPHANT, PA 18447

PHONE: (570) 285-8183 EMAIL: JKELLEY@BARRYISETT.COM

### PLANNING AND DESIGN


THE EARTH CONSTRUCTION ACTIVITIES, PROPOSED BY THIS PLAN, HAVE BEEN PLANNED AND IMPLEMENTED TO THE MAXIMUM EXTENT PRACTICABLE, IN ACCORDANCE WITH THE FOLLOWING:

- 1. MINIMIZE THE EXTENT AND DURATION OF THE EARTH DISTURBANCE.
- MAXIMIZE PROTECTION OF EXISTING DRAINAGE FEATURES AND VEGETATION.
- 3. MINIMIZE SOIL COMPACTION.
- UTILIZE OTHER MEASURES OR CONTROLS THAT PREVENT OR MINIMIZE THE GENERATION OF INCREASED STORMWATER RUNOFF.

### FLOODPLAIN MAPPING

THE PROJECT AREA WAS REVIEWED USING THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) NATIONAL FLOOD HAZARD LAYER (NFHL). THE NFHL IS A COMPILATION OF GIS DATA THAT COMPRISES A NATIONWIDE DIGITAL FLOOD INSURANCE RATE MAP. THE GIS DATA AND SERVICES ARE DESIGNED TO PROVIDE THE USER WITH THE ABILITY TO DETERMINE THE FLOOD ZONE, BASE FLOOD ELEVATION, AND FLOODWAY STATUS FOR A PARTICULAR LOCATION.

THE PROJECT AREA IS NOT LOCATED WITHIN A MAPPED FLOODPLAIN. THE PANEL FOR THE PROJECT AREA IS 42089C0432E, HAVING AN EFFECTIVE DATE OF 05/2/2013.



NOTES:

WASH RACK SHALL BE 20 FEET (MIN.) WIDE OR TOTAL WIDTH OF ACCESS. WASH RACK SHALL BE DESIGNED AND CONSTRUCTED TO ACCOMMODATE ANTICIPATED

A WATER SUPPLY SHALL BE MADE AVAILABLE TO WASH THE WHEELS OF ALL VEHICLES EXITING

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. DRAIN SPACE UNDER WASH RACK SHALL BE KEPT MAINTAINED ON SITE FOR THIS PORPOSE. DRAIN SPACE UNDER WASH RACK SHALL BE REPORT TO FURTHER OPEN AT ALL TIMES. DAMAGE TO THE WASH RACK SHALL BE REPAIRED PRIOR TO FURTHER USE OF THE RACK. ALL SEDIMENT DEPOSITED ON ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS

STANDARD CONSTRUCTION DETAIL #3-2 ROCK CONSTRUCTION ACCESS WITH WASH RACK

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
ВаВ	Bath channery silt loam, 3 to 8 percent slopes	9.4	11.6%
ВаС	Bath channery silt loam, 8 to 15 percent slopes	20.9	25.6%
BaD	Bath channery silt loam, 15 to 25 percent slopes	3.2	3.9%
BbB	Bath channery silt loam, 0 to 8 percent slopes, extremely stony	2.5	3.0%
BbC	Bath channery silt loam, 8 to 25 percent slopes, extremely stony	2.7	3.3%
BeC	Benson-Rock outcrop complex, 8 to 25 percent slopes	14.6	17.8%
BeF	Benson-Rock outcrop complex, 25 to 70 percent slopes	1.6	2.0%
CnB	Chippewa and Norwich soils, 0 to 8 percent slopes, extremely stony	12.4	15.1%
LBE	Lackawanna and Bath soils, steep, rubbly	4.8	5.9%
MbB	Mardin very stony silt loam, 0 to 8 percent slopes	6.4	7.9%
ReA	Rexford gravelly silt loam, 0 to 3 percent slopes	3.2	3.9%
Totals for Area of Interest		81.7	100.0%

	Job# 1022419.004	SOILS LIMITA	ATIONS & RESOLUTIONS SHEET	
Project Na	me: Water Gap We	ellness Accessory Buildin	nas	
-	TION Smithfield Township			COUNTY Morroe
CHARA	CTERISTICS	LIMITATIONS	RESOLUTIONS	COMMENTS
-fyDRIC	WETLANDS	NO DISTURBANCE (UNLESS ALLOWED BY DEP PERMIT;	DELINEATE WETLANDS PROTECT WETLANDS OBTAIN PERMIT(S)	SEE SOIL EROSION PLAN SHEET COPIES OF PERMITS
DEPTH TO BEOROCK	·	RESERVOIR AREAS DIVERSIONS WATERWAYS TERRACES UTILITIES BUILDING SHES	REVISE DESIGN - RELOCATE	NOT ALWAYS POSSIBLE
TOPSOIL	POOR	VEGETATIVE STABILIZATION FMBANKMENTS HIGH ACIDITY LOW FERTILITY EXCESSIVE DRYNESS EXCESSIVE WETNESS	SOIL TESTS ADJUST SOILS IMPLEMENTS AS NEEDED	SEE SEEDING WORKSHEETS AND DETAIL SHEET NOTES
VET	HIGH WATER TABLE	RESERVOIR ARFAS UTILITIES	SELECT FILL MATERIAL FROM OTHER AREA OF SITE SELECT APPROPRIATE PLANT MIXTURE	SEE SEEDING WORKSHEETS AND DETAIL SHEET NOTES
	FLOODING HYDIRC PIPING SEEPAGE	EMBANKMENTS DIKES LEVEES BUILDING SITES LANDSCAPING	PROVIDE PUMPED WATER SECIMENT REMOVAL FACILITY DRAINAGE CHANNELS - UNDERDRAINS IMPORT BORROW MATERIAL FROM OFFSITE	SEE DETAIL SHEET
VINTER GRADING BOST ACTION	POOR COMPACTION	RESERVOIR AREAS EMBANKMENTS	LIMIT DATES OF EARTH MOVING SELECT FILL MATERIAL FROM OTHER AREA OF SITE IMPORT BORROW MATERIAL FROM OFFSITE	SEE CONSTRUCTION SCHEDULE

### CONSTRUCTION SCHEDULE

ANTICIPATED START OF CONSTRUCTION: START DATE: MARCH 2025 ANTICIPATED END OF CONSTRUCTION: END DATE: AUGUST 2025

AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE MONROE COUNTY CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING.

AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED BY THE MONROE COUNTY CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION. FACH STEP OF THE SEQUENCE SHALL BE COMPLETED BEFORE PROCEEDING TO THE NEXT STEP, EXCEPT WHERE NOTED.

IMMEDIATELY STABILIZE ALL DISTURBED AREAS UPON TEMPORARY CESSATION OF WORK (4 DAYS OR LONGER) OR AS SOON AS ANY GRADED AREA REACHES FINAL GRADE.

NO AREA EXCEEDING 15,000 SQUARE FEET, WHICH IS TO BE STABILIZED BY VEGETATION, SHOULD REACH FINAL GRADE WITHOUT BEING SEEDED AND MULCHED. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE

DESCRIBED IN THIS PLAN, OVER UNDISTURBED VEGETATED AREAS. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS.

REFER TO THE SPECIFIC BMP SEQUENCES OF CONSTRUCTION ON THE PCSM PLANS FOR THE INSTALLATION OF PCSM BMP'S ON STEPS 5 AND 6 OF THE CONSTURCTION SEQUENCE BELOW:

- DELINEATE THE LIMIT OF DISTURBANCE, INSTALL RCE, AND ORANGE CONSTRUCTION FENCING. ON A DRY DAY WITH NO PRECIPITATION ANTICIPATED, BEGIN THE INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM EW-25 TO IN-21, FROM MH-24 TO IN-20, AND THE BASIN OUTLET PIPE. INSTALL PROPOSED STORM SEWER RUNS FROM DOWNSTREAM TO UPSTREAM. IMMEDIATELY INSTALL INLET PROTECTION ON INSTALLED INLETS. INSTALL RIPRAP PROTECTION AT OUTLET OF STORM PIPING. INSTALL ANTI-SEEP COLLARS ON BASIN OUTLET PIPE. PERFORM ROUGH GRADING OF CHANNEL 1 CHANNEL 2 AND CHANNEL 3. THIS WORK MUST BE PERFORMED ON A DRY DAY WITH NO PRECIPITATION ANTICIPATED. IMMEDIATELY STABLIZE AND THEN INSTALL DIVERSION SOCK DS-1. INSTALL CFS-1 TO CFS-15 AND THE CONCRETE WASHOUT.
- 2. REMOVE SITE FEATURES DESIGNATED AS TBR. STRIP TOPSOIL AND STOCKPILE AT THE LOCATION SPECIFIED ON THE PLANS BEFORE BEGINNING EXCAVATION OR GRADING
- 3. BEGIN ROUGH GRADING. INSTALL SLOPE PROTECTION MATTING ON AREAS OF STEEP SLOPES.
- 4. INSTALL PROPOSED ROCK/RETAINING WALL TREE PROTECTION BEFORE GRADING UPSLOPE AREAS.
- 5. CRITICAL STAGE: BEGIN CONSTRUCTION OF PROPOSED INFILTRATION BASIN. REFER TO PCSM PLAN SET FOR CONSTRUCTION SEQUENCE AND FURTHER DETAILS AND INFORMATION. AT NO POINT SHALL EQUIPMENT TRAVERSE WITHIN THE ORANGE CONSTRUCTION FENCING OR OVERTOP THE PROPOSED BASIN BOTTOM.
- 6. CRITICAL STAGE: INSTALL AMENDED SOILS IN INFILTRATION BASIN TO BRING BOTTOM UP TO GRADE. INFILTRATION TESTING SHALL BE PERFORMED DURING AND AFTER CONSTRUCTION TO VERIFY INFILTRATION RATES OF AMENDED SOILS.
- 7. BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM FES-19 TO MH-10. INSTALL PROPOSED STORM SEWER RUNS FROM DOWNSTREAM TO UPSTREAM. INSTALL RIPRAP PROTECTION AT OUTLET OF STORM PIPING.
- 8. BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM MH-10 TO AD-12 AND FROM MH-10 TO DEPRESSION. IMMEDIATELY INSTALL INLET PROTECTION ON INSTALLED INLETS.
- 9. BEGIN INSTALLATION OF THE PROPOSED STORM SEWER RUN FROM MH-10 TO AD-2 AND FROM DEPRESSION TO RD-7. IMMEDIATELY INSTALL INLET PROTECTION ON INSTALLED INLETS.
- 10. BEGIN CONSTRUCTION OF THE PROPOSED IMPROVEMENTS
- 11. INSTALL SITE LIGHTING.
- 12. FINAL GRADE, SPREAD TOPSOIL, RAKE, AND SEED ALL DISTURBED AREAS. TOPSOIL SHALL BE REPLACED ACROSS LAWN AREAS AT A MINIMUM THICKNESS OF 6 INCHES.
- 13. AFTER ALL DISTURBED AREAS ACHIEVE FINAL STABILIZATION, REMOVE ALL E&S CONTROLS. REPAIR, SEED, AND STABILIZE ANY AREAS DISTURBED DURING THE REMOVAL OF THE EROSION CONTROLS.
- 14. CRITICAL STAGE: FIELD VERIFY TRIBUTARY AREAS TO PCSM BMPS.
- 15. AFTER THE PROJECT IS COMPLETED, THE NPDES NOTICE OF TERMINATION PAPERWORK AND AS-BUILT PLANS SHALL BE COMPLETED AND SUBMITTED TO MONROE COUNTY CONSERVATION DISTRICT.
- 1. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70 PERCENT PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED B' THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE RE-DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE RE-DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE
- TEMPORARY EROSION CONTROL MEASURES MAY ONLY BE REMOVED AFTER APPROVAL BY THE MONROE COUNTY CONSERVATION DISTRICT, AFTER THE CONSTRUCTION AREA AND RETAINED SILT ARE STABILIZED AND AFTER LAWN AREAS ARE ESTABLISHED.

### OPERATION AND MAINTENANCE PROGRAM

PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.

THE CONTRACTOR SHALL FURNISH, INSTALL, OPERATE, AND MAINTAIN ALL EROSION AND SEDIMENT POLLUTION CONTROL (E&S) BEST MANAGEMENT PRACTICES (BMPS) IDENTIFIED HEREIN. E&S BMPS SHALL BE MAINTAINED IN ACCORDANCE WITH THIS E&S PLAN AND THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP) EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL (E&S MANUAL), MARCH 2012.

E&S BMPS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF, UNLESS OTHERWISE INDICATED. THE CONTRACTOR SHALL KEEP RECORD OF ALL INSPECTIONS USING THE VISUAL SITE INSPECTION REPORT FORM (FORM 3150-FM-BWEW0083). E&S BMPS WHICH NEED REPAIR OR REPLACEMENT, SHALL BE REMEDIED IMMEDIATELY. DISPOSAL OF MATERIALS REMOVED FROM THE BMPS SHALL BE PERFORMED IN ACCORDANCE WITH THE RECYCLING OR DISPOSAL OF MATERIALS NOTES HEREIN.

### RECYCLING OR DISPOSAL OF MATERIALS

CONSTRUCTION WASTES FROM LAND DISTURBANCE AND DEVELOPMENT SHALL BE DISPOSED OF BY THE CONTRACTOR IN AREAS SUITABLE FOR SUCH WASTES IN ACCORDANCE WITH PA DEP REGULATIONS. EXCESS SOIL/ROCK SHALL BE UTILIZED ON SITE TO IMPROVE FINAL GRADING OF LOW AREA LOTS. THESE WASTES INCLUDE, BUT ARE NOT LIMITED TO, EXCESS SOIL MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER, SANITARY WASTES, ETC. THAT COULD ADVERSELY IMPACT WATER QUALITY, MEASURES SHOULD BE PLANNED AND IMPLEMENTED FOR HOUSEKEEPING, MATERIALS MANAGEMENT, AND LITTER CONTROL. WHEREVER POSSIBLE, RECYCLING OF EXCESS MATERIALS IS PREFERRED, RATHER THAN DISPOSAL

THE OPERATOR SHALL ASSURE THAT AN E&S CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE GOVERNING CONSERVATION DISTRICT, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL/ROCK SPOIL AND BORROW AREAS, REGARDLESS OF THEIR LOCATIONS.

RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THIS PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH PA DEP RULES AND REGULATIONS. SEDIMENT REMOVED FROM ESPCP CONTROLS AND FACILITIES SHALL BE DISPOSED OF IN LANDSCAPED. AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY

- ANTICIPATED CONSTRUCTION WASTES INCLUDE, BUT MAY NOT BE LIMITED TO, THE FOLLOWING:
- SEDIMENT TRASH / DEBRIS
- VEGETATION CLIPPINGS AS MAY RESULT FROM MAINTENANCE PACKAGING MATERIAL

STABILIZED OR PLACED IN TOPSOIL STOCKPILES.

FORMWORK ASSOCIATED WITH CONCRETE FOUNDATIONS.

### CLEAN FILL NOTES

THE OPERATOR MUST USE ENVIRONMENTAL DUE DILIGENCE TO ENSURE THAT ALL FILL MATERIAL ASSOCIATED WITH THE PROJECT QUALIFIES AS CLEAN FILL

CLEAN FILL IS DEFINED AS UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPERATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.)


ENVIRONMENTAL DUE DILLIGENCE TO ENSURE ALL FILL IS "CLEAN", AS DEFINED ABOVE, SHALL INCLUDE, BUT NOT BE LIMITED TO, INVESTIGATIVE TECHNIQUES SUCH AS VISUAL PROPERTY INSPECTIONS ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. ALL TESTING SHALL BE PREFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY OF "MANAGEMENT OF


### STANDARD E&S PLAN NOTES

- 1. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.
- 2. AT LEAST 7 DAYS PRIOR TO EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LAND OWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING.
- AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THE SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO
- AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL.
- CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THE E&S PLAN.
- 7. AT NO TIMES SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- 8. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN MAP(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION FACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR FLATTER.
- IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT.
- 10. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET. SEQ., 271.1 AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.
- 11. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING
- 12. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER OF ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BY QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING.
- 13. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER DISTURBED VEGETATED AREAS.
- 14. VEHICLES AND EQUIPMENT MAY NEITHER ENTER DIRECTLY NOR EXIT DIRECTLY FROM THE SITE ONTO THE ADJACENT ROADWAY UNLESS USING THE CONSTRUCTION ENTRANCE.
- 15. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE
- 16. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION.
- 7. SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- 18. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON

THE PLAN DRAWINGS.

- 19. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES - 6 TO 12 INCHES ON COMPACTED SOILS - PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL.
- 20. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.
- 21. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN
- 22. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS.
- 23. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHLL NOT BE INCORPORATED INTO FILLS.
- 24. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.
- 25. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED
- 26. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.
- 27. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN AN AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS.
- 28. PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
- 29. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.
- 50. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S
- AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATION SEASON.
- 32. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION.
- 33. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION.





27

Str



CONTROL DE ECREATION CAS PARTNERS WANSHIP NTY, PA \* SEDIMENT CO
WELLNESS REC
P ACQUISITIONS
SMITHFIELD TOW
MONROE COUNT SP/

ROSION ATER GAR WATER GA TAL/CRS 8/26/2024 AS NOTED CRS

TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 21 OF 27


SIZE THICK, LENGTH INITIAL TERMINAL DUTLET STRUCTURE DIA LABEL Rt Aiw (FT) (FT)

> SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS. ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER FACH RUNOFF EVENT, DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS


STANDARD CONSTRUCTION DETAIL #9-1 RIPRAP APRON AT PIPE OUTLET WITH FLARED END SECTION OR ENDWALL

NOT TO SCALE



NOTES: ALL COLLARS SHALL BE INSTALLED SO AS TO BE WATERTIGHT. COLLAR SIZE AND SPACING SHALL BE AS INDICATED WITHIN TABLE.

> STANDARD CONSTRUCTION DETAIL #7-16 CONCRETE ANTI-SEEP COLLAR FOR PERMANENT BASINS OR TRAPS NOT TO SCALE




FILTREXX RUNOFF DIVERSION <u>SOXX™ PLAN</u>

DIVERSION SOCK SIZE

BARRIER NO. SIZE (IN.)

\_\_\_\_\_2" x 2" x 36" WOODEN

STAKES PLACED 10' O.C.



PA DEP EROSION CONTROL MANUAL TABLE 13.1 MAXIMUM SPACING AND MATERIALS FOR TRENCH PLUGS


PROFILE VIEW

BEDDING

	TRENCH SLOPE (%)	SPACING L (FT)	PLUG MATERIAL				
1	< 5	1000	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS				
1	5 - 15	500	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS				
┪	15 - 25	300	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS				
1	25 - 35	200	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS				
1	35 - 100	100	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS				
1	> 100	50	CEMENT BAGS (WETTED) OR MORTARED STONE				
	* TOPSOIL MAY NOT BE USED TO FILL SACKS						

IMPERVIOUS TRENCH PLUGS ARE REQUIRED FOR ALL STREAM, RIVER, WETLAND, OR OTHER WATER BODY CROSSINGS.

### STANDARD CONSTRUCTION DETAIL #13-4 TRENCH PLUG INSTALLATION NOT TO SCALE



LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS, HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE


. 022011110 01711107111001		
PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5% FOR SLOPES EXCEEDING 5% CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS. NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE

FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

STANDARD CONSTRUCTION DETAIL #3-16 PUMPED WATER FILTER BAG NOT TO SCALE




OVER EXCAVATE SINKHOLE THROAT TO REMOVE ALL SOIL AND LOOSE ROCK. PLACE ROCK(S) TO PLUG SINKHOLE THROAT. ROCKS SHALL BE SIZED SO THEY CANNOT GO THROUGH THE THROAT. FILL SMALL VOIDS WITH SMALLER ROCK TO LEVEL THE PLUG. PLACE A THIN LIFT OF BENTONITE CLAY TO LEVEL THE ROCK PLUG. PLACE GEOTEXTILE DRAINAGE FABRIC OVER THE DISTURBED AREA, EMBEDDING 6" ON ALL EDGES. FABRIC TO HAVE TENSILE STRENGTH OF 90 LBS. AND AN EQUIVALENT OPENING SIZE OF SIEVE #200

4. LARGER OPENINGS MAY REQUIRE A CONCRETE PLUG. 18"-24" THICK. PLAC E BENTONITE CLAY/SOIL (1 TO 2 LBS./S.F., 8" LIFT, 95% MOD. PROCTOR). PLACE COMPACTED FINE-GRAINED NATIVE CLAY FILL (8" LIFTS, 95% MOD. PROCTOR) EVERY OTHER LIFT TO 12" BELOW FINAL GRADE. INSTALL BENTONITE CLAY/SOIL CAP 10' BEYOND THE EXCAVATION AS SHOWN.

GRADE NATIVE CLAY TO DRAIN AWAY FROM THE AREA. PLACE 4" OF TOPSOIL, RESEED OR SOD TO STABILIZE. ALL STABILIZATION WORK SHOULD BE DONE UNDER SUPERVISION OF A GEOLOGIST OR ENGINEER FAMILIAR WITH SITE AND FOUNDATION CONDITIONS.

SINKHOLE MITIGATION DETAIL



<u>PLAN VIEW</u> INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS

SHALL BE REQUIRED FOR ALL INSTALLATIONS NOT LOCATED AT A LOW POINT.

ROLLED EARTHEN BERM IN ROADWAY SHALL BE PROVIDED AND MAINTAINED IMMEDIATELY DOWN GRADIENT OF THE PROTECTED INLET UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR TO REMAIN PERMANENTLY.


STONE INLET PROTECTION AND BERM FOR A TYPE M INLET CAN BE USED IN ONE ACRE MAXIMUM DRAINAGE AREA WITH 15 IN. OVERFLOW PIPE AND 4 IN. HEAD. A PERFORATED PLATE WELDED TO A METAL RISER MAY NOT BE SUBSTITUTED FOR THE WIRE MESH. A SLOTTED PLATE WELDED TO THE RISER MAY BE USED IN CONJUNCTION WITH THE WIRE MESH IF CALCULATIONS ARE PROVIDED TO SHOW SUFFICIENT CAPACITY OF THE INLET TO ACCEPT THE PEAK RUNOFF FOR A 2-YEAR STORM EVENT FROM THE TRIBUTARY DRAINAGE AREA. TOP OF PIPE SHALL BE AT LEAST 6 INCHES BELOW ADJACENT ROADWAY IF PONDED WATER WOULD POSE A SAFETY HAZARD TO TRAFFIC. EARTHEN BERM SHALL BE ROLLED.

SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE HEIGHT OF THE STONE. DAMAGED OR CLOGGED INSTALLATIONS SHALL BE REPAIRED OR REPLACED IMMEDIATELY.

FOR SYSTEMS DISCHARGING TO HQ OR EV SURFACE WATER, A 6 IN. THICK COMPOST LAYER SHALL BE SECURELY ANCHORED ON OUTSIDE AND OVER TOP OF STONE. COMPOST SHALL MEET THE STANDARDS IN TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.

NOT TO SCALE

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS. STANDARD CONSTRUCTION DETAIL #4-20 STONE INLET PROTECTION AND BERM - TYPE M INLET



MAXIMUM DRAINAGE AREA = 1/2 ACRE.

INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS.


ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR REMAIN PERMANENTLY.

AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.

INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS. ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS.

### STANDARD CONSTRUCTION DETAIL #4-16 FILTER BAG INLET PROTECTION - TYPE M INLET NOT TO SCALE




FENCING SHALL BE INSTALLED AT THE DRIP LINE (MIN. 5 FEET FROM TREE TRUNK).
BOARDS SHALL NOT BE NAILED TO TREES DURING CONSTRUCTION.

FEEDER ROOTS SHALL NOT BE CUT IN AREA INSIDE THE DRIP LINE THE CONTRACTOR SHALL NOT ENCROACH ONTO AREAS DELINEATED AS TREE PROTECTION. THE STORAGE OF EQUIPMENT OR MATERIALS IN THIS AREA IS STRICTLY FORBIDDEN. THE SILT FENCE ERECTED AT THE TREE PROTECTION LINE SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION PROCESS AND SHALL NOT BE CROSSED. REFER TO PLAN SHEETS FOR LOCATION OF WOODS AND TREES TO REMAIN. ALL TREES TO REMAIN WHICH ARE

ADJACENT TO CONSTRUCTION AREAS SHALL BE PROTECTED IN ACCORDANCE WITH THIS DETAIL.


NO CLEARING, EARTHMOVING, OR CONSTRUCTION SHALL COMMENCE PRIOR TO INSTALLATION OF TREE PROTECTION 7. A 48 INCH HIGH WOODEN OR PLASTIC FENCE WITH POSTS ON 8 FOOT CENTER TO CENTER (MAXIMUM) SHALL BE INSTALLED AROUND EACH EXISTING TREE PRIOR TO START OF CONSTRUCTION (TYPICAL FOR ALL TREES).

TREE PROTECTION/CONSTRUCTION FENCE DETAIL



SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE HEIGHT OF THE FILTERS. IMMEDIATELY UPON STABILIZATION OF EACH CHANNEL, REMOVE ACCUMULATED SEDIMENT, REMOVE ROCK FILTER, AND STABILIZE DISTURBED AREAS.

> STANDARD CONSTRUCTION DETAIL #4-14 ROCK FILTER NOT TO SCALE



—2 IN. x 2 IN. WOODEN STAKES PLACED 10 FT ON CENTER COMPOST FILTER SOCK-FILTÉR MEDIA UNDISTURBED AREA DISTURBED AREA UNDISTURBED AREA

BARRIER NO.	LOCATION	SLOPE %	SLOPE LENGTH ABOVE BARRIER (FT)	SIZE (IN)
CFS-1	SW OF RECREATION CENTER	6	165	12
CFS-2	NW OF RECREATION CENTER	13	205	18
CFS-3	N OF RECREATION CENTER	11	189	18
CFS-4	NE OF RECREATION CENTER	10	185	18
CFS-5	NW OF PROJECT SITE	8	233	18
CFS-6	NW OF SOIL STOCKPILE	9	103	12
CFS-7	N OF PROJECT SITE	7	89	12
CFS-8	NE OF MAIN PROJECT SITE	4	77	12
CFS-9	DOWNSLOPE OF SOIL STOCKPILE	30	20	12
CFS-10	N OF CHANNEL 4	20	31	12
CFS-11	NE OF BASIN	5	96	12
CFS-12	N OF BASIN	7	192	12
CFS-13	N OF BASIN SPILLWAY	4	151	12
CFS-14	N OF CHANNEL 3	7	121	12
CFS-15	W OF CHANNEL 3	8	134	12

PLAN VIEW


	COMPOST	TABI SOCK FABRIC	_E 4.1 _MINIMUM_SPE	CIFICATIONS			
MATERIAL TYPE	3 MIL HDPE	5 MIL HDPE	5 MIL HDPE	MULT-FILAMENT POLYPROPYLENE (MFPP)	HEAVY DUTY MULT-FILAMEN' POLYPROPYLEN (HDMFPP)		
MATERIAL CHARACTERISTICS	PHOTO- DEGRADABLE	PHOTO- DEGRADABLE	BIO- DEGRADABLE	PHOTO— DEGRADABLE	PHOTO- DEGRADABLE		
SOCK DIAMETERS	12" 18"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"		
MESH OPENING	3/8"	3/8"	3/8"	3/8"	1/8"		
TENSILE STRENGTH		26 PSI	26 PSI	44 PSI	202 PSI		
ULTRAVIOLET STABILITY % ORIGINAL STRENGTH (ASTM G-155)	23% AT 1000 HR.	23% AT 1000 HR.		100% AT 1000 HR.	100% AT 1000 HR.		
MINIMUM FUNCTIONAL LONGEVITY	6 MONTHS	9 MONTHS	6 MONTHS	1 YEAR	2 YEARS		
	1	TWO-PL	SYSTEMS				
				HDPE BIAXIAL N			
INNER CO	ONTAINMENT N	ETTING		CONTINUOUSLY WOUND FUSION-WELDED JUNCTURES			
				3/4" MAX. APE			
				SITÉ POLYPROPYL			
OLITED	FILTRATION M	IFSH		_AYER AND NO-W			
OUTER	TILINATION M	ILOI I	MECHANICA	ALLY FUSED VIA N			
COOK FARRIOS COMPOSER OF RURLAR MAY BE II			3/16"APERTURE SIZE USED ON PROJECTS LASTING 6 MONTHS OR LESS				
FILTREXX & JMD	MILOSED OF BI	JALAF MAT BE	USED ON PROC	ECIS LASIING O N	NUNTINO UK LESS		
FILINEAN & JMD			E 4.2				

FILIREXX & JMD						
TABL	TABLE 4.2					
COMPOST STANDARDS						
ORGANIC MATTER CONTENT	25% - 100% (DRY WEIGHT BASIS)					
ORGANIC PORTION	FIBROUS AND ELONGATED					
рН	5.5 - 8.5					
MOISTURE CONTENT	30% - 60%					
PARTICLE SIZE	30% - 50% PASS THROUGH 3/8" SIEVE					
SOLUBLE SALT CONCENTRATION	5.0 dS/m (mmhos/cm) MAXIMUM					

SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1, AS INDICATED. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2. COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA. TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN. COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION. COMPOST FILTER SOCKS SHALL BE REPLACED AFTER THE MINIMUM FUNCTIONAL LONGEVITY, AS INDICATED IN TABLE 4.1, HAS PASSED. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STATES SHALL BE REMOVED. THE MESH SHALL BE CUT OPEN AND REMOVED. THE MULCH CAN BE SPREAD AS A SOIL SUPPLEMENT IN VEGETATED AREAS.





LONGITUDINAL

ANCHOR TRENCH

ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL

CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.

NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

CHANNEL ND.	LOCATION	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *	STAPLE PATTER N
1	SOUTH OF REC. CENTER	1	1.50	10.0	3	Э	NAG-S75/ VEGETATED	D
2	WEST OF BASIN	3	2	19	4	4	NAG-S75/ VEGETATED	D
3	EAST OF BASIN	3	1.25	13	4	4	NAG-S75/ VEGETATED	D

\* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

(LOOKING DOWNSTREAM)

CHANNEL CROSS-SECTION

NOTE: PUMP ANY PONDING WATER ON SITE TO A PUMPED WATER FILTER BAG.


MODIFIED STANDARD CONSTRUCTION DETAIL #6-1 VEGETATED CHANNEL NOT TO SCALE


JOL JAEATION IS PARTNE WNSHIP JTY, PA ∞ EROSION VATER GAF WATER GA


TAL/CRS 8/26/2024 CALE: AS NOTE DRAWN: TAL/DFG P MGR: 1022419.004


COPYRIGHT 2024

SHEET: 22 OF 27










TAL/CRS

P MGR:

CRS






N STORMWATER MANAGEMENT PELLNESS RECREATION CENTER CQUISITIONS PARTNERS, LLC THFIELD TOWNSHIP NROE COUNTY, PA

TAL/CRS 8/26/2024 1"=30' TAL/DFG P MGR: 1022419.004

COPYRIGHT 2024 SHEET: 24 OF 27



ON STORMWATER MANAGEMENT PLA ELLNESS RECREATION CENTER ACQUISITIONS PARTNERS, LLC ITHFIELD TOWNSHIP ONROE COUNTY, PA

TAL/CRS 8/26/2024 1"=30' CRS TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024 SHEET: 25 OF 27


NOTES: 1. EXCAVATE TRENCH BOX AND INSTALL SHORING AS REQUIRED TO COMPLY WITH FEDERAL, STATE, AND LOCAL LAWS AND CODES. IF UNSUITABLE MATERIAL IS FOUND, UNDERCUT AS DIRECTED BY THE ENGINEER AND BACKFILL WITH SUITABLE MATERIAL TO BOTTOM OF BEDDING ELEVATION. S. KEEP EXCAVATINGS DRY AND FREE OF WATER. INTERCEPT AND DIVERT SURFACE DRAINAGE AWAY FROM EXCAVATIONS. DEWATER ANY PRECIPITATION AND SUBSURFACE WATER FROM EXCAVATIONS.

DO NOT ADVANCE TRENCHING OPERATIONS MORE THAN 200 FEET AHEAD OF COMPLETED PIPELINE 5. ALL TRENCHES WITHIN PAVED AREAS SHALL BE BACKFILLED WITH FULL DEPTH PA DOT NO. 2A

(REFER TO NOTE 2)

TYPICAL STORM PIPE TRENCH & BACKFILL

CRIMP AROUND OUTLET END OF PIPE AND SECURE TO PIPE WITH GALVANIZED STEEL WIRE OR OTHER ACCEPTABLE FASTENING METHODS.



EXCAVATION OVER 900 (36") IN DEPTH AND FOR A MAXIMUM WIDTH OF 600 (24") IS PAYABLE AS CLASS 4 EXCAVATION. USE SUBSURFACE DRAIN OUTLETS FOR ALL PIPE UNDERDRAIN AND PAVEMENT BASE DRAINS.

### SUBSURFACE DRAIN OUTLETS

<u>TOP</u>

<u>FRONT</u>

OUTLET STRUCTURE DETAIL

TOP OF GRATE ELEV.: 452.00

2'x4' JUNCTION BOX-

N.T.S. REFER TO PENNDOT RC-30M, LATEST EDITION

-2'x4' JUNCTION BOX

FRAME AND GRATE

TOP OF GRATE ELEV.: 452.00

TOP OF BOX ELEV.: 451.75

TOP OF ORIFICE ELEV.: 451.25

2'x4' JUNCTION BOX-

-INV.: 447.30

5/8" MIN.-

<del>II=!</del> 5/8″ MIN.

└-5/8″ MIN.

└1 1/4" MIN.

1 1/4" MIN¬


PIPE OPENING (OUTSIDE DIAMETER) INSIDE FACE = 25" MAX. OUTSIDE FACE = 26" MAX.

> PIPE OPENING (OUTSIDE DIAMETER) INSIDE FACE = 46" MAX.

> > OUTSIDE FACE = 47" MAX.

### STANDARD INLET BOX

REFER TO PENNDOT RC-46M, LATEST EDITION FOR ADDITIONAL NOTES & REQUIREMENTS



### STRUCTURAL STEEL GRATE BICYCLE SAFE

REFER TO PENNDOT RC-45M & RC-46M, LATEST EDITION

53 3/4" MIN.

SYMMETRICAL AB□UT €

TYPE M FRAME

FERROUS CAST MATERIAL STRUCTURAL STEEL FABRICATION FABRICATION

# POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM)

### PERMIT TERMINATION

UPON PERMANENT STABILIZATION OF THE EARTH DISTURBANCE ACTIVITY UNDER § 102.22(A)(2) (RELATING TO PERMANENT STABILIZATION), AND INSTALLATION OF BMPS IN ACCORDANCE WITH AN APPROVED PLAN PREPARED AND IMPLEMENTED IN ACCORDANCE WITH §\$ 102.4 AND 102.8 (RELATING TO EROSION AND SEDIMENT CONTROL REQUIREMENTS; AND PCSM REQUIREMENTS), THE PERMITTEE OR

CO-PERMITTEE SHALL SUBMIT A NOTICE OF TERMINATION TO THE DEPARTMENT OR CONSERVATION

THE NOTICE OF TERMINATION MUST INCLUDE:

(1) THE FACILITY NAME, ADDRESS AND LOCATION.

(2) THE OPERATOR NAME AND ADDRESS. (3) THE PERMIT NUMBER.

(4) THE REASON FOR PERMIT TERMINATION. (5) IDENTIFICATION OF THE PERSONS WHO HAVE AGREED TO AND WILL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS IN ACCORDANCE WITH § 102.8(M) AND PROOF OF COMPLIANCE WITH  $\S 102.8(M)(2)$ .

PCSM REPORTING AND RECORDKEEPING. THE PCSM PLAN, INSPECTION REPORTS AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE

### CONSERVATION DISTRICT

LICENSED PROFESSIONAL OVERSIGHT OF CRITICAL STAGES. A LICENSED PROFESSIONAL OR A DESIGNEE SHALL BE PRESENT ONSITE AND BE RESPONSIBLE DURING CRITICAL STAGES OF IMPLEMENTATION OF THE APPROVED PCSM PLAN. THE CRITICAL STAGES MAY INCLUDE THE INSTALLATION OF UNDERGROUND TREATMENT OR STORAGE BMPS, STRUCTURALLY ENGINEERED BMPS, OR OTHER BMPS AS DEEMED APPROPRIATE BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.


### FINAL CERTIFICATION.

THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL, WHICH READS AS FOLLOWS: II (NAME) DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA.C.S.A. 🖇 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THE ACCOMPANYING RECORD DRAWINGS ACCURATELY REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTMENT OF

ENVIRONMENTAL PROTECTION AND THAT THE PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSM PLAN, ALL APPROVED PLAN CHANGES AND ACCEPTED CONSTRUCTION

(1) THE PERMITTEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN. (2) THE PERMITTEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPONSIBLE FOR THE

LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS.



A. CONSTRUCT IN ACCORDANCE WITH PUBLICATION 408, SECTIONS 605, 606 AND 714; AND AS MODIFIED HEREIN.

C. PROVIDE STEEL REINFORCEMENT IN ACCORDANCE WITH PUBLICATION 408, SECTION 709, PROVIDE MINIMUM

1'-1/2" BOTTOM BARS

TYPE 'C' INLET IS DESIGNATED FOR INSTALLATION WITH NON-MOUNTABLE CURBS.

3. THE SELECTION OF COMPONENTS TO ACHIEVE A SPECIFIED INLET ASSEMBLY IS THE CONTRACTORS RESPONSIBILITY.

4. USE PRE CAST CONCRETE OR STEEL GRADE ADJUSTMENT RINGS WHEN REQUIRED. (REHABILITATION PROJECTS)

5. FOR WALL REINFORCEMENT, BOTH DIRECTIONS, USE 10"MINIMUM EACH WAY, EACH FACE 6" MAXIMUM SPACING.

7. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED. U.S. CUSTOMARY UNITS IN PARENTHESIS.

6. FOR FOOTING REINFORCEMENT, TOP AND BOTTOM, USE #4 BARS AT 12" CENTER EACH WAY OR 17"/M $^2$  WWF 6"

9. PIPES MAY BE CONNECTED TO DRAINAGE STRUCTURES (PRE CAST INLETS. ETC.) WITH MORTAR OR WATERTIGHT

<del>|- -| 1</del>/2″ MIN.

SECTION D-D

(STRUCTURAL STEEL)

INSIDE DIRECTION

• TYPE 'M' INLET IS DESIGNATED FOR INSTALLATION IN MEDIAN AREAS AND MOUNTABLE CURBS.

1'-1/2" SIDE COVER

2. EACH TYPE OF INLET SHOWN IS SUITED FOR A PARTICULAR SITUATION AS FOLLOWS:

### INFILTRATION BASIN

TYPICAL INFILTRATION BASIN CONSTRUCTION SEQUENCE:

PROTECT INFILTRATION BASIN AREA FROM COMPACTION PRIOR TO INSTALLATION. CONSTRUCTION VEHICLES SHALL NOT DRIVE OVER INFILTRATION BASIN AREA BEFORE,

NOTE: ENGINEER SHALL BE NOTIFIED AND ON-SITE FOR STEPS 4, 5, AND 6.

DURING, OR AFTER CONSTRUCTION, EXCEPT AS NEEDED FOR POLLUTANT REMEDIATION. . INSTALL AND MAINTAIN PROPER EROSION AND SEDIMENT CONTROL MEASURES DURING

CONSTRUCTION TO PREVENT SEDIMENT FROM ENTERING THE INFILTRATION BASIN DURING CONSTRUCTION. PIPES AND INLETS SHALL BE VACUUMED, RATHER THAN FLUSHED INTO

### 3. INSTALL BASIN OUTFLOW PIPES AND STRUCTURES.


- 4. EXCAVATE INFILTRATION BASIN BOTTOM TO AN UNCOMPACTED SUBGRADE FREE FROM DEBRIS AND STONES LARGER THAN 2 INCHES IN ANY DIRECTION. DO NOT COMPACT SUBGRADE. CONSTRUCTION VEHICLES SHALL NOT DRIVE WITHIN THE LIMITS OF THE BASIN BOTTOM (WITHIN 2 VERTICAL FEET OF SUBGRADE ELEVATION), AND EXCAVATION SHALL BE COMPLETED FROM THE SIDES OF THE BASIN. CONSTRUCT BERM IN COMPACTED LIFTS.
- 5. HALT EXCAVATION AND NOTIFY ENGINEER IMMEDIATELY IF EVIDENCE OF SINKHOLE ACTIVITY OR PINNACLES OF CARBONATE BEDROCK ARE ENCOUNTERED IN THE BIO-RETENTION AREA.
- 3. SCARIFY SUBGRADE TO LOOSEN TOP 4—6 INCHES. SPREAD MINIMUM 6 INCHES OF IMPORTED TOPSOIL. SEED AND STABILIZE. ADD BASIN PLANTINGS PER PLANS. STABILIZE BASIN SLOPES WITH EROSION CONTROL MATTING.
- . PROTECT BIO-RETENTION AREAS FROM SEDIMENT AT ALL TIMES DURING CONSTRUCTION. DO NOT REMOVE INLET PROTECTION OR OTHER EROSION AND SEDIMENT CONTROL MEASURES UNTIL SITE IS FULLY STABILIZED.
- WATER SEEDING/GRASS ONCE EVERY TWO DAYS IN THE EARLY MORNING OR EVENING. PROVIDING ONE INCH OF WATER PER WEEK UNTIL 70% UNIFORM GRASS COVER IS ESTABLISHED.

### TYPICAL INFILTRATION BASIN MAINTENANCE:

- CATCH BASINS AND INLETS (UPGRADIENT OF INFILTRATION BASIN) SHOULD BE INSPECTED AND CLEANED AT LEAST TWO TIMES PER YEAR AND AFTER RUNOFF EVENTS.
- 2. THE VEGETATION ALONG THE SURFACE OF THE INFILTRATION BASIN SHOULD BE MAINTAINED IN GOOD CONDITION, AND ANY BARE SPOTS RE-VEGETATED AS SOON AS
- VEHICLES SHOULD NOT BE PARKED OR DRIVEN ON AN INFILTRATION BASIN, AND CARE SHALL BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS. INSPECT THE BASIN AFTER RUNOFF EVENTS AND MAKE SURF THAT RUNOFF DRAINS DOWN WITHIN 72 HOURS. MOSQUITOES SHOULD NOT BE A PROBLEM IF THE WATER DRAINS IN 72 HOURS.MOSQUITOES REQUIRE A CONSIDERABLY LONG BREEDING PERIOD WITH RELATIVELY STATIC WATER LEVELS.
- 5. ALSO INSPECT FOR ACCUMULATION OF SEDIMENT, DAMAGE TO OUTLET CONTROL STRUCTURES, EROSION CONTROL MEASURES, SIGNS OF WATER CONTAMINATION/SPILLS, AND SLOPE STABILITY IN THE BERMS.
- 6. MOW ONLY AS APPROPRIATE FOR VEGETATIVE COVER SPECIES.
- REMOVE ACCUMULATED SEDIMENT FROM BASIN AS REQUIRED. RESTORE ORIGINAL CROSS-SECTION AND INFILTRATION RATE. PROPERLY DISPOSE OF SEDIMENT.

### SOIL RESTORATION NOTES

- 1. BEFORE THE TIME THE COMPOST IS PLACED AND PREFERABLY WHEN EXCAVATION IS COMPLETE. THE SUBSOIL SHALL BE IN A LOOSE, FRIABLE CONDITION TO A DEPTH OF 20 INCHES BELOW FINAL TOPSOIL GRADE AND THERE SHALL BE NO EROSION RILLS OR WASHOUTS IN THE SUBSOIL SURFACE EXCEEDING 3 INCHES IN DEPTH.
- 2. TO ACHIEVE THIS CONDITION, SUB-SOILING, RIPPING, OR SCARIFICATION OF THE SUBSOIL WILL BE REQUIRED. WHEREVER THE SUBSOIL HAS BEEN COMPACTED BY EQUIPMENT OPERATION OR HAS BECOME DRIED OUT AND CRUSTED, AND WHERE NECESSARY TO OBLITERATE EROSION RILLS. SUB—SOILING SHALL BE REQUIRED TO REDUCE SOIL COMPACTION IN ALL AREAS WHERE PLANT ESTABLISHMENT IS PLANNED. SUB—SOILING SHALL BE PERFORMED BY
- THE PRIME OR EXCAVATING CONTRACTOR AND SHALL OCCUR BEFORE COMPOST PLACEMENT. 3. SPREAD 2-3 INCHES OF APPROVED COMPOST ON EXISTING SOIL. TILL ADDED SOIL INTO EXISTING SOIL WITH ROTARY TILLER THAT IS SET TO A DEPTH OF 6 INCHES. ADD AN ADDITIONAL 4 INCHES OF APPROVED COMPOST TO BRING
- 4. AFTER PERMANENT PLANTING/SEEDING, 2-3 INCHES OF COMPOST BLANKET WILL BE APPLIED TO ALL AREAS NOT PROTECTED BY GRASS OR OTHER PLANTS.



COMPACTED TOPSOIL/IN-SITU SOIL WITHIN THE BOTTOM OF THE BMP BOTTOM WILL REQUIRE SOILS RESTORATION, AS FOLLOWS: SOILS RESTORATION SHALL TAKE PLACE ONLY WHEN THE SOIL IS DRY THE SOIL SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES. SOIL SHALL BE SCARIFIED IN A 2-DIRECTIONAL GRID PATTERN. THE SCARIFIED GRID SHALL BE SPACED A MAXIMUM OF 3 FEET APART.

IMMEDIATELY AFTER SCARIFYING IS COMPLETE, ADD AMENDED SOILS AND THEN THE DISTURBED AREAS SHALL BE SEEDED AND MULCHED.

AMENDED SOILS DETAIL

\_1 1/4″ MIN.

└ 1 1/4" MIN.

TYPE M INLET FRAME

REFER TO PENNDOT RC-45M, LATEST EDITION

└-1/2" MIN.

GRATE (STRUCTURAL STEEL SHOWN) (SEE RC-45M)

TYPE M FRAME

4" MIN. — |-

1 1/4" MIN<del>. = |=</del>

1/2" MIN. ++

(CAST IRON SHOWN) (SEE RC-45M)

—GRADE ADJUSTMENT RING (SEE RC−45M)

NOTES:
1. CONSTRUCTION REQUIREMENTS:

D. CLEAR COVER FOR STEEL:

PRE CAST CLASS AA

YIELD STRENGTH OF 400 MPa (60,000 PSI).

WALLS: PRE CAST 1'-1/2

8. PROVIDE WEEP HOLE ON INLET BOXES WHEN REQUIRED

<del>< →</del> 5/8" MIN.

R=1/4" -

SECTION C-C

(FERROUS CAST MATERIAL


INSIDE DIRECTION

\*CORNER CONFIGURATION DETAILS ARE THE FABRICATOR'S RESPONSIBILITY AND ARE APPROVED BY THE INSPECTOR.

RUBBER FLEXIBLE CONNECTORS.

FOOTINGS: PRE CAST 2' TOP BARS

### POST-CONSTRUCTION STORMWATER MANAGEMENT WATER QUALITY CONTROL SEED MIXTURE



### MAINTENANCE PERFORMANC

TASK	FREQUENCY
1. Inspect for sediment accumulation	Annually
2. Remove accumulated sediment	Every 5-10 years
3. Inspect for debris (dead vegetation and trash)	Early spring, fall and after major storms
4. Inspect for bank erosion	Early spring, fall and after major storms
5. Clear debris/repair erosion areas	As needed
6. Rake out dead vegetation	Annually, early spring
7. Inspect and remove invasive plants	Annually - July
8. Mow to a height of 6"	Annually — late fall
9. Inspect during wet weather and compare to as-built plans (by prof. engineer)	Annually
<ol> <li>Adjust/correct as determined by wet weather inspection</li> </ol>	As needed
11. Maintain records on all activities	Annually
12. Conduct emergency inspections by prof. engineer	As needed

MAINTENANCE: THE OWNER WILL MOW THE SWALES AND BASIN AREAS TO WITHIN 6 INCHES HIGH, ONCE A YEAR, IN THE FALL WHEN CONDITIONS PERMIT, THE OWNER SHALL MAINTAIN AND THAT MAY BE DEVELOPING. ANY DAMAGED AREAS SHALL BE REPAIRED IMMEDIATELY. ANY TRASH/DEBRIS SHALL BE REMOVED FROM PLANTINGS. ANNUALLY CHECK FOR INVASIVE PLANT SPECIES AND REMOVE TO ENCOURAGE A NATIVE PLANT SPECIES HABITA'

### STORMWATER BMP CONSTRUCTION NOTES

- SEDIMENT REMOVED FROM BMPs SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS, OR DRAINAGE SWALES AND IMMEDIATELY
- STABILIZED, OR PLACED IN TOPSOIL STOCKPILES. 2. TRASH THAT IS REMOVED FROM ANY OF THE CONTROL DEVICES SHALL BE DISPOSED OF
- AT AN APPROVED MUNICIPAL DISPOSAL AREA. ALL CATCH BASINS AND INLETS SHOULD BE INSPECTED AND CLEANED AT LEAST 2 TIMES

### CRITICAL STAGES OF PCSM IMPLEMENTATION

CRITICAL STAGES OF POST-CONSTRUCTION STORMWATER MANAGEMENT PLAN (PCSM) IMPLEMENTATION SHOULD BE OBSERVED AND/OR INSPECTED BY A LICENSED PROFESSIONAL OR DESIGNEE. THESE CRITICAL STAGES INCLUDE THE CONSTRUCTION OF CRITICAL BMPS AND ANY OTHER ACTIVITIES AS MAY BE REQUIRED BY THE DEP OR CONSERVATION DISTRICT. THESE CRITICAL BMPS INCLUDE:

- CONSTRUCTION OF INFILTRATION BASIN
- INSTALLATION OF AMENDED SOILS VERIFY TRIBUTARY AREAS
- A LICENSED PROFESSIONAL QUALIFIED TO OBSERVE AND INSPECT THE ABOVE SHOULD BE CONTACTED AT LEAST THREE (3) DAYS PRIOR TO EXECUTION OF ANY CRITICAL STAGES.

# CONSTRUCTION, OWNERSHIP, OPERATIONS, & MAINTENANCE

POST CONSTRUCTION BEST MANAGEMENT PRACTICES (BMP) AS PROPOSED HEREON, SHALL BE OWNED, OPERATED, AND MAINTAINED AS FOLLOWS:

LANCE PULSE, FACILITY DIRECTOR P.O. BOX 244 DELAWARE WATERGAP, PA. 18327 LPULSE@WATERGAPWELLNESS.COM

570-269-8977

OPERATIONS AND MAINTENANCE RESPONSIBILITIES SHALL BE TRANSFERRED TO ANY SUBSEQUENT OWNER(S). UPON TRANSFERENCE, PARTY CURRENTLY RESPONSIBLE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS PART OF THIS APPROVED PCSM PLAN TO

BMPS, AS PROPOSED, SHALL BE OPERATED & MAINTAINED IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS AND IN ACCORDANCE WITH THE FOLLOWING SPECIFICATIONS:

### PCSM LONG TERM OPERATIONS AND MAINTENANCE REQUIREMENTS UNTIL THE PERMITTEE OR CO-PERMITTEE HAS RECEIVED WRITTEN APPROVAL OF A NOTICE OF

TERMINATION, THE PERMITTEE OR CO-PERMITTEE WILL REMAIN RESPONSIBLE FOR COMPLIANCE WITH THE PERMIT TERMS AND CONDITIONS INCLUDING LONG-TERM OPERATION AND MAINTENANCE OF ALL PCSM BMPS ON THE PROJECT SITE AND IS RESPONSIBLE FOR VIOLATIONS OCCURRING ON THE PROJECT SITE. THE DEPARTMENT OR CONSERVATION DISTRICT WILL CONDUCT A FINAL INSPECTION AND APPROVE OR DENY THE NOTICE OF TERMINATION WITHIN 30 DAYS.

THE PERMITTEE OR CO-PERMITTEE SHALL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS UNLESS A DIFFERENT PERSON IS IDENTIFIED IN THE NOTICE OF TERMINATION AND HAS AGREED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM

FOR ANY PROPERTY CONTAINING A PCSM BMP, THE PERMITTEE OR CO-PERMITTEE SHALL RECORD AN INSTRUMENT WITH THE RECORDER OF DEEDS WHICH WILL ASSURE DISCLOSURE OF THE PCSM BMP AND THE RELATED OBLIGATIONS IN THE ORDINARY COURSE OF A TITLE SEARCH OF THE SUBJECT PROPERTY. THE RECORDED INSTRUMENT MUST IDENTIFY THE PCSM BMP. PROVIDE FOR NECESSARY ACCESS RELATED TO LONG-TERM OPERATION AND MAINTENANCE FOR PCSM BMPS AND PROVIDE NOTICE THAT THE RESPONSIBILITY FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP IS A COVENANT THAT RUNS WITH THE LAND THAT IS BINDING UPON AND ENFORCEABLE BY SUBSEQUENT GRANTEES, AND PROVIDE PROOF OF FILING WITH THE NOTICE OF TERMINATION UNDER § 102.7(B)(5) (RELATING TO PERMIT TERMINATION

THE PERSON RESPONSIBLE FOR PERFORMING LONG-TERM OPERATION AND MAINTENANCE MAY ENTER INTO AN AGREEMENT WITH ANOTHER PERSON INCLUDING A CONSERVATION DISTRIC NONPROFIT ORGANIZATION. MUNICIPALITY. AUTHORITY. PRIVATE CORPORATION OR OTHER PERSON, TO TRANSFER THE RESPONSIBILITY FOR PCSM BMPS OR TO PERFORM LONG-TERM OPERATION AND MAINTENANCE AND PROVIDE NOTICE THEREOF TO THE DEPARTMENT.

A PERMITTEE OR CO-PERMITTEE THAT FAILS TO TRANSFER LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP OR OTHERWISE FAILS TO COMPLY WITH THIS REQUIREMENT SHALL REMAIN JOINTLY AND SEVERALLY RESPONSIBLE WITH THE LANDOWNER FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS LOCATED ON THE PROPERTY.


### CLEAN FILL NOTES

- 1. IF THE SITE WILL NEED TO IMPORT OR EXPORT MATERIAL FROM THE SITE. THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND DÉTERMINATION OF CLEAN FILL WILL REST WITH (CONTRACTOR).
- 2. CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED
- S. CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE STILL QUALIFIES AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- 4. ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS.
- 5. ENVIRONMENTAL DUE DILIGENCE: THE APPLICANT MUST PERFORM ENVIRONMENTAL DUE DILIGENCE TO DETERMINE IF THE FILL MATERIALS ASSOCIATED WITH THE PROJECT QUALIFY AS CLEAN FILL. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- 6. FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT. WHICHEVER IS APPLICABLE. THESE REGULATIONS ARE AVAILABLE ON-LINE AT WWW.PACODE.COM.

### RECYCLING OR DISPOSAL OF MATERIALS

RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THIS PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH PA DEP RULES AND REGULATIONS. SEDIMENT REMOVED FROM BMPS AND STORMWATER FACILITIES SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED OR PLACED IN TOPSOIL STOCKPILES. ON-GOING PROJECT WASTES INCLUDE, BUT MAY NOT BE LIMITED TO, THE FOLLOWING:

- SEDIMENT TRASH/DEBRIS
- VEGETATION CLIPPINGS AS MAY RESULT FROM MAINTENANCE



Str 27.

TION STORMWATER MANAGEMENT D

WELLNESS RECREATION CENTE


AP ACQUISITIONS PARTNERS, LLC

SMITHFIELD TOWNSHIP

MONROE COUNTY, PA CONSTRUCTION S WATER GAP WEL

TAL/CRS 8/26/2024 CALE AS NOTE CRS RAWN: TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024

SHEET: 26 OF 27





272.200.2050

ME. CONSTRUCTION STORMWATER MANAGEMENT DEWATER GAP WELLNESS RECREATION CENTER WATER GAP ACQUISITIONS PARTNERS, LLCSAMITHFIELD TOWNSHIPMONROE COUNTY, PA

TAL/CRS 8/26/2024 CRS AS NOTED TAL/DFG P MGR: 1022419.004 COPYRIGHT 2024

SHEET: 27 OF 27 PCD-2